MOL GROUP INTEGRATED ANNUAL REPORT

2024

SUSTAINABILITY STATEMENT

CONTENT OF THIS REPORT

ESRS 2 ..... **141**
GENERAL BASIS FOR PREPARATION OF THE SUSTAINABILITY STATEMENT 141
DISCLOSURES IN RELATION TO SPECIFIC CIRCUMSTANCES 141
OVERSIGHT ON SUSTAINABILITY-RELATED ISSUES 142
STAKEHOLDER ENGAGEMENT 144
DESCRIPTION OF THE PROCESS TO IDENTIFY AND ASSESS MATERIAL IMPACTS, RISKS, AND OPPORTUNITIES 144
SUMMARY OF MOL GROUP'S DOUBLE MATERIALITY ASSESSMENT RESULTS 148
ESRS ENVIRONMENT **159**
CLIMATE CHANGE 159
TRANSITION PLAN AND TARGETS RELATED TO CLIMATE CHANGE 159
ACTIONS RELATED TO CLIMATE CHANGE 162
IMPACTS, RISKS AND OPPORTUNITIES RELATED TO CLIMATE CHANGE 165
POLICIES RELATED TO CLIMATE CHANGE MITIGATION AND ADAPTATION 170
METRICS RELATED TO ENERGY CONSUMPTION AND MIX 174
METRICS RELATED TO GHG EMISSIONS 174
INTERNAL CARBON PRICING 179
EU TAXONOMY REPORT **180**
Introduction and legal background 180
General approach 180
Eligibility screening 180
Alignment screening 180
Technical Screening Criteria (TSC) monitoring 180
Do no significant harm (DNSH) screening 181
Minimum social safeguards (MSS) assessment 181
Financial methodology 182
KPI related to turnover (turnover KPI) 182
KPI related to operating expenditure (OpEx KPI) 182
KPI related to capital expenditure (CapEx KPI) 183
Contextual information about the KPIs 183
Turnover 183
Operating expenditure (OpEx) 186
Capital expenditure (CapEx) 188
Complementary Delegated Act 190
POLLUTION 193
IMPACTS AND RISKS RELATED TO POLLUTION 193
POLICIES RELATED TO POLLUTION 194
ACTIONS AND RESOURCES RELATED TO POLLUTION 195
TARGETS RELATED TO POLLUTION 196
METRICS RELATED TO AIR, WATER AND SOIL POLLUTION 197
INFORMATION ON SUBSTANCES OF CONCERN & SUBSTANCES OF VERY HIGH CONCERN 199

WATER STEWARDSHIP 200
IDENTIFIED WATER-RELATED IMPACTS 200
POLICIES RELATED TO WATER USE 201
ACTIONS RELATED WATER USE 201
TARGETS RELATED TO WATER 202
METRICS RELATED TO WATER USE 202
BIODIVERSITY 204
IMPACTS, RISK AND OPPORTUNITIES RELATED TO BIODIVERSITY 204
POLICIES RELATED TO BIODIVERSITY AND ECOSYSTEMS 205
ACTIONS RELATED TO BIODIVERSITY AND ECOSYSTEMS 206
TARGETS RELATED TO BIODIVERSITY AND ECOSYSTEMS 206
METRICS RELATED TO BIODIVERSITY AND ECOSYSTEMS 206
RESOURCE USE AND CIRCULAR ECONOMY 207
SUB-CHAPTER A: MANAGEMENT OF IMPACTS AND RISKS RELATED TO OWN WASTE GENERATION AND TREATMENT 208
IDENTIFIED IMPACTS AND RISKS RELATED TO OWN WASTE GENERATION AND TREATMENT 208
POLICIES RELATED TO WASTE GENERATION AND TREATMENT 209
ACTIONS RELATED TO WASTE GENERATION AND TREATMENT 210
TARGETS RELATED TO WASTE GENERATION AND TREATMENT 210
METRICS RELATED TO WASTE GENERATION AND TREATMENT 210
SUB-CHAPTER B: CIRCULAR ECONOMY & RESOURCE USE IN THE DOWNSTREAM SEGMENT 214
IDENTIFIED RISKS AND OPPORTUNITIES RELATED TO CIRCULAR ECONOMY & RESOURCE USE IN THE DOWNSTREAM SEGMENT ... 214
POLICIES RELATED TO RESOURCE USE 216
ACTIONS RELATED TO RESOURCE USE 217
METRICS RELATED TO RESOURCE IN- AND OUTFLOWS OF THE DOWNSTREAM BUSINESS SEGMENT 218
SUB-CHAPTER C: MANAGEMENT OF IMPACTS, RISKS AND OPPORTUNITIES RELATED TO CIRCULAR ECONOMY SERVICES 219
IDENTIFIED IMPACTS, RISKS AND OPPORTUNITIES RELATED TO CIRCULAR ECONOMY SERVICES 219
POLICIES RELATED TO CIRCULAR ECONOMY SERVICES 221
ACTIONS AND RESOURCES RELATED TO CIRCULAR ECONOMY SERVICES 222
TARGETS RELATED TO THE CIRCULAR ECONOMY SERVICES BUSINESS SEGMENT 224
METRICS RELATED TO RESOURCE IN- AND OUTFLOWS OF THE CIRCULAR ECONOMY SERVICES BUSINESS SEGMENT 225
EXCLUDED DISCLOSURE REQUIREMENTS FROM ENVIRONMENTAL STANDARDS: 227
DISCLOSURES ON SOCIAL STANDARDS 228
WORKFORCE 228
SUB-CHAPTER A: HUMAN RESOURCE MANAGEMENT 229
IDENTIFIED IMPACTS AND RISKS RELATED TO HUMAN RESOURCE MANAGEMENT 229
POLICIES & ENGAGEMENT RELATED TO OWN WORKFORCE 230
ACTIONS RELATED TO HUMAN RESOURCES 232
TARGETS RELATED TO HUMAN RESOURCES 234
METRICS RELATED TO COLLECTIVE BARGAINING COVERAGE AND SOCIAL DIALOGUE 235
ADEQUATE WAGES 235
SUB-CHAPTER B: WORKER HEALTH AND SAFETY MANAGEMENT 235
IDENTIFIED IMPACTS AND RISKS RELATED TO OCCUPATION HEALTH & SAFETY 235

POLICIES RELATED TO HEALTH, SAFETY AND SECURITY OF WORKERS 238
ENGAGEMENT RELATED TO HEALTH, SAFETY AND SECURITY OF WORKERS 243
ACTIONS AND RESOURCES RELATED TO OCCUPATIONAL HEALTH & SAFETY 244
TARGETS RELATED TO HEALTH & SAFETY 248
METRICS RELATED TO HEALTH AND SAFETY 248
SUB-CHAPTER C: ETHICS 251
IDENTIFIED IMPACT RELATED TO DIVERSITY AND INCLUSION 251
POLICIES, ENGAGEMENT AND GRIEVANCES RELATED TO DIVERSITY AND INCLUSION 251
POLICIES RELATED TO GRIEVANCES AND REMEDIATION 254
ACTIONS RELATED TO DIVERSITY AND INCLUSION 255
TARGETS RELATED TO DIVERSITY AND INCLUSION 256
METRICS RELATED TO CHARACTERISTICS OF EMPLOYEES 257
METRICS RELATED TO DIVERSITY AND INCLUSION 257
METRICS RELATED TO REMUNERATION (PAY GAP AND TOTAL REMUNERATION) 258
METRICS RELATED TO INCIDENTS AND COMPLAINTS RELATED A FAIR, ETHICAL, INCLUSIVE WORK ENVIRONMENT 258
AFFECTED COMMUNITIES 259
SUB-CHAPTER A: MANAGING IMPACTS AND RISKS RELATED TO LOCAL COMMUNITIES 259
IMPACTS AND RISKS RELATED TO AFFECTED LOCAL COMMUNITIES 259
POLICIES RELATED TO AFFECTED LOCAL COMMUNITIES 260
ACTIONS TO MANAGE IMPACTS AND RISKS RELATED TO AFFECTED LOCAL COMMUNITIES 262
TARGETS RELATED TO AFFECTED LOCAL COMMUNITIES 264
SUB-CHAPTER B: SHARED WEALTH & ECONOMIC IMPACT 264
IMPACTS RELATED TO SHARED WEALTH & ECONOMIC IMPACT 264
POLICIES RELATED TO SHARED WEALTH & ECONOMIC IMPACT 265
ACTIONS RELATED TO SHARED WEALTH & ECONOMIC IMPACT 266
TARGETS RELATED TO SHARED WEALTH & ECONOMIC IMPACT 267
CONSUMERS AND END-USERS 267
IMPACTS AND OPPORTUNITIES RELATED TO CONSUMERS 267
POLICIES RELATED TO CONSUMERS AND END-USERS 269
ACTIONS RELATED TO CONSUMERS AND END-USERS 270
EXCLUDED DISCLOSURE REQUIREMENTS FROM SOCIAL STANDARDS 272
DISCLOSURES ON GOVERNANCE STANDARDS 273
SUB-CHAPTER A: BUSINESS CONDUCT 273
IMPACTS, RISKS & OPPORTUNITIES RELATED TO BUSINESS CONDUCT 273
POLICIES RELATED TO BUSINESS CONDUCT 274
INCIDENTS OF CORRUPTION OR BRIBERY 275
POLITICAL INFLUENCE AND LOBBYING ACTIVITIES 276
SUB-CHAPTER B: SUPPLY CHAIN MANAGEMENT 278
IMPACTS ON SUPPLIERS 278
POLICIES RELATED TO RELATIONSHIPS WITH SUPPLIERS 278
METRICS RELATED TO PAYMENT PRACTICES 279
SUB-CHAPTER C: DATA PROTECTION & CYBER SECURITY 280

IMPACTS AND RISKS RELATED TO DATA PROTECTION AND CYBER SECURITY ON SUPPLIERS....280
POLICIES ON DATA PROTECTION & CYBER SECURITY....280
ACTIONS RELATED TO DATA PROTECTION & CYBER SECURITY....282
TARGETS AND METRICS RELATED TO CYBER SECURITY....282
EXCLUDED DISCLOSURES....283
APPENDIX I: INDICATORS UNDER REASONABLE ASSURANCE....**284**
APPENDIX II: MANAGEMENT SYSTEM & POLICIES....**285**
ASSURANCE STATEMENT....**293**

ESRS 2

GENERAL BASIS FOR PREPARATION OF THE SUSTAINABILITY STATEMENT

/BP-1/

The sustainability statement is prepared in accordance with the European Sustainability Reporting Standards (ESRS). The scope of consolidation of consolidated sustainability statement is same as for financial statements. MOL Group relies on internal policies, materiality and risk assessments to determine whether data collection processes should be set up at subsidiaries. Metrics related to own workforce (S1) are collected at subsidiaries where headcount is above 100. Ethics-related metrics are collected at subsidiaries where an Ethics Officer is appointed, which is mandatory for every subsidiary with above 50 FTE. Regarding environmental, energy, occupational health and safety and process safety metrics, the Group HSE MS allows for a three-year integration period of newly acquired or established subsidiaries in order to set up the policies and data collection processes. Beside the integration period, the materiality of subsidiaries is assessed yearly for all the aforementioned topics. If a subsidiary under integration is expected to be material, it is listed in footnotes of the relevant metrics. MOL Group's double materiality assessment, and thus its sustainability statement, also covers the Group's upstream and downstream value chain and relevant policies, actions, targets and metrics are reported accordingly.

We are committed to continuously improving our sustainability reporting processes and addressing these limitations in future reports to provide more comprehensive and reliable information to our stakeholders.

In preparing this sustainability statement, MOL Group acknowledges certain inherent limitations due to the initial reporting under the Corporate Sustainability Reporting Directive (CSRD). Consequently, comparisons over time may be constrained as frameworks for sustainability reporting are continuously evolving. The data collection processes and methodologies for certain sustainability metrics are still being refined. As such, some data points may be subject to estimation and may not capture all aspects of performance accurately. Any future changes in structure or operations may impact the reported sustainability metrics. The sustainability impacts reported herein are influenced by external factors such as regulatory changes, market conditions, and technological advancements, which may affect the outcomes of our sustainability initiatives.

Section 134/J of the Accounting Act requires the Company to prepare its consolidated annual report in the electronic reporting format (XHTML) as defined in the Commission Delegated Regulation (EU) 2019/815 (ESEF Regulation) and to indicate the sustainability disclosures defined by the ESEF taxonomy in the consolidated sustainability report using the XBRL markup language, including the disclosures required by Article 8 of Regulation (EU) 2020/852. Given that the ESEF taxonomy for sustainability reporting has not yet been adopted, the Company has not been able to perform the XBRL markup.

Assurance

Deloitte provided limited assurance over the sustainability statement and reasonable assurance over two selected KPIs: Scope 1 CO_2 emissions under ETS and TRIR. Please see the auditor's assurance reports.

DISCLOSURES IN RELATION TO SPECIFIC CIRCUMSTANCES

/BP-2/

Changes in preparation or presentation of sustainability information

From this year, MOL Group includes FGSZ Zrt. in the consolidated Group-level metrics. Due to the unbundled nature of the Midstream company, FGSZ Zrt. was not included in the Group's previous sustainability reports. Since FGSZ Zrt. is a financially fully consolidated subsidiary of MOL Plc., the company is included in the sustainability statement. When inclusion of FGSZ Zrt. was not possible because of differences in calculation methodologies and data collection processes, it is mentioned in the footnotes. Overall, it does not materially affect the conclusions of this report.

Incorporation by reference

The placement of ESRS 2 disclosure requirements in the management report can be found in the section 'List of Disclosure Requirements complied with in preparing the sustainability statement' of this chapter.

Estimations and outcome uncertainty (including value chain estimation)

Some data points require the use of estimations until more reliable direct measurement processes are introduced at the Group-level. For Scope 3 emissions, MOL Group uses activity data and emission factors to calculate emissions where it is not feasible to collect supplier-specific data. In case of the disaggregation of energy consumption and production, MOL Group has to extrapolate on existing reliable data.

Restatements

2023 water discharge figures were restated due to a miscalculation in connection with water discharge with no treatment in INA d.d.

OVERSIGHT ON SUSTAINABILITY-RELATED ISSUES

/GOV-1, GOV-2/

Role of Administrative and Supervisory bodies

General description of MOL Group's governance structure is available in the Corporate Governance Declaration. The Financial Risk Committee (FRC) and the Sustainable Development Committee (SDC) oversee impacts, risks, and opportunities at MOL Group. The SDC approves the Double Materiality Assessment, while the FRC monitors financial and operational risks, including the ERM system. The SDC ensures that management systems and rules of procedures are in place and applied to achieve MOL Group's sustainability goals. Members of the Supervisory Body also attend FRC and SDC meeting, providing oversight of their activities. The roles and responsibilities of Committees are regulated by the Charter of the Committees operated by the Board of Directors of MOL Plc., available on the company's website.

Role of management

Executive management at MOL Group assesses and manages climate-related risks across various roles, including Group Strategy, Chief Economist, Public and EU Regulatory Affairs, HSE department, and Investor Relations. The Board of Directors defines business objectives and reviews strategies based on climate-related risks, receiving regular updates from senior management.

Reporting lines, controls and procedures

The Board of Directors communicates through the Chairman-CEO, who implements resolutions and reports on company affairs. The Board receives updates on strategic issues, capital market developments, and evaluates business unit performance. Additionally, the Board of Directors, committees, and Board members are entitled to request information or opinions from any unit or employee of the company, provided they inform the Chairman-CEO simultaneously.

The Board regularly reports to the Supervisory Board on management, financial situation, and business policy. In addition to the reports from the Board of Directors, Senior Management, and the Audit Committee, the Supervisory Board receives briefings from Internal Audit and detailed information on the functioning of major business areas such as Strategy and Business Development, Investor Relations, Corporate Relations and Regulatory Affairs, Human Resources, Group Compliance and Ethics, Group Security, and Cybersecurity.

Governance is carried out through the Chief Executives' Committee (CEC) and the Management Committee (MC). The CEC adopts strategic decisions, while the MC links the CEC with the company's work organization. Internal Audit evaluates financial, operational, and control activities, reporting to the Finance and Risk Management Committee, Audit Committee, and Supervisory Board.

Setting of targets and monitoring of progress

The Board of Directors defines business objectives and reviews the Group's strategy, integrating climate-related risks. The Board and its committees monitor progress against goals and targets, receiving regular updates on sustainability-related issues.

The Sustainable Development Committee (SDC) and the Finance and Risk Management Committee (FRC) handle climate-related responsibilities. The SDC monitors progress against sustainability goals, with regular reports from the Group Vice President of Health, Safety & Environment and the Head of Investor Relations & ESG Coordination. The Board of Directors and SDC receive sustainability-related topics during meetings.

Sustainability-related expertise

The Board of Directors (BoD), and the Sustainable Development Committee of the BoD receive a wide range of sustainability related topics, either as reports or proposals during each meeting (typically 6 and 4 meeting per year respectively). MOL Group publishes each year the

agenda of each Board of Director Meeting: The main measures for developing and enhancing the highest governance body's (BoD) collective knowledge of economic, environmental, and social topics are the discussed agenda points at BoD meetings, where each of these main topics are regularly covered.

Diversity of the Supervisory Board and Board of Directors

	UNIT OF MEASURE	2024	2023	ESRS
Supervisory Board and Board of Directors by gender				ESRS 2 – GOV-1
Male	%	95.5	95.5	ESRS 2 – GOV-1
Female	%	4.5	4.5	ESRS 2 – GOV-1
Supervisory Board and Board of Directors by citizenship				ESRS 2 – GOV-1
Hungarian	%	82.0	82.0	ESRS 2 – GOV-1
Slovak	%	9.0	9.0	ESRS 2 – GOV-1
Croatian	%	0.0	0.0	ESRS 2 – GOV-1
Omani	%	4.5	4.5	ESRS 2 – GOV-1
Czech	%	4.5	4.5	ESRS 2 – GOV-1
Supervisory Board and Board of Directors by age groups				ESRS 2 – GOV-1
Below 30 years of age	%	0.0	0.0	ESRS 2 – GOV-1
Between 30-50 years of age	%	18.2	18.2	ESRS 2 – GOV-1
Over 50 years of age	%	81.8	81.8	ESRS 2 – GOV-1

STAKEHOLDER ENGAGEMENT

/SBM-2, SBM-3/

Groups of stakeholders MOL Group regularly engages with can be obtained from the Stakeholder Engagement section of our website, which include, but are not limited to Shareholders, Employees, Customers, Suppliers, Professional associations, Local communities and authorities. On top of the regular engagement activities conducted by specialised functional departments and business owners within MOL Group, during the autumn of 2023 the ESG Coordination department did a broad internal and external stakeholder engagement with the specific aim to gather information to support our materiality assessment:

- Internal stakeholders were selected to represent both MOL Group's corporate structure (Downstream, Upstream, Consumer Services and Corporate Functions) and geographic structure (Group-level divisions, Mol Hungary, Slovnaft and INA). To assess the Group's impact on external stakeholders, we shortlisted stakeholders including investors & financial analysts, creditors and banks, affected communities, regulators and non-governmental organisations.
- We reached out to our stakeholders by sending them tailored questionnaires, and we conducted in-depth interviews to gather insightful details shared by high-priority stakeholders. Overall, we have registered over 75 samples to our assessment.
- The results were consolidated by using weighting each stakeholder type equally to sufficiently represent all stakeholders. Findings of this exercise as a foundation for our Double Materiality Assessment ensure the continuity of our previous, GRI-based materiality assessment methodology.

The views and expectations of key stakeholders also informed MOL Group's Shape Tomorrow Strategy which includes sustainability-related targets as well. The targets are disclosed in this report in their respective topical chapters.

DESCRIPTION OF THE PROCESS TO IDENTIFY AND ASSESS MATERIAL IMPACTS, RISKS, AND OPPORTUNITIES

/ESRS 2. IRO-1/

ESRS	Disclosure Requirement IRO-1 Disclosure Requirement SBM-2
GRI	GRI 2-14 GRI 2-29 GRI 3-1
IFRS	IFRS S2.25(a)(v) IFRS S2.25(b) IFRS S2.25(a)(iii) IFRS S2.25(a)(iv) IFRS S2.25(c) IFRS S2.25(a)(i) IFRS S2.25(a)(vi)

Double materiality assessment

In 2024, MOL Group introduced a new Double Materiality Assessment (hereinafter: DMA) methodology to comply with CSRD requirements and following the Materiality Assessment Implementation Guidance published by EFRAG. Whilst the bottom-line of the exercise remained to determine the relevant content for MOL Group's Sustainability Report, a key focus of the approach shifted from assessing the importance

of certain sustainability topics, to identification of the material impacts on people and the environment; and financial risks and opportunities related to sustainability matters (hereinafter: IROs).

Identification of impacts

Since risks and opportunities generally derive from impacts & dependencies of the company, first step the DMA was the identification of impacts on people and the environment. Building on the results of our established survey-based stakeholder engagement results, analysis of findings from due diligence processes, peer and sector studies, and deep-dive workshops with all relevant internal subject matter experts & leaders related to sustainability matters, we concluded a list of impacts rated by severity (based on the scale, scope and irremediable character of negative impacts and the scale and scope of positive impacts), likelihood and time-horizons.

Table: Scale

	Positive impacts	Negative impacts
Negligible	Scale of the impact is not as significant that would justify inclusion in the Group-level Sustainability Report.	Scale of the impact is not significant, and / or can easily be remediated.
Moderate	The company's activities generate noticeable positive effects on individuals, communities, or the environment, such as improved working or living conditions, or enhanced ecological balance. While these benefits are tangible, they do not represent a fundamental shift in social or environmental well-being.	Scale of the impact is noticeable on the people and environment, but with appropriate mitigation and/or remediation actions grievances are unlikely to be received.
Significant	The company's activities have significant positive impact on individuals or groups that contributes to better living standards or improved conditions, or have a positive impact on the state of environment or availability of natural resources.	The company's activities have negatively impact on individuals, groups of people or on the environment, to the degree that mitigation actions are crucial to avoid or address grievances; or there is potential for irremediability.

Table: Likelihood

	Positive impacts	Negative impacts
Very low	Positive impact is unlikely to reach material level	Unlikely that impact will have material consequences, but precaution is necessary
Low	No / very few cases when positive impact have been present to a material degree.	No / very rare occasions of impact in the past, but constant monitoring is necessary
Medium	Positive impact can materialise, but not as a consequence of regular activities of the company	There has been past events where such impact happened, but actions are in place to manage negative / enhance positive impacts.
High	Positive impact often materialised, but during but not strictly connected to regular activities of the company	Impact is very likely to occur (e.g., in the macro environment), but not part of business as usual
Actual	Positive impact is present as direct consequence of regular company actions or operations	Negative impact is present during regular operations (business as usual)

Table: Scope

Local	Impact is only noticeable in a limited area, e.g. in the proximity of the site.
Territorial	The impact not only have affects in the close proximity of the site where the impact originates, but potentially also affect people or environment of the region.
Country level	Impact is notable or significant in a given country, but does not have significant cross-border implications.
CEE	Impact is noticeable in multiple countries of Central-Easter Europe, where the company operates.
Global	The impact is not limited or connected to a given geographical area.

Table: Time horizons

Short-term	Until the end of the upcoming next reporting period (2025 for current report)
Medium-term	Between 1 and 5 years (2026-2029 for current report)
Long-term	Over years (2030 and later for current report)

Identification of risks

To assess and identify risks related to sustainability matters, the starting point was MOL Group's regular Enterprise Risk Management (hereinafter: ERM) process, which follows the step laid down in the GROUP RISK MANAGEMENT POLICY. This process takes a bottom-up approach, where Risk Owners and Risk Sponsors list all relevant risks related to the business or functional units in their domain. To increase their awareness on ESG topics, the Group Risk Management and Group ESG Coordination organised workshops and shared support materials with relevant Risk Owners and Risk Sponsors to ensure that appropriate consideration were given to the environment, social and governance related risks stemming from dependencies, and identified impacts on people and the environment. From the concluded complete risk register, risks related to sustainability matters have been selected and used to determine the Group-level ESG risks. For each ESG risk, a likelihood and financial effect were determined based on the consolidation of individual risks provided by different business segments and Subject Matter Experts. When assessing the financial effect, resources allocated to mitigate related risks, and where applicable, expected decrease in EBIDTA were taken into account.

Table: – Financial effect of risks

Magnitude of financial effect	Environmental risks (Quantitative assessment)	Social and Governance risks (Qualitative assessment)
Low	Cost of mitigations actions and/or associated EBIDTA loss is unlikely to exceed the threshold of USD 20 million per year in any time horizon on Group level.	Cost of mitigations actions and/or associated EBIDTA loss associated with the risk is unlikely to have financial implications notable to users of the company's statements.
Medium	Resources allocated to mitigations actions and/or associated EBIDTA loss are likely to exceed this USD 20 million per year threshold, but unlikely to exceed USD 50 million in any year before 2030 on Group level.	Cost of mitigations actions and/or associated EBIDTA loss associated with the risk have a potential to be of the interest of the users of the company's statements, but is unlikely to imply notable changes in the business model of the company.
High	MOL Group's business planning processes allocated to mitigation actions, and/or associated EBIDTA loss is very likely to exceed USD 50 million in any year before 2030	The actual or potential cost associated mitigations actions and/or potential EBIDTA loss imply the need for strategic investments or noticeable actions on Group level.

Note: This categorisation regarding the materiality of risks different from those applied for during the Group level ERM in two aspects:

1. Firstly, ERM takes deviation in cash-flow or in EBITDA (asset damage, loss in production, lost revenue, etc.) into consideration; whilst for the financial materiality assessment of sustainability topics relevant under CSRD, the basis of financial materiality is the resources allocated to mitigate related risks and negative impacts on people or the environment, plus in cases where applicable the deviation in EBITDA (positive for opportunities, negative for risks) have been considered.
2. Secondly, the in case of the ERM, USD 20 mn financial impact on the mid-term on Group level is considered the reporting threshold, and USD 50 mn for the materiality threshold. In order to follow the requirements of CSRD, the categorisation of financial magnitude is aligned with to the materiality threshold.

Level of likelihood of risks was determined on the categories below, following the Group-level ERM requirements:

Table. Likelihood of risks

Very low	Is rare/very unlikely to occur within the foreseeable future
Low	Is unlikely to occur within the foreseeable future
Moderate	May occur within the foreseeable future
High	Is likely to occur within the foreseeable future
Very high	Is almost certain to occur within the foreseeable future

Identification of opportunities

The starting point for the identification of opportunities for the DMA was MOL Group's Shape Tomorrow Strategy, which revised in 2024, and additional insights of management of key business units they provided during the aforementioned workshops during the ERM process. The opportunities have been classified based on the two aspects: Maturity at MOL Group and expected magnitude of increased EBIDTA and/or the amount associated of associated investments.

Table. – Maturity of opportunities

General opportunity	The company considers investing in the opportunity on the medium or long term, but currently no activities.

Assessed/ planned	The company is preparing to invest in the opportunity on the short or medium, but currently no significant activities.
Pilot	The company has investments and in the opportunity and prepared for the ramp-up in the short or medium term, but the scale of the projects is currently not significant.
Implemented at scale	The company has mature investments related to the matter and actively engaged in the ramp-up.

Table. – Financial effects of opportunities

Low	Planned or actual CAPEX and/or associated EBIDTA currently does not to exceed the threshold of USD 20 million per year.
Medium	Planned or actual CAPEX and/or associated EBIDTA likely to exceed the USD 20 million per year threshold, but unlikely to exceed USD 50 million in any year before 2030 on Group level.
High	Planned or actual CAPEX and/or associated EBIDTA exceeds, or very likely to exceed USD 50 million in any year before 2030.

Determining material IROs


The materiality of each identified IRO has been determined by taking three factors into consideration: scale, likelihood and scope. The table below provides a summary of what these factors mean in each case:

Table. – Factors to determine materiality

	Impacts	Risks	Opportunities
Scale	Scale of the impact, determined by expert judgement	Financial effect of risk	Financial effect of opportunities
Likelihood	Likelihood that the impact will have material consequence on people or environment	Likelihood of the risk materialising on the indicated scale	Refers to the level of the maturity of the opportunity in the companies' operations – see
Scope	Geographic scope where the impact generally materialises	Not relevant	

The threshold for materiality of IROs have been determined based on Table 10.:

Table 10. Materiality thresholds



Validation and approval of our Double Materiality Assessment

Our materiality assessment was first validated by our internal SMEs and our most important external stakeholders. After finalisation, we fulfilled the mandatory requirements described by CSRD & national legislation in Hungary on sustainability reporting: the result has been validated by the Board of Directors, while our methodology has been approved by an external auditor – see Independent Assurance Report attached to our Sustainability Report.

SUMMARY OF MOL GROUP'S DOUBLE MATERIALITY ASSESSMENT RESULTS

/IRO-2/


Material IROs consists of a list of 10 positive and 12 negative impacts, 9 risks (and 3 currently non-material considering the current circumstances, with expectation to became material on the long-term) and 11 opportunities:

IRO group	ID	IRO title	Materiality	Chapter
Actual positive impact	IM-01	Contribution to the transition to low carbon economy	Material (High)	E1
Actual negative impact	IM-02	Effect on climate	Material (High)	E1
Actual negative impact	IM-03	Effect on air quality	Material (High)	E2
Potential negative impact	IM-04	Spills	Material	E2
Potential negative impact	IM-05	Water discharges	Material	E3
Potential negative impact	IM-06	Operations in areas in or near areas with high environmental value	Material	E4
Actual positive impact	IM-07	Providing waste management & circular economy services	Material (High)	E5
Potential negative impact	IM-08	Waste generation	Material	E5
Actual positive impact	IM-09	Key regional business partnerships	Material (High)	G1

IRO group	ID	IRO title	Materiality	Chapter
Potential negative impact	IM-10	Risk of unfair business conduct	Material	G1
Actual positive impact	IM-11	Corporate culture	Material (High)	S1
Actual positive impact	IM-12	Secure employment on fair terms	Material (High)	S1
Potential negative impact	IM-13	Work-related injuries and road accidents	Material	S1
Actual positive impact	IM-14	Training and skills development	Material (High)	S1
Potential negative impact	IM-15	Human rights & labour practices in the value chain	Material	S2
Actual positive impact	IM-16	Corporate giving, donations, volunteering	Material (High)	S3
Potential negative impact	IM-17	Disturbance from operations	Material	S3
Actual positive impact	IM-18	MOL Group as a taxpayer	Material (High)	S3
Potential negative impact	IM-19	Operations in areas with low security	Material	S1
Actual positive impact	IM-20	Supply of critical products (fuel, electricity, convenience products)	Material (High)	S4
Potential positive & negative impact	IM-21	Consumer health & safety	Material	S4
Actual positive impact	IM-22	Providing sustainable mobility services	Material (High)	S4
Potential negative impact	IM-23	Risk of data exposure	Material	S4
Market/technology & legal risk	RK-01	Increased cost of greenhouse gas emissions	Material (High)	E1
Market/technology & legal risk	RK-02	Risks related to new energy efficiency and renewable energy regulations	Material (High)	E1
Potential physical & operational risk	RK-03	Climate change induced physical risks & other natural disasters	Non-material	E1
Physical & operational risk	RK-04	Personal injury risk due to system integrity failure or accidents	Material	E2
Potential physical & operational risk	RK-05	Risk of increased cost of environmental load reduction	Non-material	E2
Operational risk	RK-06	Risks due to waste handling & recycling capacity bottlenecks	Material	E5
Potential operational risk	RK-07	Labour market risks - Employee attraction & retention capabilities	Non-material	S1
Operational risk	RK-08	Risk of shortage of services, feedstock, products to be obtained from market	Material	S2
Physical risk	RK-09	Exposure to security threats	Material	S1
Operational risk	RK-10	Operational hinderances and / or increased expenses due to community issues	Material	S3
Fraud risk	RK-11	Risk of fraud	Material	G1
Operational risk	RK-12	Risk of information & cyber security incidents	Material	G1
Piloted opportunity	OP-01	Green hydrogen production	Material (High)	E1
Opportunity implemented at scale	OP-02	Waste management services	Material (High)	E5
Piloted opportunity	OP-03	Sustainable chemicals	Material (High)	E2
Piloted opportunity	OP-04	Renewable energy production	Material (High)	E1
Assessed / planned opportunity	OP-05	Leveraging subsurface expertise	Material	E1
Opportunity implemented at scale	OP-06	Sharing economy services	Material	S4
Opportunity implemented at scale	OP-07	E-charging network	Material	E1
Assessed / planned opportunity	OP-08	Waste-based fuel usage & production	Material	E1
Opportunity implemented at scale	OP-09	Energy efficiency projects	Material (High)	E1
Piloted opportunity	OP-10	Sustainable aviation fuel	Material (High)	E1
Opportunity implemented at scale	OP-11	Biogas production	Material (High)	E1

Details of each IRO – such as description, time horizons, remendability, information on the relevancy in MOL Group's value chain and connected sustainability topics are described in the beginning of the corresponding topical standard. MOL Group's Materiality Matrix provides the sustainability matters from the topical perspective. It maps the list of topics taken from *ESRS 1 paragraph AR 16*, and tailored to MOL Group - i.e., by selecting the most illustrative granularity, and by adding entity-specific topics: Disturbance of local communities, Shared wealth and economic impact, Cyber security). The matrix considers each of the selected topics from the two dimensions of Double Materiality:

	Explanation
Impact materiality	A sustainability matter is material from an impact perspective when it pertains to MOL Group's material actual or potential, positive or negative impacts on people or the environment connected with its own operations as well as through its business relationships, value chains and products & services. In our assessment, a topic is considered material from the "impact" perspective, if there was at least one *impact* on the IRO list, where the topic was marked as relevant.
Financial materiality	A sustainability matter is material from the financial perspective when it is considered material for primary users of general-purpose financial reports in making decisions relating to providing resources to the entity. In our assessment, a topic is considered material from the "financial" perspective, if there was at least one *risk or opportunity* on the IRO list, where the topic was marked as relevant.



Selecting material Disclosure Requirements /IRO-2_13/

The primary aim of the DMA is to determine which Disclosure Requirements (DR) are to be elaborated on in out Sustainability Report. As a preliminary step, we have assigned the relevant DR to each IRO on our final list. For this exercise, we have consulted the document *„Links*

between AR16 and Disclosure requirements" (ID 177) published by EFRAG. Generally, if we matched at least one material IRO to a DR, we considered it material, meaning we include it in MOL Group's 2024 Sustainability Report. To determined materiality the sub-paragraphs under DRs, we also considered the Materiality Matrix and relevant IROs to make our judgement.

List of Disclosure Requirements complied with in preparing the sustainability statement

DR		Reference to chapter
ESRS 2 BP-1	General basis for preparation of the sustainability statements	
ESRS 2 BP-2	Disclosures in relation to specific circumstances	
ESRS 2 GOV-1	The role of the administrative, management, and supervisory bodies	• Oversight on sustainability related issues • Corporate Governance Declaration (2.-6.)
ESRS 2 GOV-2	Information provided to and sustainability matters addressed by the undertaking's administrative, management and supervisory bodies	
ESRS 2 GOV -3	Integration of sustainability-related performance in incentive schemes	• Corporate Governance Declaration (8.)
ESRS 2 GOV-4	Statement on sustainability due diligence	• G1 – Sub-chapter B: Supply chain management
ESRS 2 GOV-5	Risk management and internal controls over sustainability reporting	• Oversight on sustainability related issues • Integrated Risk Management
ESRS 2 SBM-1	Strategy, business model, and value chain	• Management Discussion&Analysis (3.)
ESRS 2 SBM-2	Interests and views of stakeholders	• Stakeholder engagement
ESRS 2 SBM-3	Material impacts, risks, and opportunities and their interaction with strategy and business model	
ESRS 2 IRO-1	Description of the process to identify and assess material impacts, risks, and opportunities	
ESRS 2 IRO-2	Disclosure requirements in ESRS standards covered by the undertaking's sustainability statements	• Summary of MOL Group's double materialiaty assessment
E1-1	Transition plan for climate change mitigation	• Transition plan and targets related to climate change
E1, SBM-3	Material impacts, risks, and opportunities, and their interaction with strategy and business model	• Impacts, risks and opportunities related to climate change
E1, IRO-1	Description of the process to identify and assess material climate-related impacts, risks, and opportunities	
E1-2	Policies related to climate change mitigation and adaptation	
E1-3	Actions and resources in relation to climate change policies	• Action related to climate change
E1-4	Targets related to climate change mitigation and adaptation	• Transition plan and targets related to climate change
E1-5	Energy consumption and mix	• Metrics related to energy consumption and mix
E1-6	Gross scope 1, 2, 3 and total GHG emissions	• Metrics related to GHG emissions
E1-7	GHG removals and GHG mitigation projects financed through carbon credits	• No disclosure (not materials)
E1-8	Internal carbon pricing	

DR		Reference to chapter
E1-9	Anticipated financial effects from material physical and transition risks and potential climate-related opportunities	No disclosure (phase-in)
E2, IRO-1	Description of the processes to identify and assess material pollution-related impacts, risks and opportunities	• Impacts and risks related to pollution
E2-1	Policies related to pollution	
E2-2	Actions and resources related to pollution	
E2-3	Targets related to pollution	
E2-4	Pollution of air, water and soil	• Metrics related to air water and soil pollution
E2-5	Substances of concern and substances of very high concern	• Information on substances of concern & Substances of very high concern
E2-6	Anticipated financial effects from pollution-related impacts, risks and opportunities	No disclosure (phase-in)
E3, IRO-1	Description of the processes to identify and assess material water and marine resources-related impacts, risks and opportunities	• Identified water related impacts
E3-1	Policies related to water and marine resources	• Policies related to water use
E3-2	Actions and resources related to water and marine resources	• Actions related to water use
E3-3	Targets related to water and marine resources	• Targets related to water
E3-4	Water consumption	• Metrics related to water use
E3-5	Anticipated financial effects from water and marine resources-related impacts, risks and opportunities	No disclosure (phase-in)
E4-1	Transition plan and consideration of biodiversity and ecosystems in strategy and business model	No disclosure (not material)
E4, SBM-3	Material impacts, risks and opportunities and their interaction with strategy and business model	No disclosure (not material)
E4, IRO-1	Description of processes to identify and assess material biodiversity and ecosystem-related impacts, risks and opportunities	• Impacts, risks and opportunities related to biodiversity
E4-2	Policies related to biodiversity and ecosystems	
E4-3	Actions and resources related to biodiversity and ecosystems	• Actions related to biodiversity and ecosystems
E4-4	Targets related to biodiversity and ecosystems	
E4-5	Impact metrics related to biodiversity and ecosystems change	• Metrics related to biodiversity and ecosystems
E4-6	Anticipated financial effects from biodiversity and ecosystem-related risks and opportunities	No disclosure (phase-in)
E5, IRO-1	Description of the processes to identify and assess material resource use and circular economy-related impacts, risks and opportunities	• Identified impacts and risks related to own waste generation and treatment • Identified risks and opportunities related to circular economy & resource use in the downstream segment • Identified impacts, risks and opportunities related to circular economy services
E5-1	Policies related to resource use and circular economy	• Policies related to waste generation and treatment • Policies related to resource use • Policies related to circular economy services
E5-2	Actions and resources related to resource use and circular economy	• Actions related to waste generation and treatment • Actions related to resource use • Actions and resources related to circular economy services
E5-3	Targets related to resource use and circular economy	• Targets related to waste generation and treatment • Targets related to the circular economy services business segment
E5-4	Resource inflows	• Metrics related to waste generation and treatment • Metrics related to resource in- and outflows of the downstream business segment • Metrics related to resource in- and outflows of the circular economy services business segment
E5-5	Resource outflows	• Metrics related to waste generation and treatment • Metrics related to resource in- and outflows of the downstream business segment

DR		Reference to chapter
		• Metrics related to resource in- and outflows of the circular economy services business segment
E5-6	Anticipated financial effects from resource use and circular economy-related impacts, risks and opportunities	No disclosure (phase-in)
S1, SBM-2	Interests and views of stakeholders	• Identified impacts and risks related to human resource management • Identified impacts and risks related to occupation health & safety • Identified impact related to diversity and inclusion
S1, SBM-3	Material impacts, risks and opportunities and their interaction with strategy and business model	
S1-1	Policies related to own workforce	• Policies & engagement related to own workforce • Policies related to health, safety and security of workers • Policies, engagement and grievances related to diversity and inclusion • Policies related to grievances and remediation
S1-2	Processes for engaging with own workers and workers' representatives about impacts	• Policies & engagement related to own workforce • Engagement related to health, safety and security of workers • Policies related to health, safety and security of workers • Policies, engagement and grievances related to diversity and inclusion
S1-3	Processes to remediate negative impacts and channels for own workers to raise concerns	• Policies related to health, safety and security of workers • Policies, engagement and grievances related to diversity and inclusion • Policies related to grievances and remediation
S1-4	Taking action on material impacts on own workforce, and approaches to mitigating material risks and pursuing material opportunities related to own workforce, and effectiveness of those actions	• Actions related to human resources • Actions and resources related to occupational health & safety • Actions related to diversity and inclusion
S1-5	Targets related to managing material negative impacts, advancing positive impacts, and managing material risks and opportunities	• Targets related to human resources • Targets related to health & safety • Targets related to diversity and inclusion
S1-6	Characteristics of the undertaking's employees	• Metrics related to characteristics of employees
S1-7	Characteristics of non-employee workers in the undertaking's own workforce	No disclosure (phase-in)
S1-8	Collective bargaining coverage and social dialogue	• Metrics related to collective bargaining coverage and social dialogue
S1-9	Diversity metrics	• Metrics related to diversity and inclusion
S1-10	Adequate wages	
S1-11	Social protection	No disclosure (phase-in)
S1-12	Persons with disabilities	
S1-13	Training and skills development metrics	• Actions related to human resources
S1-14	Health and safety metrics	• Metrics related to health and safety
S1-15	Work-life balance metrics	No disclosure (phase-in)
S1-16	Compensation metrics (pay gap and total compensation)	• Metrics related to remuneration (pay gap and total remuneration)
S1-17	Incidents, complaints and severe human rights impacts	• Metric related to incidents and complaints related to a fair, ethical , inclusive work environment
S2, SBM-2	Interests and views of stakeholders	No disclosure (phase-in)
S2, SBM-3	Material impacts, risks and opportunities and their interaction with strategy and business model	
S2-1	Policies related to value chain workers	• Policies, engagement and grievances related to diversity and inclusion (phase-in)
S2-2	Processes for engaging with value chain workers about impacts	No disclosure (phase-in)

DR		Reference to chapter
S2-3	Processes to remediate negative impacts and channels for value chain workers to raise concerns	• Policies related to grievances and remediation (phase-in)
S2-4	Taking action on material impacts on value chain workers, and approaches to managing material risks and pursuing material opportunities related to value chain workers, and effectiveness of those action	No disclosure (phase-in)
S2-5	Targets related to managing material negative impacts, advancing positive impacts, and managing material risks and opportunities	
S3, SBM-2	Interests and views of stakeholders	• Impacts and risks related to affected local communities • Impacts related to shared wealth & economic impact
S3, SBM-3	Material impacts, risks and opportunities and their interaction with strategy and business model	
S3-1	Policies related to affected communities	• Policies related to affected local communities • Policies related to shared wealth & economic impact
S3-2	Processes for engaging with affected communities about impacts	
S3-3	Processes to remediate negative impacts and channels for affected communities to raise concerns	
S3-4	Taking action on material impacts on affected communities, and approaches to managing material risks and pursuing material opportunities related to affected communities, and effectiveness of those actions	• Actions to manage impacts and risks related to affected local communities • Actions related to shared wealth & economic impact
S3-5	Targets related to managing material negative impacts, advancing positive impacts, and managing material risks and opportunities	• Targets related to affected local communities • Targets related to shared wealth & economic impact
S4, SBM-2	Interests and views of stakeholders	• Impacts and opportunities related to consumers
S4, SBM-3	Material impacts, risks and opportunities and their interaction with strategy and business model	
S4-1	Policies related to consumers and end-users	
S4-2	Processes for engaging with consumers and end-users about impacts	• Policies related to consumers and end-users
S4-3	Processes to remediate negative impacts and channels for consumers and end-users to raise concerns	
S4-4	Taking action on material impacts on consumers and end-users, and approaches to managing material risks and pursuing material opportunities related to consumers and end- users, and effectiveness of those actions	• Actions related to consumers and end-users
S4-5	Targets related to managing material negative impacts, advancing positive impacts, and managing material risks and opportunities	• Excluded (more information in Excluded Disclosure Requirements from Social Standards)
G1, GOV-1	The role of the administrative, supervisory and management bodies	• Oversight on sustainability related issues
G1, IRO-1	Description of the processes to identify and assess material impacts, risks and opportunities	• Impacts, risks & opportunities related to business conduct • Impacts on suppliers
G1-1	Corporate culture and Business conduct policies and corporate culture	• Policies related to business conduct •
G1-2	Management of relationships with suppliers	• Policies related to relationships with suppliers
G1-3	Prevention and detection of corruption and bribery	• Policies related to business conduct
G1-4	Confirmed incidents of corruption or bribery	• Incidents of corruption or bribery
G1-5	Political influence and lobbying activities	• Political influence and lobbying activities
G1-6	Payment practices	• Metrics related to payment practices

List of datapoints in cross-cutting and topical standards that derive from other EU legislation

DR	Data point		Legislation	Chapter
ESRS 2 GOV-1	21 (d)	Board's gender diversity	SFDR, BRR	Oversight on sustainability related issues
ESRS 2 GOV-1	21 (e)	Percentage of Board members who are independent	BRR	Oversight on sustainability related issues
ESRS 2 GOV-4	30	Statement on due diligence	SFDR	Supply chain management
ESRS 2 SBM-1	40 (d) i	Involvement in activities related to fossil fuel activities	SFDR, P3, BRR	Management Discussion&Analysis (3.)
ESRS 2 SBM-1	40 (d) ii	Involvement in activities related to chemical production	BRR	Management Discussion&Analysis (3.)
ESRS 2 SBM-1	40 (d) iii	Involvement in activities related to controversial weapons	BRR	not relevant
ESRS 2 SBM-1	40 (d) iv	Involvement in activities related to cultivation and production of tobacco	EUCL	not relevant
ESRS E1-1	14	Transition plan to reach climate neutrality	EUCL	Transition plan and targets related to climate change
ESRS E1-1	16 (g)	Undertakings excluded from Paris-aligned Benchmarks	P3, BRR	Transition plan and targets related to climate change
ESRS E1-4	34	GHG emission reduction targets	SFDR, P3, BRR	Transition plan and targets related to climate change
ESRS E1-5	38	Energy consumption from fossil sources disaggregated by sources	SFDR	Metrics related to energy consumption and mix
ESRS E1-5	37	Energy consumption and mix	SFDR	Metrics related to energy consumption and mix
ESRS E1-6	44	Gross Scope 1, 2, 3 and Total GHG emissions	SFDR, P3, BRR	Metrics related to GHG emissions
ESRS E1-6	53-55	Gross GHG emissions intensity	SFDR, P3, BRR	not material
ESRS E1-7	56	GHG removals and carbon credits	EUCL	not material
ESRS E1-9	66	Exposure of the benchmark portfolio to climate related physical risks	BRR	No disclosure (phase-in)
ESRS E1-9	66 (a), (c)	Disaggregation of monetary amounts by acute and chronic physical risk; location of significant assets at material physical risk	P3	No disclosure (phase-in)
ESRS E1-9	67 (c)	Breakdown of the carrying value of its real estate assets by energy-efficiency classes	P3	No disclosure (phase-in)
ESRS E1-9	69	Degree of exposure of the portfolio to climate related opportunities	BRR	No disclosure (phase-in)
ESRS E2-4	38	Amount of each pollutant listed in annex II of the E-PRTR regulation emitted to air, water, and soil	SFDR	Metrics related to air, water and soil pollution
ESRS E3-1	9	Water and marine resources	SFDR	Policies related to water use
ESRS E3-1	13	Dedicated policy	SFDR	Policies related to water use
ESRS E3-1	14	Sustainable oceans and sea	SFDR	Policies related to water use
ESRS E3-4	28 (c)	Total water recycled and reused	SFDR	Metrics related to water use
ESRS E3-4	29	Total water consumption in m3 per net revenue on own operations	SFDR	Metrics related to water use
ESRS 2 – IRO 1 – E4	16 (a) i	Activities negatively affecting biodiversity-sensitive areas	SFDR	Impacts, risks and opportunities related to biodiversity
ESRS 2 – IRO 1 – E4	16 (b)	Land degradation, desertification, or soil sealing	SFDR	No disclosure (not material)
ESRS 2 – IRO 1 – E4	16 (c)	Threatened species	SFDR	No disclosure (not material)
ESRS E4-2	24 (b)	Sustainable land/agriculture practices or policies	SFDR	No disclosure (not material)
ESRS E4-2	24 (c)	Sustainable oceans/seas practices or policies	SFDR	No disclosure (not material)
ESRS E4-2	24 (d)	Policies to address deforestation	SFDR	No disclosure (not material)

DR	Data point		Legislation	Chapter
ESRS E5-5	37 (d)	Non-recycled waste	SFDR	Metrics related to waste generation and treatment
ESRS E5-5	39	Hazardous waste and radioactive waste	SFDR	Metrics related to waste generation and treatment
ESRS 2 – SBM 3 – S1	14 (f)	Risk of incidents of forced labour	SFDR	Workforce
ESRS 2 – SBM 3 – S1	14 (g)	Risk of incidents of child labour	SFDR	Workforce
ESRS S1-1	20	Human rights policy commitments	SFDR	Policies, engagement and grievances related to diversity and inclusion
ESRS S1-1	21	Due diligence policies on issues addressed by the fundamental International Labor Organisation Conventions 1 to 8	BRR	Minimum social safeguards (MSS) assessment
ESRS S1-1	22	Processes and measures for preventing trafficking in human beings	SFDR	No disclosure (not material)
ESRS S1-1	23	Workplace accident prevention policy or management system	SFDR	Policies related to health, safety and security of workers
ESRS S1-3	32 (c)	Grievance/complaints handling mechanisms	SFDR	Policies, engagement and grievances related to diversity and inclusion
ESRS S1-14	88 (b), (c)	Number of fatalities and number and rate of work-related accidents	SFDR, BRR	Metrics related to health and safety
ESRS S1-14	88 (e)	Number of days lost to injuries, accidents, fatalities or illness paragraph	SFDR	No disclosure (phase-in)
ESRS S1-16	97 (a)	Unadjusted gender pay gap	SFDR, BRR	Metrics related to remuneration (pay gap and total remuneration)
ESRS S1-16	97 (b)	Excessive CEO pay ratio	SFDR	Metrics related to remuneration (pay gap and total remuneration))
ESRS S1-17	104 (a)	Non-respect of UNGPs on Business and Human Rights and OECD	SFDR, BRR	Metric related to incidents and complaints related to a fair, ethical , inclusive work environment
ESRS 2 – SBM 3 – S2	11 (b)	Significant risk of child labour or forced labour in vaue chain	SFDR	No disclosure (not material)
ESRS S2-1	17	Human rights policy commitment	SFDR	No disclosure (phase-in)
ESRS S2-1	18	Policies related to value chain workers	SFDR	No disclosure (phase-in)
ESRS S2-1	19	Non-respect of UNGPs on Business and Human Rights principles and OECD guidelines	SFDR, BRR	No disclosure (phase-in)
ESRS S2-1	19	Due diligence policies on issues addressed by the fundamental International Labor Organisation Convention 1 to 8	BRR	No disclosure (phase-in)
ESRS S2-4	36	Human rights issues and incidents connected to its upstream and downstream value chain	SFDR	No disclosure (phase-in)
ESRS S3-1	16	Human rights policy commitments	SFDR	Policies related to affected communities
ESRS S3-1	17	Non-respect of UNGPs on Business and Human Rights, ILO principles and OECD guidelines	SFDR, BRR	No disclosure (not material)
ESRS S3-4	36	Human rights issues and incidents	SFDR	No disclosure (not material)
ESRS S4-1	16	Policies related to consumers and end-users	SFDR	Policies related to consumers and end-users
ESRS S4-1	17	Non-respect of UNGPs on Business and Human Rights and OECD guidelines	SFDR, BRR	No disclosure (not material)
ESRS S4-4	35	Human rights issues and incidents	SFDR	No disclosure (not material)
ESRS G1-1	10 (b)	United Nations Convention against Corruption	SFDR	Minimum social safeguards (MSS) assessment
ESRS G1-1	10 (d)	Protection of whistle-blowers	SFDR	Policies related to grievances and remediation

DR	Data point		Legislation	Chapter
ESRS G1-4	24 (a)	Fines for violation of anti-corruption and anti-bribery laws	SFDR, BRR	Incidents of corruption and bribery
ESRS G1-4	24 (b)	Standards of anti-corruption and anti-bribery	SFDR	Policies related to business conduct

(SFDR = Sustainable Finance Disclosure Regulation, P3 = EBA Pillar 3 disclosure requirements, BRR = Climate Benchmark Standards Regulation, EUCL = EU Climate Law)

ESRS ENVIRONMENT

CLIMATE CHANGE

/E1/

TRANSITION PLAN AND TARGETS RELATED TO CLIMATE CHANGE

/E1-1; E1-4/

Shape tomorrow strategy

MOL Group recognized early the necessity of coordinated industrial development and sustainable objectives. Since the publication of the Group-level strategy in 2016, the focus has been on a gradual transition towards meeting the demands of a low-carbon economy.

In 2024, MOL Group announced its updated Shape Tomorrow Strategy in response to the changing external environment. Despite MOL Group's long-term goals and the fundamental principles of its strategy remaining unchanged, evolving energy and fuel demand market trends, the importance of secure energy supply, and the EU's more ambitious decarbonization targets necessitated an update to the strategy, prompting the revision of sustainability goals to accelerate the transition. The strategy was updated to reduce absolute emissions by 25% by 2030 compared to our 2019 base value. This 25% absolute emission reduction target is equivalent to a 33% reduction on the previous (2019 like-for-like) terms. Representatives of the main business divisions and functional areas are involved in strategy and target setting, and any changes to the strategy need approval from the Board of Directors.

MOL Group's sustainability strategy is embedded in its business strategy and business planning: the company strives for a smart energy transition which makes the Central and Eastern European region more sustainable, more self-sufficient and more competitive. The transition path builds on the above-average growth trajectory expected in CEE economies and MOL's ambition to retain or increase its presence in this area in its traditional wholesale and retail markets. This resilient growth model is foreseen to be maintained over the strategic horizon to 2030 and is the main engine to fund the transition.

To reach its ambition of net climate neutrality by 2050, MOL Group is committed to the transformation of its fossil-fuel-based operation into a low-carbon, sustainable business model. This model builds on the already existing integrated nature of the company: MOL will provide sustainable materials and circular solutions for the economy, low carbon fuels for mobility and convenient products and services for the people on the move, while also minimizing the environmental footprint of its own operations.

Transition plan and decarbonization levers

Expanding on MOL Group's Shape Tomorrow strategy, the company also discloses its transition plan for the first time in the 2024 sustainability statement. The transition plan was approved by the Sustainable Development Committee of the Board of Directors in February 2025. As part of the sustainability statement, it was also approved by the Board of Directors in March 2025, and by the Annual General Meeting in April 2025. The plan includes key milestones for 2030 and 2050 with the following targets:

- Decrease absolute gross Scope 1 and 2[8] GHG emission by 25% by 2030 compared to 2019[9],
- Decrease absolute gross Scope 3 GHG use-phase emissions of our sold energy products[10] (Category 11: Use of sold products) by 5% by 2030 compared to 2022,
- Reach net zero GHG emissions on all Scopes by 2050,
- Allocate 30-40% of total CAPEX to low-carbon and sustainable business projects between 2025 and 2030.

The targets take into account MOL Group's best estimates with regards to macroeconomic scenarios, the speed of the energy transition in the Central and Eastern European region, established regulatory frameworks and the Group's expected strategic shifts in the business scope.

The base year and the baseline value for Scope 1 and 2 GHG emissions are aligned with the Shape Tomorrow Strategy and remains unchanged. Since there was no significant change neither in the GHG reporting boundary in the 2019-2024 period, nor in the measurement methodologies and significant assumptions behind the GHG calculation, the baseline value is considered representative and consistent with the reported GHG inventory boundaries[11] of MOL Group's current operations. The baseline value was 6.93 mn tons of CO_2-eq for Scope 1 emissions and 0.7 mn tons of CO_2-eq for Scope 2 location-based emissions. Due to the unbundled nature of FGSZ Zrt., Scope 1 and 2 emissions of FGSZ are not included in the target and in the described decarbonization levers. Metrics are disaggregated in 'Metrics related to GHG emissions' section for traceability of target scope.

[8] Scope 2 location based

[9] GHGs covered in target: carbon dioxide (CO_2) and methane (CH_4)

[10] Target refers to Scope 3 Category 11: Use of sold products, which includes sales of natural gas and fossil-based refinery products.


[11] As stated in section Basis for Preparation, newly acquired companies are not yet part of the GHG inventory.

The base year for Scope 3 GHG use-phase emissions of sold energy products is 2022 due to more reliable data collection and the fact that this is a newly introduced target[12]. The target is consistent with the Group's GHG inventory boundary and includes the use-phase emission of all energy products sold to third parties, most notably natural gas, motor gasoline and diesel. The baseline value for Scope 3 GHG use-phase emissions of sold energy products is 56.7 mn tons of CO_2-eq.

MOL Group's target for the share of low-carbon CAPEX takes into account a wide variety of projects, including, but not limited to EU Taxonomy aligned projects. MOL's low carbon definition covers every project which contributes to the Group's energy transition by lowering emissions (including energy efficiency, electrification) or stepping into new, low carbon businesses (renewable energy, circular economy).

MOL Group identified the key decarbonization levers and their expected contribution to the aforementioned Scope 1 and 2 target. The levers are listed below and also visualized on the below figure. Decarbonization levers.

Figure. Decarbonization levers



1. Energy efficiency: Energy efficiency involves optimizing processes and equipment to reduce energy consumption and emissions. This includes upgrading to more efficient machinery, improving insulation, and implementing advanced process controls. By reducing energy waste, companies can lower their carbon footprint and operational costs. Energy efficiency technologies are well-established and widely implemented across various industries, including the oil and gas sector. For this reason, energy efficiency initiatives are key from the earliest stages of decarbonization.

MOL Group has already implemented several actions related to this decarbonization lever, listed in the *Actions related to Climate Change* section. Energy efficiency is expected to contribute 800 kt of Scope 1 and 2 emissions reductions between 2025-2030.

2. Electrification and renewable energy: Electrification involves replacing fossil fuel-based energy sources with electricity. This transition can significantly reduce greenhouse gas emissions, especially when combined with renewable energy integration. The maturity of electrification and renewable energy technologies varies. Solar and wind power are highly mature and cost-competitive with traditional energy sources in the CEE region. While rapidly advancing technology, integrating renewable energy at industrial production sites also poses several challenges. The variability and intermittency of renewable energy sources can lead to reliability issues; conventional power management systems require significant upgrades or the adoption of advanced solutions such as energy storage installation; more specifically for oil and gas operations, full balance of steam systems also has to be considered.

MOL Group has already implemented actions which support the electrification of its production sites. Electrification and renewable energy is expected to contribute a further 100-200 kt of Scope 1 and 2 emissions reduction between 2025-2030.

3. Sustainable feedstocks and products: This lever includes using sustainable feedstocks such as green hydrogen, biogas, biomethane, biofuels, waste-based feedstock, and recycled plastics. These alternatives can replace conventional fossil-based feedstocks, reducing the carbon intensity of products and processes. The above-mentioned products are not only feedstocks for MOL Group's own operations but also direct the company towards a more sustainable product portfolio.

[12] Based on the European Sustainability Reporting Standards and the Transition Plan Implementation Guidance, baseline value cannot be earlier than 2022, except for cases where a target was already set before the publication of the transition plan.

The maturity of sustainable feedstocks and products varies. For example, biofuels and biogas are relatively mature and commercially available, while technologies like green hydrogen are still developing but show significant potential. MOL Group has already implemented projects in all of these directions. A more detailed description is available in the *Actions related to Climate Change* section.

4. Carbon capture solutions: Carbon removal solutions involve capturing and storing carbon dioxide emissions from industrial processes or directly from the atmosphere. Technologies include carbon capture, utilization, and storage (CCUS), direct air capture (DAC) and solutions related to land-use change. Verified negative emissions are an acknowledged part of climate scenarios and will be necessary to tackle residual emissions in hard-to-abate sectors such as oil and gas.

Carbon removal technologies are in various stages of development. CCUS is relatively mature and has been implemented in several large-scale projects around the world, while DAC is still in the early stages but is rapidly advancing. MOL Group plans to use and gradually scale up carbon removal solutions after 2030 to reach its net zero target.

Beside the described decarbonization levers, MOL Group acknowledges that future organic growth (investments in new assets), but also the decline of traditional fossil fuel sales due to demand changes (presented as organic decline in the chart) will affect the Group's emission pathway. The planned actions and the expected demand changes are also taken into account in the transition plan.

Assumptions of transition plan and 1.5°C alignment

MOL Group's transition plan is based on the company's long-term premises, in line with the Shape Tomorrow Strategy. MOL premises are the basis of project evaluation and strategic direction setting. Premises are developed through partial equilibrium models where we regularly use external assumptions, including IEA World Energy Outlook scenario results. However, climate modelling is not the scope of these exercises.

Universally accepted economic or energy models that can incorporate the impact of and on climate change typically lack the granularity necessary for the design of the transition plan of more concentrated asset portfolios such as that of MOL Group. Hence, it is difficult to apply global results to specific regions, countries, especially if the green transition is multi-speed. First, the EU commitment to green transition suggests a very different transition path from the path of the global average. But even with EU-level granularity, there are significant differences between Western and Central and Eastern Europe in key factors defining the pathway, such as access to capital, technology and innovation, government policies, production costs, customer preferences. That suggests that even within the EU/Europe there will be different transition pathways.

Assessment of the transition plan's compatibility with a 1.5°C pathway faces difficulties not just from the point of view of geographical limitations, but also industry-specific ones. A widely accepted, oil and gas industry specific benchmark for a 1.5°C compatible gross absolute GHG emission pathway is not yet available. MOL Group will assess the feasibility of adopting such a plan once the relevant guidelines and resources, primarily from the Science Based Target Initiative (SBTi), become available.

MOL Group's forecasts are prepared for three scenarios: Slow Transition, Steady Transition & Net Zero Emission. The green energy transition is happening in all three scenarios, the biggest difference between them is the pace of the transition. The Shape Tomorrow Strategy and the transition plan is predominantly based on the Steady Transition scenario. If one of the other two scenarios materializes, it would mostly affect the timing of the investments and actions envisaged in the Shape Tomorrow Strategy and the transition plan, not the strategic directions themselves.

For the above reasons, MOL Group's 2030 targets are below the SBTi's cross-sector pathway, which suggests that gross Scope 1, 2 and 3 emissions should be reduced by 42% by 2030 and 90% by 2050 from 2020 levels[13]. Based on the Group's activities, MOL Group is excluded from the EU Paris-aligned Benchmarks.[14]

More information about the resilience of the strategy are available in the Integrated Risk Management chapter of the Management Report and under the description of 'RK-03: Climate change induced physical risks & other natural disasters' of this chapter.

Assessment of locked-in emissions

As an integrated oil and gas company, MOL Group's current operations include hydrocarbon exploration and production, crude oil refining and petrochemical production. While these operations and the related assets and product portfolio make up the overwhelming majority of the Group's emission profile, they are also key to the Group's abilities to finance and implement the actions necessary to the energy transition.

The Upstream operations span nine countries, with active production in eight. In 2024, MOL Group produced 93,838 barrels of oil equivalent per day. At the end of 2023, MOL Group was estimated to have 76 MMboe of natural gas and 242 MMboe of crude oil and condensates as proved reserves (1P). While MOL is committed to launching low-carbon projects in the Central and Eastern Europe (CEE)

[13] SBTi: Pathways to Net Zero
[14] Article 12(1) of Commission Delegated Regulation (EU) 2020/1818

region between 2025 and 2030 as part of its 2030 strategy, the current production activities inherently involve significant emissions. These emissions are locked in due to the nature of the existing assets and their expected operational lifetimes.

The Downstream segment includes three refineries (Danube refinery, Bratislava refinery, Rijeka refinery) and two petrochemical units, located in Slovakia, Hungary, and Croatia, and with sales focused in 14 countries across Central and Eastern Europe. These facilities convert crude oil into various refined products such as gasoline, diesel, heating oil, lubricants and petrochemical products such polypropylene, low-density and high-density polyethylene. In 2024, MOL Group sold 18.6 million tons of refined products and 1.1 million tons of petrochemical products. MOL Group's largest ever organic investment, the Polyol project was inaugurated in May 2024 and will significantly enhance the Group's petrochemical production capacity. Given that Downstream operations contribute significantly to the Group's emissions, these facilities and the related product portfolio represent the highest locked-in emissions within our portfolio. While these emissions could hinder our ability to meet our GHG reduction targets and increase transition risk, the facilities are also the primary candidates for carbon removal technologies due to the concentrated GHG emissions. Thus, we are actively focusing on GHG emission reduction, sustainable chemical transformation, circular economy initiatives, renewable fuels, including green hydrogen projects to mitigate these emissions and diversify our product portfolio from fossil fuels towards sustainable materials, as presented earlier in this chapter. The Sisak refinery in Croatia, previously shut down, is being retrofitted to become a biogas/biomethane plant utilizing agricultural waste. This transformation is part of our broader strategy to transition into a low-carbon energy company while ensuring stable and affordable supply of energy products.

ACTIONS RELATED TO CLIMATE CHANGE

/E1-3/

Progress: actions taken and planned

MOL Group has already implemented several actions and initiatives to converge towards the aforementioned transition targets. This chapter reports on our past progress compared to our base year in 2019 and more specifically focuses on developments in 2024, while also presents the key actions and resources to achieve our goals.

Past progress

MOL Group has decreased Scope 1 and 2 emissions by 9% between 2019 and 2024. The key decarbonization lever which contributed to this decrease is energy efficiency. Since 2020, several projects have been implemented with 0.3 mn tons of CO_2 reduction impact compared to the 2019 base year. In 2024, MOL Group invested approximately USD 38 million in CAPEX on several major projects aimed at enhancing energy efficiency and reducing emissions.

EU Taxonomy eligible activities in turnover is 9.3%, in OpEx 28.4%, in CapEx 21.0% for the year 2024. EU Taxonomy aligned activities in turnover is 0.5%, in OpEx 5.5%, in CapEx 7.3% for the year 2024. Relatively low alignment percentages are partially result of the previously demonstrated facts, that significant part of MOL Group's activities is still related to the oil and gas industry and a conservative approach has been followed in the assessment and reporting. More detailed table can be found in the EU Taxonomy Report of the Sustainability Statement.

The financial figures presented in this section are part of the same line items in the financial statement as the definition of total CAPEX in the EU Taxonomy Report.

One key initiative involved replacing four high-power rate condensing turbines in Rijeka Refinery in 2023 with electric drives equipped with frequency drive system. This upgrade significantly improved energy performance indicators by increasing overall efficiency. Another important project in Rijeka Refinery focused on hydrogen management improvement. By installing new pipes and spill pressure flow control systems, surplus pure hydrogen was redirected directly to the Hydrocracking Unit, translating into emission reduction of 11 ktpa.

Heat integration in a Crude Oil Distillation Unit was a major focus in 2024 at Danube Refinery, as they are among the biggest energy consumers. Efficiency improvements were achieved by installing compabloc type heat exchangers on the main and preflash columns as condensers, integrating them into the crude preheat line, and utilizing heat from vacuum residue to preheat reduced crude. This project aimed to improve efficiency, reduce natural gas consumption, and lower CO_2 emissions.

Another project that also focused on CDU efficiency upgrade involved revamping the existing INA Rijeka Refinery Crude Distillation Unit to enhance energy efficiency and operational conditions, implemented during 2020-2024.

To increase feedstock processing efficiency and produce more products like ethylene and propylene, two new Pressure Swing Absorption units were installed in steam cracker units in 2023 at MPC (MOL Petrochemicals). These units produce high-purity hydrogen, which can be used in fuel gas systems or provided to the Polyol Complex project.

One of the most significant green hydrogen projects aims to develop production capabilities that could replace traditional hydrogen production units at Danube refinery. We invested over USD 17 mn in an electrolyzer unit to partially phase out conventional hydrogen

production. In 2024, we successfully inaugurated a green hydrogen facility at the Danube Refinery with a 10 MW electrolysis unit, which reduces CO_2 emissions by 25 ktpa, producing about 1,600 t of green hydrogen to be used primarily in our own fuel production.

In 2020, the rubber bitumen plant in Zalaegerszeg began operations, utilizing a new manufacturing technology for crumb rubber developed jointly by MOL and Pannon University. This rubber bitumen, made from bitumen and waste tyres, offers several advantages over conventional road construction bitumen, including a longer lifecycle, better resistance to environmental impacts, and improved traffic safety due to reduced braking distances.

Overall, these projects are able to reduce CO_2 emission in MOL Group operations by more than 150 ktpa.

In line with our strategic direction, several acquisitions have been made in recent years. In 2019, MOL Group acquired the German-based Aurora Kunststoffe GmbH, a leading engineering plastic scrap recycling company supplying the automotive industry. This acquisition strengthened our presence in recyclate-based compounds and our position as an automotive supplier, supporting MOL Group's ambition to transform its fuel-based business model in Downstream to a higher value-added petrochemical product portfolio.

In April 2022, MOL Group acquired ReMat, Hungary's market-leading plastics recycling company, which uses communal and industrial waste to create recycled plastic granules. This transaction increased MOL Group's total capacity for recycled plastic material from 25,000 tons/year to 40,000 tons/year.

In 2023, MOL Group acquired its first biogas plant near Szarvas, Hungary. This plant processes over 100,000 tons of feedstock, including residual waste from food producers, farmers, and livestock producers in the region, producing more than 12.5 million cubic meters (mcm) of biogas per year.

Additionally, in December 2024, we expanded our renewable energy capacity by acquiring Naperőmű Farm Kft. This company oversees the construction of a 66 MWp photovoltaic plant in Ballószög, Hungary. With construction completed, trial runs are expected to start in January 2025.

Further sustainability-related initiatives have also been implemented at our Circular Economy Services segment in Hungary. While these actions do not result in immediate Scope 1 and 2 emission reductions, the successful operation of this segment is key to MOL Group's long-term strategy.

The integrated waste management concession started its operation successfully in 2023 in line with the terms laid down in the Act on Waste and in the concession agreement. The scope of the concession covers the waste management public service task and the waste management institutional tasks. MOHU takes a managing role in the waste management value chain from collection to handover for treatment. Waste management services continued with an uninterrupted frequency, collection method being consistent with pre-concession period. The cooperation with relevant authorities and government bodies is continuous. The government published the relevant legislative acts and guiding methodologies, introducing a completely new, cost-based price regulation, which includes the setting of fees for the EPR system.

With regards to efficiency measures, the waste management landscape has been rationalized in the first quarters of operation. The previous modus operandi of 26 independent service providers had been reviewed for the concession. By reducing the number of regions to six and bringing the service providers under these umbrellas, MOHU has already explored how, on a country-wide scope, synergies could and can be identified and utilized for a more efficient operation.

The new extended producer responsibility system (EPR) has been introduced from 1 July 2023, in which producers are responsible for financing the treatment or disposal of post-consumer products. Furthermore, the deposit refund system (DRS) has commenced on 1 January 2024. In case of both systems, MOHU is the designated operating organization. As part of the DRS and with close cooperation of retail partners, more than 2,600 reverse vending machines (RVMs) have already been installed by 1 July 2024, when the system came into full effect after a half-year transition period. By the end of the year, the number of installed RVMs reached approximately 3,200, with a further 1,500 contracted manual takeback points increasing national coverage of the system.

All investments made in 2024 were intended to intensify selective waste collection, and projects included the development of separate textile waste collection infrastructure, the rollout of bio kitchen waste collection system, and the purchase of first own collection vehicles. Furthermore, the first own waste yard investment in Esztergom had been completed and started its operation in May 2024, performing above expectations in terms of waste material throughput.

Key actions planned and allocated resources

Over the next five years, we have several actions planned to enhance efficiency and reduce emissions, requiring around USD 800 million in CAPEX from our total planned USD 4.3 billion for low-carbon projects. Efficiency projects include initiatives such as boosting profitability by replacing liquid fuel with gaseous fuel at the Slovnaft powerplant. This change is expected to reduce CO_2 emissions by approximately 230 ktpa and increase the yield of white products, making it one of the largest CO_2 reduction initiatives in Downstream. Various efficiency enhancements are also planned at the Slovnaft Refinery.

In terms of electrification and renewable energy, we are focusing on replacing key condensing steam drives with electromotors at the Slovnaft refinery. This change aims to reduce heavy fuel oil usage for steam production, leading to a decrease in CO_2 and other pollutant emissions by 100-150 ktpa. At MPC, we plan to improve energy efficiency and electrification and reduce CO_2 emissions by upgrading turbines and installing a new steam pipeline. These measures are expected to save significant energy and decrease CO_2 emissions by 61 kt pa.

A leading decarbonization project in Upstream with significant emission reduction of more than 100 ktpa is the construction of CO2 compressor station at Ethane Plant in Croatia, designed to compress CO_2 separated from natural gas. This project is part of the EOR (Enhanced Oil Recovery) program which aims to reduce CO_2 emission through recycling and injecting it back to the system.

The company will also expand its green electricity production in Tiszaújváros with a new 48 MWp solar power plant, one of the largest directly connected to an industrial consumer in Hungary. The project, planned to be implemented by 2026, covers an average of 5% of the Tiszaújváros manufacturing unit's annual electricity demand, which can reach up to 30% during peak periods. The solar park reduces the site's CO_2 emissions by 17 ktpa.

Our sustainable feedstocks and products strategy includes green hydrogen, biomethane, and waste feedstock, together requiring around USD 3 billion in CAPEX investment. Green hydrogen production at the Group level is crucial for ensuring long-term compliance and competitiveness in the renewable energy sector. Therefore, we plan to undertake additional green hydrogen projects, including the development and investment in a 20 MW electrolyser unit at the Slovnaft Refinery. This initiative aims to partially phase out conventional hydrogen production by 2030. Following the handover of the green hydrogen plant at Danube Refinery, the next step involves preparing and developing an investment option to produce green hydrogen at a scale that can replace one of the current grey hydrogen producing unit at the Danube Refinery. The bio-oil processing project aims to introduce bio-content into motor fuels produced by Slovnaft, focusing on cost efficiency. By co-processing bio-materials using existing refinery assets, the project minimizes investment and environmental impact by avoiding new greenfield investments, and maximizes cost efficiency for incorporating bio-content into finished fuels. MOL Group is also planning to carry out multiple projects that will scale up biomethane production for both internal and external demand.

To manage our hazardous waste and meet all emission requirements, we began constructing a state-of-the-art hazardous waste incinerator at the Danube Refinery in 2020. This project aims to address both MOL's operational waste and the increasing demand in the Hungarian market.

Until 2050, major efficiency projects will continue to be our main decarbonization lever, in Danube refinery as well as in MPC and Slovnaft, electrification projects will continue its later phases well into 2040s at all large sites under MOL Group. The upstream business is currently investigating geothermal opportunities, which, if successful, will be implemented post-2030, and expected to cut our emissions by cca. 100 ktpa. Green hydrogen projects will expand into MPC with the objective of reducing the CO_2 footprint of MOL Petrochemicals by partially replacing hydrogen production from a grey-hydrogen plant with a new green-hydrogen electrolysis technology. The produced green hydrogen will be used within the existing assets of the MPC, specifically in the Polyol complex, with no plans for external sales. The remaining emissions will be addressed with carbon capture (more than 1 million tonnes of CO_2) and the organic decline of fossil-based production due to changes in consumer behavior (more than 2.3 million tonnes of CO_2), which is expected to accelerate by the 2040s.

Overall, the described transformation requires significant funding. MOL Group has published its financial framework for the 2025-2030 period in the Shape Tomorrow Strategy, which presents a viable path towards the full execution of the Group’s organic investment plan, even at conservative macro assumptions. More favourable macroeconomic conditions would leave financial headroom fro special dividends and acquisitions as well.

In 2024, MOL Group has spent 492 bn HUF on CAPEX and investments related to its Upstream, Downstream and Consumer Services business divisions covering significant CapEx for oil and gas related economic activities, as stated in the Management Discussion and Analysis chapter 3.3-3.5. MOL Group has no coal-related economic activities.

IMPACTS, RISKS AND OPPORTUNITIES RELATED TO CLIMATE CHANGE

/E1. IRO-1; E1. SBM-3/

ESRS	Disclosure Requirement E1.IRO-1, E1.SBM-3,
IFRS	IFRS S2.25(a) IFRS S2.10(d) IFRS S2.22(b)(i)(2) IFRS S2.22(b)(i)(3) IFRS S2.22(b)(i)(4) IFRS S2.25(a) IFRS S2.25(b) IFRS S2.25(a)(ii) IFRS S1.23 IFRS S1.B42(c)

MOL Group's double materiality assessment conducted in 2024 covered the impact of our operations on climate change, and the vast implications of climate change on the current and future financial performance of MOL Group – including risks and opportunities. The general methodology and consultation process are detailed in section ESRS 2 IRO-1 of this report. Procedures for identifying actual and potential environmental impacts and risks – including climate change, pollution and water use are outlined in *Element 2: Risk & Change Management* of Health, Safety and Environment Management System (hereinafter HSE MS) of MOL Group:

- MOL Group has a company-wide HSE risk assessment system in place to identify, assess, manage, regularly review and document hazards and risks related to operations.
- Risk assessment is conducted by competent personnel with appropriate knowledge and experience. The methodology used for risk assessment is selected in accordance with the complexity of the assessed activities/workplaces.
- Identified risks, preventive, control and mitigation measures are documented and a tracking system is in place that facilitates regular reviews to ensure that risks are properly managed. Risk mitigation measures follow the hierarchy of elimination, substitution, engineering control, administrative control and personal protective equipment.
- A management-of-change process is in place to assess, control and manage all critical changes to organization/personnel, technologies, facilities and processes. All changes in operations, processes and activities are accordingly re-assessed from a risk perspective. Risk assessments related to changes are subject to the same rigorous review that is applied to new processes and activities.
- Identified risks, preventive, control and mitigation measures are communicated to all relevant employees and affected parties.
- Environmental risks and impact of the operation are identified and assessed. In order to minimize medium and high risks and impacts, action plan is developed and implemented.

HSE MS details specific measures related to GHG management, including regular risk assessment (see Section Policies: Climate change mitigation and adaptation in this chapter). Furthermore, each business unit has processes related to the identification of climate related risks which are then channeled into the Group-level risk assessment and strategy processes – see description of processes in section E1-*Policies: Climate change* of this chapter. Insights from this process are aggregated the double materiality assessment through engagement with internal environmental protection experts and business-side stakeholders, ensuring a comprehensive evaluation of climate risks and impacts.

MOL Group has identified 2 climate change related impacts, 3 risks and 4 opportunities in the 2024 double materiality assessment. As a result, we concluded the topic Climate Change to be material from impact perspective. From financial perspective, currently (on the short- and medium term) we consider climate change as material topic due to the high likelihood and high magnitude of the financial effect.

The list of material impacts, risks and opportunities are described in the tables below:

Table IM-01: Contribution to the transition to low carbon economy

Severity	Significant positive impact
Scope	CEE
Likelihood	Actual impact
Description	MOL Group has long-standing experience in conventional energy production, however, it is exploring opportunities arising from low carbon energy solutions & dedicated towards decarbonisation of its own operations and its value chain to contribute to the energy transition of the CEE region. One of the key pillars of MOL Group's "Shape tomorrow" strategy is investing in green electricity generation & electric car charging, increasing energy efficiency of production, using and producing low-carbon fuel alternatives such as biogas & biofuels, and utilising modern technologies such as CO2 injection for Enhanced Oil Recovery to reduce carbon footprint and increase productivity.
Mitigation actions & remendability	MOL Group's mitigation actions include ensuring business continuity by developing and maintaining comprehensive contingency plans, investing in emerging green technologies to promote sustainability, and exploring innovative business solutions to adapt to evolving market demands.
Time horizons	MOL Group's contribution to a low carbon economy is integral part of its long-term strategy, as the company's dedicated to become a net-zero carbon by 2050.
Relevance in the value chain	Transition to low carbon economy has a material impact of MOL Group's industrial operations, including New and Sustainable Businesses (hereinafter: NSB), Consumer Services and in the Circular Economy Services business segments.

Table IM-02: Effect on climate

Severity	Significant negative impact
Scope	Global
Likelihood	Actual impact
Description	MOL Group's main activities are related to the oil and gas industry, associated with high greenhouse gas (GHG) emissions during its own operations (Scope 1), through its upstream value chain (Scope 2 & 3) and through its sold products (Scope 3). In 2024, MOL Group's total GHG footprint (Scope 1, 2 and 3) was 63.6 mn tonnes of CO2eq. MOL Group acknowledges that via its GHG footprint it contributes to climate change, affecting both people and the environment.
Mitigation actions & remendability	MOL Group's mitigation actions include GHG emission reduction actions such as transitioning to low-carbon solutions and implementing energy efficiency projects. Generally, effect of GHG emissions are considered irremediable. MOL Group is dedicated to reduce its emissions and the exploration of carbon capture technologies (see OP-5) to contribute to rectifying the impact of emissions on the longer term.
Time horizons	MOL Group aims to reduce its GHG emission gradually, by 25% until 2030 (compared to 2019) and reach net zero emissions by 2050. Until 2050, we expect the impact to be material.
Relevance in the value chain	Climate change is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical, Gas Midstream, New and sustainable businesses, Consumer Services and in the Circular Economy Services business segments.

Table RK-01: Increased cost of greenhouse gas emissions

Type	Market/technology and legal risk
Likelihood	Very high
Magnitude of financial effect	High
Description	Existing (ETS I.) and emerging (ETS II., CBAM, Methane Regulation) legislation in relation to the European Green Deal leads to increased costs for companies for their GHG emissions. Fluctuation in the price of emission quotas leads to uncertainties and poses risk to the profitability of MOL Group's core activities.
Related impact & dependencies	An integrated oil&gas company (O&G) Mol Group's current business model is highly dependent on fossil fuels both during its energy intensive industrial operations (drilling, oil refining, petrochemical production) which lead to significant Scope 1 & 2 GHG emissions, and also due to Scope 3 value chain emissions associated with sold fuels and polymers. This causes exposure to climate mitigation regulation. Because of its current business model, Mol Group has a significant impact on climate change (IM-1).
Mitigation actions	To reduce the aforementioned risk stemming from dependency on fossil fuels and impact on climate change, MOL Group has a detailed Climate Transition Plan (see DR E1-1). To ensure the business continuity while transitioning away from fossil fuels, MOL Group in engaged in providing various low carbon solutions (see IM-2) and puts great emphasis on improving energy efficiency and fuel switch (see DR E1-3). Green transition also opens new business fields which the company is actively pursuing – see Mol Group's Shape Tomorrow strategy and for more information.
Financial effect & time horizons	As of 31 December 2024, the Group has recognised a provision of HUF 72,464 million for the shortage of emission quotas. For more details, see MOL Group's Financial statement (Non-Financial Assets and Liabilities – 16. Provisions). On the long term, we expect the price of quotas to increase due to the shrinking number of total free allocated quotas. We consider the topic climate change mitigation as financially material due to the significant amount of related investment plans on short, medium and long-term as well.
Relevance in the value chain	Climate change is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical, Gas Midstream, New and sustainable businesses, Consumer Services and in the Circular Economy Services business segments.

Table RK-02: Risks related to new energy efficiency and renewable energy regulations

Type	Market/technology and legal risk
Likelihood	High
Magnitude of financial effect	High
Description	EU's ambitious regulatory requirements related to the use of renewable energy and energy efficiency puts pressure on the oil & gas sector to adapt new, often immature and high-cost technologies. Compliance requires high CAPEX thus poses risks to short-term competitiveness. On the other hand, improving energy efficiency and adaptation of renewables are not only crucial the realise emission reduction targets, but also contributes to more efficient operations and potential revenue sources on the long-term.
Related impact & dependencies	The source of the risk is that as an integrated oil&gas company (O&G), MOL Group's current business model is highly dependent on fossil fuels during its energy intensive industrial operations (drilling, oil refining, petrochemical production), which leads to exposure to regulation aimed at promoting renewable energy sources. Because of its current business model, Mol Group has a significant impact on climate change (IM-1).
Mitigation actions	To reduce the aforementioned risk stemming from dependency on fossil fuels and impact on climate change, MOL Group has a detailed Climate Transition Plan (see DR E1-1). To ensure the business continuity while transitioning away from fossil fuels, MOL Group in engaged in providing various low carbon solutions (see IM-2) and puts great emphasis on improving energy efficiency and fuel switch (see DR E1-3). Green transition also opens new business fields which the company is actively pursuing – see Mol Group's Shape Tomorrow strategy for more information.
Financial effect & time horizons	Albeit the financial risks associated with exposure to regulation aimed at promoting renewable energy sources (mainly RED III and EED) is only expected to materialise after 2030 (long-term), the MOL Group is already investing significant amounts to increase the use of renewable energy and energy efficiency, therefore the financial magnitude of these actions are important also on the short- and medium term.
Relevance in the value chain	Climate change is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical, Gas Midstream, New and sustainable businesses, Consumer Services and in the Circular Economy Services business segments.

Table RK-03: Climate change induced physical risks & other natural disasters

Type	Physical risk
Likelihood	Low
Magnitude of financial effect	Low
Description	Identified physical risks include a combination of both acute risks (extreme rainfall and flooding), as well as chronic risks (extreme heat, fluctuating water levels and drought). If any of these events were to occur, they could have an adverse effect on MOL Group's assets, operations and staff. MOL Group has incurred and is likely to continue incurring additional costs to protect its assets, operations and staff from physical risks. To the extent such severe weather events or other climate conditions increase in either frequency, severity or both, MOL Group may be required to adjust its operations and incur costs that could adversely affect its financial position. See more information in our Integrated Risk Management Report (TCFD disclosures).
Related impact & dependencies	The source of this risk is external, and not related to dependencies or impacts.
Mitigation actions	MOL Group operates Risk Engineering program, where the potential impacts of water-related events analysed in main Downstream sites. Actions related to climate change adaptation and water supply issues are elaborated in DR E1-3 and DR E3-2.
Financial effect & time horizons	The financial effect of this risk category relates to the asset damage & lost production due to the aforementioned events. Other relevant costs include the cost of insurance and the expanse of investments to adopt & mitigate potential losses – see DR E1-3. Since the majority of MOL Group's assets are heavy industry equipment, they are relatively resilient even to extreme weather events. Operational hinderances due to natural phenomena (such as lack of industrial water supply) are also rare. Therefore, physical risks are only considered (potentially) financially material on the long term.
Relevance in the value chain	Climate change is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical, Gas Midstream, New and sustainable businesses, Consumer Services and in the Circular Economy Services business segments.

Table OP-01: Green hydrogen production

Maturity at MOL Group	Pilot
Magnitude of financial effect	High
Description	Green hydrogen is expected to play a major role in heavy industry and transportation decarbonization. MOL Group can leverage existing infrastructure and expertise in large-scale industrial processes to produce green hydrogen via electrolysis using renewable energy sources, supporting the transition to a low-carbon economy. MOL inaugurated its first 10 MW capacity green hydrogen plant in Százhalombatta and announced planned investments in Slovakia and Croatia.
Related impact & dependencies	MOL Group's business model requires significant amount of energy – with increasing emphasis on renewable sources. Green hydrogen production supports the regulatory compliance with both carbon reduction schemes (such as EU ETS) and renewable energy use (RED III), therefore contributes to the mitigation of related impacts and risks (see IM-01, IM-02, RK-01, RK-02).
Financial effect & time horizons	This opportunity is already pursued by MOL Group since the inauguration of facility in Százhalombatta (EUR 22 million CAPEX), which will produce ca. 1600 tonnes of green hydrogen annually. Therefore, it is considered financially material in all time horizons.
Relevance in the value chain	Green hydrogen production is material impact of MOL Group's industrial operations, including the Refining, Petrochemical and New and Sustainable Businesses.

Table OP-04: Renewable energy production

Maturity at MOL Group	Pilot
Magnitude of financial effect	High
Description	MOL Group is currently implementing multiple renewable energy projects to increase the share of green electricity in our overall energy consumption. For instance, renewable electricity will be used to cover the consumption growth of green hydrogen (H2), which is utilized to decarbonize the energy consumption of owned plants and sites or sold to third parties. The current portfolio of 110 MW is planned to scale up in synergy with current and future electricity consumption (up to 2500 GWh RE consumption by 2030). While solar projects are expected to provide the majority of production, complementary renewable sources (such as geothermal) and storage solutions are also considered.
Related impact & dependencies	MOL Group's business model requires a significant amount of energy, with an increasing emphasis on renewable sources. Green energy is essential for regulatory compliance with carbon reduction schemes

	(such as the EU ETS) and renewable energy use (RED III), thereby contributing to the mitigation of related impacts, risks and costs (i.e. IM-01, IM-02, RK-01, RK-02).
Financial effect & time horizons	The current operation of 110 MW of solar production is considered the first step, making the opportunity financially material only in the mid- and long term. The scale-up of the portfolio is planned in synergy with the company's current and future electricity consumers, with an organic CAPEX of USD 700 million between 2025 and 2030.
Relevance in the value chain	Renewable energy production is material impact of MOL Group's industrial operations, including the New and Sustainable Businesses and others.

Table OP-05: Leveraging subsurface expertise (geothermal, lithium and Carbon Capture and Storage (CCS)

Maturity at MOL Group	Assessed/Planned
Magnitude of financial effect	Medium
Description	Oil and gas expertise in subsurface exploration can be applied to geothermal energy production, lithium extraction for batteries, and implementing carbon capture and storage technologies to mitigate greenhouse gas emissions. MOL Group has been in the process of planning to utilize geothermal energy as a renewable energy source. The project is still in the exploration phase both in Hungary and Croatia, but has the same benefits as presented in CCS is also in the exploration phase, MOL Group is identifying suitable storage sites. The technology has the potential to become a key enabler of achieving net zero emissions targets, especially in hard-to-abate industries MOL Group is analyzing the opportunity of Direct Lithium Extraction to extract a valuable metal from underground, which is a key material for green-tech solutions.
Related impact & dependencies	Geothermal energy, lithium mining and CCS technologies are a key enablers of becoming net zero for the industry, therefore expected to play an increasingly important role in Mol Group's low carbon transition, thereby contributing to the mitigation climate change of related impacts, risks and costs (i.e. IM-01, IM-02, RK-01, RK-02).
Financial effect & time horizons	Since large scale implementation of these technologies are only expected after 2030, the financial effect is considered „medium".
Relevance in the value chain	Leveraging subsurface expertise is material impact of MOL Group's industrial operation, specifically in the Upstream business segment.

Table OP-09: Energy efficiency projects

Maturity at MOL Group	Implemented at scale
Magnitude of financial effect	High
Description	Investment in energy efficiency and electrification initiatives optimise operations, reduce energy consumption, and lower greenhouse gas emissions – consequently, it contributes to the competitiveness and profitability of MOL Group. Energy efficiency improvement is relevant in all business activities with focus on the refining segment, where to goal is to reach second quartile in Solomon Energy Intensity Index.
Related impact & dependencies	Energy efficiency investments support the mitigation of climate related impacts and risks (see IM-01, IM-02, RK-01, RK-02) by reducing the carbon footprint of the company.
Financial effect & time horizons	MOL Group expects investments in high asset efficiency to deliver USD 150mn savings by 2025 via energy efficiency, maintenance, and logistics on track to secure additional cash flow for strategic investments. The opportunity is considered material on all time horizons.
Relevance in the value chain	Energy efficiency projects is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical and New and Sustainable Businesses.

The climate related opportunities has strong interconnections with other environmental and social topics, such as resource use and circular economy, consumers and end-users. Please see these described in the respective chapters:

- OP-06: Sharing economy services (Chapter S4)
- OP-07: E-charging network (Chapter S4)
- OP-08: Waste-based fuel usage and production (Chapter E5)
- OP-10: Sustainable aviation fuel (Chapter E5)
- OP-11: Biogas production (Chapter E5)

POLICIES RELATED TO CLIMATE CHANGE MITIGATION AND ADAPTATION

/E1-2/

ESRS	Disclosure Requirement E1-2
GRI	Several GRI 3 3-3 c
IFRS	IFRS S2.25(a) IFRS S2.25(b)

The following section outlines MOL Group's policies for managing material impacts, risks, and opportunities related to climate change mitigation and adaptation. MOL Group recognises the need to simultaneously strengthen the supply security and accelerate the green energy transition. Our commitment to mitigate the impact of our operations on climate change (IM-01, IM-02), and approach to manage financial effects and risks associated with GHG emission related regulations and adaptation to climate change (RK-01,RK-02) whilst seeking business opportunities in the area of green transition (OP-1, OP-4 , OP-7, OP-9, OP-10, OP-11) is expressed at all layers of our policies:

1. **Strategic level:** The long-term business strategy of MOL Group aims at transforming our traditional fossil-fuel-based operations into a low-carbon, sustainable business model.
2. **Business unit level:** Business specific processes related to climate change mitigation and adaptation are outlined in each business unit's respective Area Books.
3. **Environmental regulations:** MOL Group's approach to handling Health, Safety and Environment related impacts and risks of climate change are outlined in the overarching Group-level internal regulations covering all activities with environmental impact.

1. Strategic level: Shape Tomorrow Strategy

The overarching climate strategies and policies of MOL Group are outlined in its **Shape Tomorrow Strategy** Review, approved by the Board in 2024. These strategies are driven by the company's commitment to achieving long-term climate neutrality and integrating sustainability into its operations. Key focus areas include:

- **Climate Neutrality Commitment**: Aiming for net climate neutrality by 2050, MOL Group has set progressively ambitious targets for reducing greenhouse gas emissions, demonstrating an even stronger focus on tackling climate change.
- **Sustainable Transformation in Downstream Operations**: Supporting the vision to become a sustainable chemicals company and a low-carbon mobility provider, MOL Group is dedicated to reducing its operational carbon footprint and striving toward net-zero emissions.
- **Advancing New and Sustainable Businesses**: Driving emission reductions and transition to green economy by accelerating the development of biogas and hydrogen value chains and expanding activities in recycling and material compounding.
- **Renewable Energy and Circular Economy**: Prioritizing the use of renewable electricity and advancing waste management operations to supply feedstock for the energy industry, contributing to both decarbonization and resource efficiency.
- **Green and Integrated Mobility Solutions:** Transforming into a digitally advanced provider of sustainable mobility services, MOL Group aims to meet evolving consumer and market demands by integrating green mobility solutions, such as low-emission transportation options and innovative, environmentally friendly mobility services, into its offerings. This transition supports a broader commitment to reducing carbon emissions in the transportation sector.
- **Decarbonizing Exploration and Production (E&P)**: Leveraging expertise in areas such as geothermal energy and lithium projects, complying with methane regulations, and exploring carbon capture and storage (CCS) technologies to support the Group's climate goals.

These commitments are also transposed into time-bound, measurable targets – as outlined in the Transition Plan section of this chapter.

2. **Business unit level:**

MOL Group's key business unit define their approach to climate change mitigation and sustainable development in their respective Area Books, outlining relevant processes and principles:

Downstream Production Area Book

The primary objective of Downstream Production is to convert raw materials into high-quality products in a safe, sustainable, reliable, and efficient manner, in line with the Shape Tomorrow Strategy. To achieve our hydrocarbon refining and petrochemical production goals, we focus on providing the necessary resources in a way that ensures operational safety and environmental protection:

- Energy Management: The key priority is improving energy performance, reducing GHG emissions, and optimizing energy production and consumption at the site level. This is achieved through accurate planning aligned with production needs, as well as corrective and efficiency measures to ensure continuous improvement.
- Environmental Compliance: Downstream Production units operate in accordance with strict environmental regulations to keep emissions within prescribed limits. Technologies and processes are designed to prevent major environmental spills that could result in groundwater, air, or soil pollution.

Renewables & Energy Efficiency Management Area Book

This framework establishes MOL Group's Renewables & Energy Efficiency Management System in line with ISO 50001 standards. The objective is to implement a systematic approach to improving energy efficiency and integrating energy management practices across the organization:

- **Energy Performance:** Continuous improvement in energy efficiency is pursued to reduce costs, enhance competitiveness, and lower GHG emissions.
- **Knowledge Sharing & Awareness:** The principles of energy efficiency are promoted across the Group through training, workshops, and internal communication to encourage energy-conscious project development and decision-making.

Circular Economy Services Area Book

MOL Group aims to be a key player in the circular economy within the Central and Eastern European region. This is a model across value chains and industries, redefining product design, production and consumption, and it aims to reduce waste and resource use by transforming the lifecycle of products. Circular economy is based on three principles, driven by design eliminating waste and pollution; circulating materials and products at their highest value; and regenerating nature. The Area Book defines the processes embedding these principles into business operations:

- **Regulatory Compliance & Investment:** Circular Economy Services (CES) oversees compliance with EU and national waste management directives, ensuring MOL meets Extended Producer Responsibility (EPR) obligations efficiently. Investment projects are planned and executed according to MOL Group's project management principles to align with corporate and regulatory sustainability goals.
- **Recycling & Waste Management:** The Group is expanding its petrochemical portfolio with recycled plastic feedstocks and is committed to energy recovery from non-recyclable waste through incineration.

3. **Environmental regulations:**

The Group HSE and Social Impact Policy declares MOL Group's public commitment to acting responsibly regarding the health, safety, environmental (HSE), and social impacts of our daily operations. This commitment includes improving asset integrity, preventing incidents of all kinds, and maintaining high standards in emergency response. We are dedicated to reducing our environmental footprint, protecting natural resources, and supporting international efforts to address climate-change related risks. MOL Group also strives to create positive impacts in the communities where we operate, while eliminating negative effects on society as a whole.

All of our employees and contractors have a responsibility to maintain high HSE standards and management must take a leadership role in this. Accountability for implementing the policy lies primarily with the top management, local CEOs or Managing Directors, supported by the Group HSE Senior Vice President and local HSE Managers.

This overarching policy applies to all MOL Group activities, extending across both operated and, where feasible, non-operated joint ventures. It spans the entire MOL value chain and geographical reach, affecting a wide range of stakeholders, including employees, contractors, visitors, and surrounding communities. It specifically addresses all stages of project development, from design through decommissioning, ensuring HSE principles are embedded throughout.

This commitment is integrated into MOL Group's corporate governance systems on multiple levels:

Health Safety and Environment Area Book is the highest level process-based regulation in the field of HSE management, focusing on end-to-end processes describing the operation model and the interactions within and outside the organisation.

MOL Group Health, Safety & Environment Management System (Current version: V5, hereinafter: HSE MS) is a Process Description regulating all processes listed in Health Safety and Environment Area Book, establishing a comprehensive framework that aligns health, safety, environmental, and community impact guidelines with MOL's strategic business objectives across 12 key elements**.** The table below gives the description of elements which are relevant for the purposes of this report, indication on how they related to managing the identified material IROs and reference to the relevant parts of this report:

Element	Description	Relevant IROs
ELEMENT 1: Leadership, Commitment & Accountability	Management, workforce and contractors understand their accountabilities aligned with job responsibilities, authority levels and performance objectives, and they demonstrate leadership and commitment to the Group-level HSE and Social Impact Policy through visible and effective HSE management.	
ELEMENT 2: Risk & Change Management	Systems are in place to identify, assess, manage, regularly review and document HSE-related hazards and risks associated with MOL Group activities to prevent or reduce the likelihood and/or consequences of incidents. Planned and unplanned changes to MOL Group activities are identified and properly managed from a risk perspective.	All HSE-related

Element	Description	Relevant IROs
ELEMENT 3: Competence, Training & Behaviour	Employees, contractors and third parties are aware of relevant HSE requirements, hazards, risks and controls, and are competent at conducting their activities and behave responsibly. Competencies are regularly assessed.	IM-13, IM-14, IM-15, RK-04
ELEMENT 4: Contractor Management	Contractors are assessed for their capabilities and competencies and selected to perform work for / on behalf of MOL Group where they are monitored to ensure their HSE performance is in alignment with MOL Group requirements.	
ELEMENT 5: Design & Construction	The assessment and management of process and HSE risks are an integral part of project design and construction, enabling sound HSE performance throughout the planning, construction and commissioning of facilities.	IM-06
ELEMENT 6: Operational and occupational safety	Operational safety: Maintain operational reliability and integrity throughout the whole lifecycle of our assets by use of clearly defined and documented operational and structured maintenance and inspection programs. This requires effective procedures, reliable safety-critical equipment, and adequate and competent human resources who consistently execute these procedures and practices. Occupational safety: We continuously maintain occupational safety by use of clearly defined and documented operational and structured work safety programs. This requires effective procedures and training of staff as well as reliable, adequate and competent human resources who consistently support these procedures and practices, while protecting the health of employees, providing adequate relevant medical services, and promoting healthy lifestyles.	IM-13, IM-14, IM-15, RK-04
ELEMENT 7: Environmental Stewardship	Our environmental footprint is reduced, natural values are protected, and climate-change related risks are addressed. Environmental issues are addressed and controlled, consistent with policy, regulatory requirements and business plans. Environmental performance (including emissions, discharges and wastes) is tracked and stewarded to meet performance goals.	IM-01, IM-02, IM-03, IM-04, IM-05, IM-06, IM-08, RK-01, RK-02, RK-06, RK-05
ELEMENT 8: Information & Documentation	All the information required to ensure accuracy and consistency when applying risk controls is documented and systematically maintained. The HSE impacts of MOL Group's products and services are assessed, managed and communicated to customers and users to enable their responsible use. The introduction of new products/substances into manufacturing or operational processes is controlled.	IM-04
ELEMENT 9: Stakeholder & Community Relations	Open, proactive and effective HSE communication and consultation is maintained with stakeholders regarding the HSE aspects of all of our business activities.	IM-17
ELEMENT 10: Incident Management	Systems are in place to ensure that all HSE incidents are reported, recorded, investigated and analysed in a timely manner to prevent recurrence and improve performance. Corrective and preventive actions are defined, their effectiveness is evaluated and learning outcomes are shared.	RK-04
ELEMENT 11: Emergency Preparedness & Response	Plans, procedures and resources are in place to effectively respond to emergency situations, to protect people/employees, the environment (including the workplace) and the public, and to preserve the company's assets and reputation.	RK-04
ELEMENT 12: Assurance, Monitoring & Improvement	HSE performance and systems are monitored, audited and reviewed to identify trends, measure progress, assess compliance and drive continuous improvement. HSE Planning is an integral part of business planning with strategic objectives, goals and annual targets to drive performance improvement.	All HSE-related

HSE MS is applicable for all types of operations and projects; and manages operational integrity through the lifecycle of the assets. Requirement are applicable not only to MOL Group's own employees, but to contractors and subcontractors as well. In case of newly joining (acquired) companies an integration period of maximum three years is considered depending on maturity of its HSE management system, in order to catch up with the relevant Group level requirements. During this period, general principles of the HSE MS are applicable to the companies, but their HSE performance is not included into overall MOL Group HSE performance.

Element 7 - Environmental Stewardship describes the processes related to managing GHG emission related matters, including MOL Group's approach to reduce GHG emissions to minimise our impact on climate change and manage financial effects and risks associated with GHG emission related regulations and adaptation to climate change. Key commitments include:

- Eliminating routine flaring during normal operations, while non-routine flaring (e.g. during start-ups, shutdowns, emergency) is minimized. Routine venting is not an acceptable. Venting shall only be allowed in case of an emergency or malfunction and where it is feasible flaring has to be preferable to venting.
- Leak Detection and Repair (LDAR) program is in place for accurately quantifying and reducing the emission from fugitive sources.
- Greenhouse Gas Emissions (GHG) management system is in place:
  (a) Methane, ETS I and II: local-level process descriptions are in place to ensure legal compliance.
  (b) In each high GHG intensity businesses GHG reduction plans are in place and executed to ensure carbon neutrality.
  (c) Compliance with the CBAM regulation is ensured.

The goal of the GHG management system is to help verify that the installations and regulated entities of MOL Group that are subject to EU ETS system (I and II) comply with legal requirements. The document details the process steps to monitor, calculate, verify, plan, forecast the GHG emissions of relevant operators subject to EU ETS I and ETS II. ETS quota inventory management processes are maintained to ensure limitation on CO2 inventories while also providing flexibility for Emitting Entities managing their business models. For more details on tasks and responsibilities, please refer to *Detailed rules on Environmental Stewardship (Element 7) - CO2 Management*, which is an Appendix to the HSE MS.

METRICS RELATED TO ENERGY CONSUMPTION AND MIX

/E1-5/

	UNIT OF MEASURE	2024	2023	ESRS
TOTAL ENERGY CONSUMPTION	MWh	27 183 633	27 924 988	E1-5_01, E1-5_19
Direct energy consumption	MWh	24 217 712	25 132 604	E1-5_16
o/w crude oil and petroleum products	MWh	16 408 214	18 094 965	E1-5_11
o/w natural gas	MWh	8 040 921	7 037 639	E1-5_12
Indirect energy consumption	MWh	2 734 498	2 792 384	E1-5_14
o/w renewable energy	MWh	102 181	140 109	E1-5_07
ENERGY INTENSITY (from activities in high climate impact sectors)	MWh/million HUF	2.96	-	

All energy consumption of MOL Group is accounted as activities in high climate impact sectors (therefore indicators related to high-climate sectors are not indicated separately). MOL Group's total energy consumption was 3.64% lower in 2024 compared to 2023. Both the direct energy consumption (fuels combusted in boilers, furnaces, heaters, turbines, flares, incinerators, generators, and company-owned vehicles and machines) and the indirect energy consumption (intermediate energy, i.e., heat, steam and electricity purchased from outside MOL Group) were lower.

MOL Group's energy intensity from activities in high climate impact sectors was 2.96 MWh/mn HUF in 2024. Since MOL Group does not have material revenues from sectors which are not considered high climate impact, Total Net sales are taken into account from the Consolidated Statement of Profit or Loss for the purpose of this calculation. Similarly, total energy consumption as presented in the above table is equivalent to the total energy consumption in high climate impact sectors.

As stated in the Shape Tomorrow Strategy, MOL Group is dedicated towards diversification of its energy sources towards renewable sources, however, its current business model is heavily reliant on fossil fuels. 67.75% of direct energy consumption in 2024 has been sourced from crude oil and petroleum products including, fuels distilled from crude oil, including LPG, compressed natural gas, LNG, butane, propane, ethane and refinery fuel gas used for the energy-intensive production processes (e.g., oil refining, petrochemical production); and gasoline, autogas, diesel used for company owned vehicles and for machines. 33.20% of consumed energy is from natural gas purchased and produced.

The share of renewable energy both in consumption and production remained below 0.5% (disclosed number is based on estimation as majority of the renewable energy production comes from solar panels placed in office buildings and service stations, which are out of the scope of the energy management system of MOL Group due to negligible energy intensity compared to industrial production) – even with new solar panels acquired at multiple locations in 2024.

METRICS RELATED TO GHG EMISSIONS

/E1-6/

GREENHOUSE GAS EMISSIONS	UNIT OF MEASURE	2024	2023	ESRS
Gross Scope 1 GHG emissions	**mn t CO2-eq**	**6.38**	**6.64**	E1-6_07
o/w Consolidated accounting group	mn t CO_2-eq	6.37	-	E1-6_02
o/w Operational control group, excl. Consolidated accounting group	mn t CO_2-eq	0.01	-	E1-6_02
o/w Upstream	mn t CO_2-eq	**0.86**	**0.91**	E1-6_03
o/w Downstream	mn t CO_2-eq	**5.41**	**5.69**	E1-6_03
o/w Refining	mn t CO_2-eq	3.14	3.29	E1-6_03
o/w Petrochemicals	mn t CO_2-eq	1.25	1.29	E1-6_03
o/w Power and Heat Generation	mn t CO_2-eq	0.98	1.07	E1-6_03
o/w Other downstream	mn t CO_2-eq	0.04	0.04	E1-6_03
o/w Midstream	mn t CO_2-eq	**0.08**	-	E1-6_03
o/w Others	mn t CO_2-eq	**0.03**	**0.04**	E1-6_03

GREENHOUSE GAS EMISSIONS	UNIT OF MEASURE	2024	2023	ESRS
Percentage of Scope 1 GHG emissions from regulated emission trading schemes	%	**89.85**	**88.28**	E1-6_08
Gross location-based Scope 2 GHG emissions	mn t CO_2-eq	**0.65**	**0.61**	E1-6_09
o/w Consolidated accounting group	mn t CO_2-eq	0.64	-	E1-6_02
o/w Operational control group, excl. Consolidated accounting group	mn t CO_2-eq	0.01	-	E1-6_02
Gross market-based Scope 2 GHG emissions	mn t CO_2-eq	**0.92**	**0.81**	E1-6_10
o/w Consolidated accounting group	mn t CO_2-eq	0.90	-	E1-6_02
o/w Operational control group, excl. Consolidated accounting group	mn t CO_2-eq	0.02	-	E1-6_02
Total GHG Emissions Scope 1+2 – by business	mn t CO_2-eq	**7.03**	**7.25**	E1-6_03
Total GHG emission of Upstream (Scope 1 + Scope 2)	mn t CO_2-eq	0.92	0.97	E1-6_03
Total GHG emission of Downstream (Scope 1 + Scope 2)	mn t CO_2-eq	5.93	6.16	E1-6_03
o/w Total GHG emission of Refining (Scope 1 + Scope 2)	mn t CO_2-eq	3.33	3.46	E1-6_03
o/w Total GHG emission of Petrochemicals (Scope 1 + Scope 2)	mn t CO_2-eq	1.47	1.50	E1-6_03
Total GHG emission of Midstream (Scope 1 + Scope 2)	mn t CO_2-eq	0.08	-	E1-6_03

In 2024, our total Scope 1&2 GHG emissions decreased by around 5% compared to last year. This reduction was observed across all business segments and aligns with our transition plan, which included various energy efficiency and electrification projects from Upstream to Retail stations.

In the Upstream segment, flaring was eliminated at certain sites, which reduced gas consumption. At the Danube refinery, fuel oil usage was decreased through technical upgrades and optimized furnace operations. Energy consumption is monitored at the device level, focusing on operational energy use reduction. For instance, we optimize steam production at steam generators using Visual Mesa Software, and flaring is monitored daily. At Slovnaft, extensive turnarounds during 2024 resulted in total GHG emissions being less than 250 kt compared to 2023.

In MOL Petrochemicals, major energy efficiency projects were completed in 2024, including the introduction of a steam tracking system and compressor bypass optimization. Methane combustion in the HRSG system was optimized, reducing the plant's fuel consumption and Scope 2 emissions compared to 2023. To reduce venting, we focused on minimizing start-up losses by applying lessons learned and taking definitive actions with the production and energy management organization.

For our retail stations, energy and electricity consumption are regularly monitored, with stations equipped with LED lights and electrified heating methods. However, the primary driver for emission reduction was not only efficiency and electrification projects. In cases like Slovnaft, extensive turnarounds during 2024 were the main reason for the reduction.

CAT	GHG EMISSIONS SCOPE 3	UNIT OF MEASURE	2024	2023	ESRS
	Total GHG Emissions Scope 3	tonnes CO_2-eq	**56 538 921**	**55 767 391**	E1-6_11
1	**Purchased goods and services**	tonnes CO_2-eq	**1 854 922**	**1 827 952**	
	o/w purchased crude oil	tonnes CO_2-eq	1 393 206	1 348 802	
	o/w purchased biofuel	tonnes CO_2-eq	461 716	479 151	
2	**Capital Goods**	tonnes CO_2-eq	**18 321**	**20 287**	
3	**Fuel and Energy Related Activities**		*not measured (not material)*		
4	**Upstream Transportation and Distribution**	tonnes CO_2-eq	**240 478**	**226 209**	
5	**Waste Generated in Operations**		*not measured*		
6	**Business travel**		*not measured (not material)*		
7	**Employee Commuting**		*not measured (not material)*		
8	**Upstream Leased Assets**		*not applicable*		
9	**Downstream Transportation and Distribution**		*accounted under Scope 1*		
10	**Processing of Sold Products**	tonnes CO_2-eq	**873 417**	**1 005 048**	
11	**Use of sold products**	tonnes CO_2-eq	**52 430 648**	**51 478 543**	
	o/w sold refinery products (excl. naphtha)	tonnes CO_2-eq	48 546 393	47 426 000	
	o/w sold natural gas	tonnes CO_2-eq	3 884 255	4 052 543	
12	**End-of-life treatment of sold products**	tonnes CO_2-eq	**651 154**	**752 622**	
13	**Downstream Leased Assets**		*not applicable*		
14	**Franchises**		*not applicable*		
15	**Investments**	tonnes CO_2-eq	**469,982**	**456,728**	
	Total GHG (Scope 1 + Scope 2 location-based + Scope 3)	mn t CO_2-eq	**63.57**	**63.01**	E1-6_11
	Total GHG (Scope 1 + Scope 2 market-based + Scope 3)	mn t CO_2-eq	**63.84**	**63.22**	E1-6_13

In 2024, our Scope 3 emissions increased by around 1.4% compared to last year. This rise was primarily driven by higher purchases of crude oil, increased upstream transportation and distribution, and notably, the use of sold refinery products excluding naphtha. The 5% growth in our fuel product sales was a major contributor to this increase. On the positive side, we achieved notable reductions in certain Scope 3 categories compared to the previous year, including the processing of sold products (polymers), natural gas sales, and the end-of-life treatment of sold products (polymers).

Methodologies and significant assumptions behind metric

MOL Group's calculation methodology for Scope 1 and 2 GHG emissions is regulated by the Group's Reporting Handbook. The Group report carbon dioxide (CO2) and methane (CH4) emissions as part of its Scope 1 and 2 reporting.

Regarding Scope 1 calculation, there are two equally acceptable methods for calculating emissions from sources (energy, process and flares related), and the choice of method depends on the information available for input. Scope 1 CO2 emissions under the EU ETS are also externally verified.

One of the options is using the energy data. For each source or operation, the total consumption of fuel within the assessment period of each different fuel type is recorded. Where fuel property data is available, the fuel consumed is converted to an equivalent energy input in GJ using the average net calorific value of the fuel over the period. The emission of carbon dioxide is then calculated by multiplying the

total energy input for each fuel type by a carbon dioxide emission factor for that fuel. The emission factor should be calculated based on actual fuel properties. Where fuel property data is not available, the IPCC emission factors should be used. This default factors should only be used where fuel data is not available and in preference to reporting no data.

The second option is using the mass data. In this case, the emission of carbon dioxide is calculated by multiplying the mass of fuel burnt by the carbon content of the fuel burnt, on the basis that all carbon is emitted as carbon dioxide. For gaseous fuel, the carbon content should include any carbon dioxide in the fuel. If the fuel flow is not metered, the fuel consumption should be estimated from the equipment load data such as specific fuel consumption of a gas turbine or the thermal output of a boiler. The emission of carbon dioxide is calculated from the mass of gas flared and the carbon content of the flared gas (including any inorganic carbon). The calculation should be done on the basis of 100% conversion to CO2, and no correction to flare efficiency. The accuracy of the estimate is dependent on the reliability of the flow and composition data. Estimates of gas flared are generated using plant logs and engineering calculations based on process design information.

Scope 1 methane emission calculation has further specificities. Methane emissions could be due to venting, flares, process fugitives, combustion, chemical or refinery processes. In case of venting, the preferred method of methane determination is to carry out engineering estimates based on as much direct field measurement as is practical, including pressures, duration and number of venting operations, physical dimension and types of valves and chokes through which the venting is controlled, grabbing of samples of the gas being vented for analysis of the methane content, and flash calculations or correlation based on process simulations calculation. Regarding flares, methane is estimated using the assumption that the composition of methane in the emitted hydrocarbon is the same of the methane content of the flared hydrocarbons. The methane component of the leaked gas should be determined from the composition of fluids within the system. The basic assumption is that the leaking fluid has the same composition as the contained fluid.

Scope 2 emissions are calculated from information about the energy (steam and electricity) imported and exported across a facility boundary. Other indirect emissions, such as from offsite waste disposal, are specifically excluded. The emission of CO2 is obtained by multiplying the net amount of energy imported by a CO2 emission factor. The carbon emission factor to be applied depends on the source of the imported energy. The intent is to account for the CO2 emissions from third parties as a consequence of generating energy for MOL Group.

Reporting boundaries, scope of calculation

- MOL Group is calculating and reporting GHG (scope 1 and 2) emissions that are arising from wholly owned and/or operated assets, excluding legal entities with only office/administrative activities.
- Scope 1 emission (direct emissions) are direct GHG emissions from sources that are owned or controlled by MOL Group. Scope 1 can include emissions from fossil fuels burned on site, emissions from entity-owned or entity-leased vehicles, and other direct sources.
- Scope 2 emissions (indirect emissions) are indirect GHG emissions resulting from the generation of electricity, heating and cooling, or steam generated off site but purchased by the entity, and the transmission and distribution (T&D) losses associated with some purchased utilities (e.g., chilled water, steam, and high temperature hot water).
- Scope 3 emissions include indirect GHG emissions from sources not owned or directly controlled by MOL Group but related to the entity's activities. They are a consequence of the activities of the company, but occur from sources not owned or controlled by the company. Some examples include third party deliveries, business travel activities and use of sold products and services

Calculation methodology:

Various methods are used for each categories included in our Scope 3 calculation, all based on GHG protocol. From our subsidiaries over which we have operational control, the data for following categories of Scope 3 are collected:

- Category 1 (Purchased biofuel & crude oil)
- Category 2 (Capital goods)
- Category 4 (Upstream transportation and distribution)
- Category 10 (Processing of sold polymers)
- Category 11 (Use of sold natural gas; use of sold refinery products)
- Category 12 (End-of-life treatment of sold polymers)
- Category 15 (Investments)

Categories included in Scope 3 GHG emission calculation:

- **Category 1 –Purchased Goods and Services** (bio-fuel for blending and purchased petroleum product for using as feedstock): MOL Group includes in its Scope 3 calculation the footprint of the externally produced crude oil purchased by MOL for processing in the Group's refineries. MOL Group also includes the gross footprint (GHG removals not included) of the biofuel produced externally and purchased for the blending into the Group's fuel. In line with EU regulation, each biofuel purchase transaction includes the CO2 footprint of its production. For the calculation of CO2 emissions, MOL Group uses the average-data method

calculation and applies CO2 conversion factors from the Directive (EU) 2018/2001 of the European Parliament and of the Council of 11 December 2018 on the promotion of the use of energy from renewable sources (LINK).

- **Category 2 - Capital Goods** (steel and concrete for construction): MOL Group includes in its Scope 3 calculation the footprint of the externally produced steel and concrete purchased by MOL Group. In 2024, we identified major CAPEX investments with the highest potential for steel and concrete usage. With confirmation from their project managers, these footprints have been included in the calculation. For the calculation of CO2 emissions, MOL Group uses the average-data method calculation and applies CO2 conversion factors from the World Steel Association (LINK) for steel and Global Cement and Concrete Association (LINK) for concrete.
- **Category 4 - Upstream transportation and distribution:** MOL Group includes in its Scope 3 calculation the footprint of the transportation of externally produces crude oil purchased by MOL for processing in the Group's refineries. For the calculation of GHG emission, MOL Group uses the distance-based method calculation and applies CO2eq conversion factors from the Greenhouse gas reporting: conversion factors used for the 2024 GHG calculation were obtained from the UK Government (LINK) and CEFIC (LINK).
- **Category 10 - Processing of sold products:** MOL Group includes in its Scope 3 calculation the footprint of the processing sold intermediate petrochemical products (used for plastic). For the calculation of GHG emission, MOL Group uses the average-data method calculation and applies CO2eq conversion factors based on product categories. Conversion factors used for the 2024 GHG calculation were obtained from a recent publication in Circular Economy and Sustainability (LINK) for polymer products.
- **Category 11 - Use of Sold Products** (Refinery excl. naphtha): As of 2024, for the CO2 Emission Factor (conversion rates) of its different sold refinery products, MOL Group applies IPCC's emission factors for mobile (LINK) and stationary (LINK) combustion. The methodology includes references to "global warming potential" (GWP). MOL Group includes in the calculation the CO2 impact of the following sold products: natural gas, diesel, motor gasoline (petrol), jet fuel, heating oil, LPG, fuel oil and petroleum coke. Naphtha is excluded as its byproducts are accounted for under Category 10 and 12. Sold fuel includes both own produced as well as purchased (traded) from third parties. As of 2020, MOL Group no longer calculates with natural gas produced, but with natural gas sold for the CO2eq calculation.
- **Category 12 - End-of-Life Treatment of Sold Products** (polymers): This category includes the expected end-of-life emissions from polymer products sold during the accounting year, independent of the year in which they are actually disposed of. The Group's petrochemical sales (2024 MOL Group sales are available from the 2019-2024 Data Library) are made up polymers, butadiene and monomers (polymers make up around three quarters of total petrochemical sales). GHG Protocol Scope 3 Standard directs companies to consider estimating emissions for this category if they can reasonably estimate the downstream emissions associated with end use. Consequently, for the calculation of the End-of-Life Treatment of Sold Products calculation, only polymer sales have been considered, as emissions associated with end use can be reasonably estimated. The production of the Group's polymers (plastics) is made up of LDPE, HDPE and PP, with the first two accounting for around half the sales. The Group's polymers are manufactured by its two petrochemical plants in Hungary and Slovakia. As a result, most of the Group's polymers (LDPE, HDPE and PP) are sold on European markets. LDPE and HDPE are mostly sold for the packaging industry, whereas PP is sold to the automotive, agriculture, construction and packaging industries. It is assumed that the products would be used and disposed of in the countries to which MOL Group sold them, therefore EU disposal statistics from Plastics Europe's "The Circular Economy for Plastics - A European Overview" report (LINK) were applied for the end-of-life treatment of products based on their application: packaging, automotive, agriculture, construction and other. End-of-life treatment based emission factors used for the 2024 GHG emission calculation are based on a 2019 publication in Nature (LINK)
- **Category 15 – Investments:** Since 2020, MOL Group incorporated into the Scope 3 calculation the Scope 1 and 2 emissions of major non-operated JVs in both Upstream and Downstream. MOL Group follows the principle of conservativeness (i.e. erring on the side of overestimating rather than underestimating emissions)

Categories excluded from Scope 3 GHG emissions calculation:

- **Category 3 - Fuel- and Energy-related Activities:** As MOL Group is an integrated oil and gas company, it produces and consumes mainly its own fuels and energy and it is included in the Scope 1 and Scope 2 emission calculation, therefore Category 3 is not material for the company in the Scope 3 emission calculation.
- **Category 5 - Waste generated in operations:** currently not reported. Currently, boundaries are being determined and data is being collected for future reporting and disclosure.
- **Category 6 - Business Travel**: This is not a material source of Scope 3 emissions in MOL Group's value chain. Employees travelling for business-related transportation mainly use the MOL Group's own internal fleet which is accounted for under Scope 1.
- **Category 7 - Employee Commuting:** This is not a material source of Scope 3 emissions in MOL Group's value chain. Those commuting using MOL Group fleet cars are accounted for under Scope 1.
- **Category 8 - Upstream Leased Assets:** Not relevant. An emissions figure is not calculated for this category as MOL Group does not lease upstream assets in the course of normal operations.
- **Category 9 - Downstream Transportation and Distribution:** This is not a material source of Scope 3 emissions in MOL Group's value chain given the integrated nature of MOL Group. Downstream logistics is accounted for under Scope 1 emission.
- **Category 13 - Downstream leased assets:** This is not a material source of Scope 3 emissions in MOL Group's value chain as the only leased assets are the fleet of the MOL Fleet Solutions which are using cars owned by MOL Group. In addition, MOL fuel

cards are used to fuel cars of the fleet on MOL Petrol stations, therefore, fuel sales are already calculated under Scope 3 category 11 (use of sold products).

- **Category 14 - Franchises:** This is not a material source of Scope 3 emissions in MOL's value chain as all petrol stations are under MOL Group control. Franchised service stations constitute a small number of the total Group Service station network.

In terms of primary data obtained from our suppliers, we receive purchased biofuels certificate from our suppliers which we use in our Scope 3 calculation for category 1.

As mentioned in this Management Report's Management Discussion and Analysis under Biofuels in MOL Group section, MOL Group's biofuel purchase with regards to both supply points (9 countries) and concluded amount (>600 kilotons) remained stable in.

There has been no significant changes in our operations or supply chain which could possibly affect the year-to-year comparability of our GHG emissions.

The amount of biofuels purchased in 2024 is included in our Scope 3 calculation.

We do not disclose GHG intensity based on net revenue as changes in the GHG/net revenue do not reflect the effectiveness of GHG reduction targets, and revenue in O&G industry is generally determined by fluctuation in oil & gas quotations.

INTERNAL CARBON PRICING

/E1-8/

MOL Group applies internal carbon pricing as a shadow price to factor in the financial impact of carbon emissions, during:

- Capital expenditure and investment decisions
- Risk management and opportunity assessment
- Project development (organic/inorganic)
- Operations and value chain engagement
- Product development and R&D

This ensures consideration of potential future carbon costs arising from regulatory changes, market trends, and climate risks. Currently, the internal carbon pricing scheme applies to Scope 1 emissions under EU ETS, covering 89.85% in 2024. Carbon price premises are reviewed annually, incorporating EU ETS forecasts. MOL Group projects a continuous price increase until the 2040s, driven by free allocation phase-out and stricter benchmarks. After 2040, prices are expected to gradually decline as emissions decrease. The company discloses an ETS carbon price forecast of EUR 100-140/t by 2030 in its scenario analysis and capital market releases.

CO_2-related costs from EU ETS and the Hungarian CO_2 tax are embedded in financial planning and capital allocation. A key example is MOL Group's green hydrogen plant at the Danube Refinery, reducing CO_2 emissions by ~25 kt/year and mitigating EU ETS price risks. MOL Group ensures internal carbon pricing aligns with financial statements, including asset valuation and impairment calculations and fair value assessment of acquired assets. The company recognizes provisions for excess CO_2 emissions, factoring in market prices, forward contract rates, and Upstream Emission Reduction (UER) quotas for EU Fuel Quality Directive compliance.

EU TAXONOMY REPORT

Introduction and legal background

Based on Article 8 of Regulation (EU) 2020/852 (hereinafter Taxonomy Regulation)[15], undertakings - that are subject to an obligation to publish a non-financial statement or a consolidated non-financial statement pursuant to Article 19a or Article 29a of Directive 2013/34[16] of the European Parliament and of the Council, shall include in their non-financial statement or consolidated non-financial statement on how and to what extent their activities are associated with economic activities, that qualify as environmentally sustainable under Articles 3 and 9 of the Taxonomy Regulation. As part of that, the covered undertakings, including MOL Group shall disclose KPIs (key performance indicators) on the proportion of the turnover, capital expenditure (CapEx) and operating expenditure (OpEx) of their activities related to assets or processes associated with environmentally sustainable economic activities. Detailed description of each KPI and its calculation methodology can be found on page 11.

General approach

For financial year 2024, an extensive identification approach was conducted, with eligibility and alignment assessments for all environmental objectives contributing to climate change mitigation, climate change adaptation, sustainable use and protection of water and marine resources, transition to circular economy, pollution prevention and control and the protection and restoration of biodiversity and ecosystems. This is possible with the publication of Delegated Regulation (EU) 2023/2486 of 27 June 2023[17] (hereinafter Environmental Delegated Act). Relevant activities for MOL Group are covered under Climate change mitigation, Climate change adaptation, Transition to circular economy and Pollution prevention and control, based on the Groups activity scope, however, all objectives are monitored for future investments. MOL Group has not identified any activity at CapEx, OpEx or Turnover level, which would contribute to multiple environmental objectives.

In terms of financial instruments, MOL Group has not issued any sustainability-linked or green bonds in the assessed periods, although it used sustainability-linked loans for funding.

Eligibility screening

An eligible economic activity is an economic activity that is listed and described under the EU Taxonomy regulation. The screening covered MOL Group core businesses in case of every consolidated activity and operation. The eligible items are identified with the help of the different businesses across the company. Furthermore, the eligibility screening is already incorporated into the project preparation process of the company, with several approval and cross-checking rounds. This is allowing MOL Group to identify every relevant project already in early phase of their lifecycle.

Alignment screening

In line with the EU Taxonomy assessment logic, alignment screening was completed in three steps. Compliance with technical screening criteria (TSC) has been assessed first, followed by the do no significant harm (DNSH) screening on activity level. Compliance with minimum social safeguards (MSS) has been assessed on the Group level.

MOL Group has screened some of its activity types in a group-level joint alignment assessment (including TSC and DNSH). The covered activities are the group level EV charger and solar activities, the Hungarian waste management network (operating under Circular Economy Services (CES) segment, controlled by MOHU MOL Waste management Zrt. (hereafter MOHU)) , and the Hungarian transmission and distribution networks for renewable and low-carbon gases. This joint assessment is possible, since these activity types are conducted in several sites (with large geographical extension) and with similar technical profile. Furthermore, the screened sites one by one are financially not significant at MOL Group level.

Technical Screening Criteria (TSC) monitoring

The Technical Screening Criteria are specific characteristics that can be used to determine whether an economic activity provides a substantial contribution to one of the environmental objectives. Pre-selected eligible activities were subject to a technical screening criteria (TSC) monitoring as the first step to proving their alignment. For the TSC screening the responsible project managers and business departments have been contacted with internal assessment templates. The templates aim to translate the EU Taxonomy legislative criteria into MOL Group language and providing a step-by-step guidance with binding content for project teams.

[15] Regulation (EU) 2020/852 of the European Parliament and of the Council of 18 June 2020 on the establishment of a framework to facilitate sustainable investment, and amending Regulation (EU) 2019/2088

[16] Directive 2013/34/EU of the European Parliament and of the Council of 26 June 2013 on the annual financial statements, consolidated financial statements and related reports of certain types of undertakings, amending Directive 2006/43/EC of the European Parliament and of the Council and repealing Council Directives 78/660/EEC and 83/349/EEC (Text with EEA relevance)

[17] Commission Delegated Regulation (EU) 2023/2486 of 27 June 2023 supplementing Regulation (EU) 2020/852 of the European Parliament and of the Council by establishing the technical screening criteria for determining the conditions under which an economic activity qualifies as contributing substantially to the sustainable use and protection of water and marine resources, to the transition to a circular economy, to pollution prevention and control, or to the protection and restoration of biodiversity and ecosystems and for determining whether that economic activity causes no significant harm to any of the other environmental objectives and amending Commission Delegated Regulation (EU) 2021/2178 as regards specific public disclosures for those economic activities.

Do no significant harm (DNSH) screening

Activities fulfilling technical screening criteria have been tested against the do no significant harm (DNSH) requirements of the remaining five environmental objectives. To prove the activities alignment with the DNSH criteria, a detailed assessment has been carried out.

Appendix A screening (i*.e. compliance with Climate change adaptation criteria*)[18] has been conducted for every aligned activity. In order to deliver climate risk and vulnerability assessment for the relevant activities, already existing in-house expertise and knowledge on risk management has been combined with the EU Taxonomy additional requirements – and integrated to a specific Appendix A framework.

For the future climate scenarios, IPCC (Intergovernmental Panel on Climate Change) and EEA (European Environmental Agency) sources have been used in the assessment – as referred to in Appendix A requirements. Furthermore, to select the material physical climate risks, the European Climate Adaptation Platform (Climate-ADAPT)[19] database has been applied.

A conservative approach has been implemented during the assessment and the worst-case scenario; the RCP 8.5 pathway was examined[20]. The latest available climate scenarios were used. Future scenarios were analysed until 2050. Due to the geographical proximity and due to the similar climate profile of the main operational countries of MOL Group, the applied scientific framework examined them as one region, so as Western and Central Europe (for example in the IPCC projections). Due to this reason in the risk assessments all material physical climate risks have been screened relevant to this area. The material physical climate risks have been assessed in the scenarios as detailed above, taking into account the likelihood and impact on the Group and adaptation plan defined whenever necessary.

According to the methodology of MOL Group in case of the group level EV charger, solar activities, and the Hungarian transmission and distribution networks a group level joint climate risk and vulnerability assessment has been conducted. This approach was also conducted with waste management site screenings based on the high number of sites with similar profiles in the Hungarian region.

During proofing compliance with criteria set out by **Appendix B**[21] (*i.e. compliance with Sustainable use and protection of water and marine resources criteria*) and **Appendix D**[22] (*i.e. compliance with Protection and restoration of biodiversity and ecosystems criteria*) screening, operational permits have been reviewed with the help of the relevant permitting departments within the company. According to the screening process the compliance can be fulfilled either by IPPC certificate, or Environmental Impact Assessment (EIA) or by further environmental permits. A further option is that based on local law Environmental Impact Assessment is not required in case of the activity and the criteria is not relevant due to the nature of the activity. In order to proof the compliance an internal screening template have been created. The Appendix B and D screening was conducted by involving project managers, HSE and permitting experts.

During the screening of **Appendix C**[23] (*i.e. compliance with Pollution prevention and control criteria*) screening was conducted according to the appendix elaborated under this environmental objective. Criteria defined by the points ”a”-”f” have been assessed in details with an internal screening template. In case of a relevant activity the internal REACH expert is involved into the assessment.

The transition to a circular economy and other DNSH criteria defined by the regulation have been assessed on a case-by-case basis, as these criteria are not uniform across all activities but differ depending on the specific activity. Since each activity has its own environmental impacts and challenges, the criteria applied vary to align with the specific environmental and sustainability objectives of each activity.

Minimum social safeguards (MSS) assessment

Basis of detailed assessment was the Final Report on Minimum Safeguards[24] issued by the Platform on Sustainable Finance, focusing on human rights, anti-corruption, fair competition and taxation.

MOL Group respects fundamental human rights, its Code of Ethics and Business Conduct[25] includes the company's commitments. MOL Group respects the Universal Declaration of Human Rights, which summarizes fundamental human rights in 30 articles and further guidance documents on human rights such as the UN Global Compact, the UN Guiding Principles, the OECD Guidelines for Multinational Enterprises and the ILO Declaration on Fundamental Principles and Rights at Work and voluntary principles about security and human rights. Furthermore, the MOL Group Compliance & Ethics department

[18] Appendix A (Generic Criteria for Climate Change Adaptation) of ANNEX I of Delegated Regulation (EU) 2021/2139
[19] The European Climate Adaptation Platform Climate-ADAPT (2024)
[20] COMMISSION NOTICE on the interpretation and implementation of certain legal provisions of the EU Taxonomy Climate Delegated Act establishing technical screening criteria for economic activities that contribute substantially to climate change mitigation or climate change adaptation and do no significant harm to other environmental objective (C/2023/267), Question 168
[21] Appendix B (Generic Criteria for DNSH to Sustainable Use and Protection of Water and Marine Resources) of ANNEX I of Delegated Regulation (EU) 2021/2139
[22] Appendix D (Generic Criteria for DNSH to Protection and Restoration of Biodiversity and Ecosystems) of ANNEX I of Delegated Regulation (EU) 2021/2139
[23] Appendix C (Generic Criteria for DNSH to Pollution Prevention and Control Regarding Use and Presence of Chemicals) of ANNEX I of Delegated Regulation (EU) 2021/2139
[24] Final Report on Minimum Safeguards, Platform on Sustainable Finance, October 2022
[25] Code of Ethics and Business Conduct (2024) MOL Group

operates a corporate grievance mechanism (*Speak-Up!*), whereas the internal and external parties have the possibility to report every ethics related issue, including any concern regarding the human rights. During the 2024 financial year MOL Group did not faced with any human rights related violation, similar to previous years.

Integrity and transparency are important values for MOL Group and fighting against corruption is an essential part of our corporate strategy. MOL Group respects guidance documents on anti-corruption like the UN Global Compact, OECD Guidelines for Multinational Enterprises, United Nations Convention against Corruption (UNCAC) and takes into consideration suggestions of Transparency International, and the World Economic Forum Partnering Against Corruption Initiative (PACI). The anti-corruption policy is part of Code of Ethics and Business Conduct. MOL Group has well operated Ethics Management System including an annual group level mandatory training program and regulated speak-up channel for internal and external colleagues. MOL Group has special Anti-Fraud & Investigation department to prevent, detect, deter, investigate, sanction fraudulent / corrupt risks and practices.

MOL Group is dedicated to practice fair market behaviour; its activities on the market must be conducted in accordance with the norms of fair competition and the spirit and letter of applicable competition law.

Fully complying with competition law is not only a legal obligation but it is related to attitudes and cultures that can positively impact a company's business. The aim of our Compliance Program is to raise the awareness of our employees and to eliminate legal risks, thus supporting the effective implementation of business strategies in a legal way. Group Compliance organization has a constantly adjusted scope to the changing regulatory and business environment (Group Compliance Plan), which focuses on those compliance risks that require engagement on corporate level, e.g. competition law. Group Compliance Plan is operated for minimizing compliance exposure by conducting investigations and performing group-level trainings to increase awareness. Group Compliance has its dedicated experts. In-house investigations and simulations aiming at monitoring compliance with internal and external commitments are being performed.

Regarding taxation the company has an adequate governance structure in place to ensure full tax compliance and tax transparency. The company or its subsidiaries has not been convicted on violating tax laws during the 2024 financial year.

Financial methodology

In terms of the assessment of the EU Taxonomy eligible and aligned activities and calculation of the mandatory KPIs such as turnover, OpEx and CapEx as the main rule MOL Group followed the requirements defined by the Disclosure Delegated Act (EU 2021/2178)[26], however, in some cases materiality thresholds and simplification considerations have been applied as described in below sections.

KPI related to turnover (turnover KPI)

For the KPI calculation the consolidation system was used for the reporting. The data for the reporting process was collected and cross-checked by the responsible finance teams.

The turnover KPI's numerator calculation is based on the turnover of the identified eligible and aligned activities of MOL Group. In the case of profit centers where both eligible and non-eligible turnover was identified, only the turnover related to the eligible products was collected and calculated. The same logic is applied in case of aligned, and non-aligned activities. To avoid double counting, only third-party external turnover is considered in the calculation. No materiality threshold has been applied, and all relevant activities independently from the magnitude of contribution to the Group Turnover have been considered. The turnover KPI's denominator is the same as the Net Sales line in the Consolidated Statement of Profit or Loss and can be found on page 15 of the Consolidated Financial Statements of the Annual Financial Report.

KPI related to operating expenditure (OpEx KPI)

OpEx KPI has been calculated even for the profit centers, the individual reporting units of value creation with impact on both costs and revenues, where sustainable turnover has not been identified. Furthermore, the OpEx spendings of the CapEx projects have been involved into the OpEx KPI.

In the case of OpEx KPI the not-relevant OpEx items (such as Personnel-Type Expenses (PTE), charged services (allocated internal functional costs), energy and raw material) were deducted first, otherwise the calculation was done using the consolidation system, by taking into account all the relevant general ledger accounts based on the methodology defined by the Disclosure Delegated Act.

[26] Supplementing Regulation (EU) 2020/852 of the European Parliament and of the Council by specifying the content and presentation of information to be disclosed by undertakings subject to Articles 19a or 29a of Directive 2013/34/EU concerning environmentally sustainable economic activities, and specifying the methodology to comply with that disclosure obligation (EU 2021/2178)

For the numerator calculation in the case of profit centers where both eligible and non-eligible OpEx was identified, only OpEx related to the eligible products was collected and calculated. In case of production units (especially in the case of Annex I/ 3.14 Manufacture of organic basic chemicals activity) allocation keys are applied in the OpEx KPI allocation, based on the production volume of the EU Taxonomy eligible product. The same logic has been applied in the case of aligned, and non-aligned activities.

MOHU related OpEx alignment screening was conducted in 2024, with extensive assessment of processes. Activities were analyzed on a subcontractor level, with the inclusion of TSC and DNSH criteria.

For the denominator calculation the total Group level amount of the relevant general ledger accounts have been accounted.

The data for the reporting process was collected and cross-checked by the segment finance teams. An 1-9 test report was taken place in order to prepare the organisation for the 1-12 reporting process and to demonstrate preliminary result for the organisation.

Overall, the OpEx KPI is considered as less material for the description of MOL Group's EU Taxonomy related activities.

KPI related to capital expenditure (CapEx KPI)

In the case of CapEx KPI the central CapEx reporting and monitoring tool of MOL Group has been used. In the system already from early phase the EU Taxonomy relevancy of the projects are marked. The data was provided and cross-checked by the Group Sustainable Investment Solutions team (responsible for CapEx resource allocation). Throughout the year the MOL Group issues an internal monthly EU Taxonomy report in order to track the relevant CapEx spendings.

Concerning the CapEx definition used in this database and the definitions used in the Taxonomy Regulation the following comments must be taken: the central CapEx reporting and monitoring tool of MOL Group does not include additions from borrowing costs, right-of-use assets, estimated field abandonment and site restoration costs. MOL Group believes, that these differences do not have a material impact on the numerator of the KPI. For the numerator the relevant (eligible and/or aligned) realized capital expenditure of investment projects for the respective financial year 2024 has been considered.

In the case of CapEx KPI a materiality threshold of USD 100 thousand has been applied. The CapEx figure used as the denominator is comparable with the figure on page 20 of the Consolidated Financial Statements of the Annual Financial Report. The CapEx KPI's denominator is the same as the Additions and capitalizations plus Acquisition of subsidiaries line in the Property, plant and equipment movement table, additions of Investment property and the Additions plus Acquisition of subsidiary line in the Intangible asset movement table. In case of related sustain type of investments by the eligible or aligned operations (cost center & company or site), investments will be calculated automatically as eligible or aligned. These investments are supporting the day-to-day running of the eligible/aligned business activity of MOL Group.

Contextual information about the KPIs

EU Taxonomy eligible activities in turnover is 9.3%, in OpEx 28.4%, in CapEx 21.0% for the year 2024. EU Taxonomy aligned activities in turnover is 0.5%, in OpEx 5.5%, in CapEx 7.3% for the year 2024.

Relatively low alignment percentages are partially result of the previously demonstrated facts, that significant part of MOL Group's activities is still related to the oil and gas industry and a conservative approach has been followed in the assessment and reporting.

Furthermore, MOL Group won[27] the Hungarian state concession tender through MOHU (MOHU MOL Hulladékgazdálkodás Zrt.) for waste management services in July 2022, and started the operations on 1st of July 2023 supporting our aspiration to become a key player in the circular economy. MOL Group is responsible for the collection, transportation, pre-treatment, handling over to treatment, sales operations and operating EPR and DRS systems of the municipal solid waste and committed to make circular economy related investments. For the first time in 2024, these investments and economic activities were screened on alignment level.

Turnover

The eligible turnover proportion in 2024 is 9.3%, which is similar to the previous year (9.6%). The aligned turnover proportion increased to 0.5% from last year's 0.2%. The similar results in the eligible turnover proportion are due to our similar EU Taxonomy related activity portfolio compared to 2023 financial year. The increase in aligned turnover percentage is due to the waste management segment (MOHU), which is reported on alignment level for the first time this year. However, even though significant proportion of MOHU is related to the transition to circular economy environmental objective,

[27] MOL wins concession for waste management services (2022). molgroup.info

the turnover of this subsidiary is limited compared to the total of MOL Group. MOL Group will continue its journey of smart transition, contributing to both sustainability and competitiveness at the same time. That is, alongside with its promising low carbon and green investment projects, will generate a growing EU Taxonomy related revenue in the upcoming years.

Aligned activities are associated with the following activity categories:

- *2.3. Collection and transport of non-hazardous and hazardous waste,* linked to MOHU, as the sole operator of the Hungarian waste management system.
- *2.6. Depollution and dismantling of end-of-life products,* is a key activity within MOHU, which aims material recovery and preparation for re-use from complex end-of-life products in several sites in Hungary.
- *2.7. Sorting and material recovery of non-hazardous waste,* linked to MOHU, dedicated to return as much high quality secondary raw material as possible to the economy, minimizing the waste stored in landfills.
- *3.17. Manufacturing of plastics in primary form*, linked to ReMat operations. In April 2022 MOL Group acquired ReMat, Hungary's market leading plastics recycling company, using communal and industrial waste for creating recycled plastic granules. With this transaction MOL Group's total capacity of recycled plastic material was raised from 25,000 tons/year to 40,000 tons/year.
- *4.1. Electricity generation using solar photovoltaic technology*, linked to solar operations activity in Hungary and Croatia. MOL Group stepped into the solar power business in 2018, with the building of photovoltaic powerplants. MOL Group is currently having around 31 MW solar capacity in Hungary and 14 MW in Croatia.
- *5.9. Material recovery from non-hazardous waste*, covering Aurora Kunststoffe Gmbh activities and rubber bitumen production of Zala Refinery, Hungary. MOL Group acquired Aurora Kunstoffe Gmbh in 2019 and strengthened its presence in recycle-based compounds and its position as an automotive supplier. This transaction supported MOL Group's ambition to transform its fuel-based business model in Downstream to a higher value-added petrochemical product portfolio. The rubber bitumen plant started its operation in 2020 in Zalaegerszeg, Hungary and applies a new manufacturing technology of crumb rubber, which is made from bitumen and waste tyres and has been developed jointly by MOL and Pannon University. The rubber bitumen has several advantages compared to the conventional road construction bitumen as it has a longer lifecycle, better resistance on environmental impacts as well as providing an improved traffic safety due to the reduced braking distance.
- *6.4. Operation of personal mobility device, cycle logistics*, covering operation in Bratislava, Slovakia. Bike sharing activity has been the first initiative of MOL Group in the mobility field in the year 2014.
- *6.5. Transport by motorbikes, passenger cars and light commercial vehicles*, attributable to another building block of our mobility services, through providing leasing services, including financing and fleet management for MOL Group and external clients. The transitional economic activity[28] could be proven to be aligned only partially, as not the entire car park is compliant with the 'low- and zero-emission light-duty vehicles' (lower than 50gCO2/km emission) criteria. With the continuous modernization of the fleet, the percentage of environmentally friendly vehicles is expected to grow year by year.
- *6.15. Infrastructure enabling low-carbon road transport and public transport* enabling economic activity[29] is linked to our electric vehicle charging station network, covering nearly 300[30] EV chargers in the CEE region. E-mobility is also one of the key pillars of our mobility solutions.

For details, please see *Table 1*

[28] As it is stated in our long-term Shape Tomorrow Strategy, MOL Group aims to provide complex mobility services in order to reach its sustainability targets. Increasing the zero and low carbon emission vehicles share within our portfolio is in line with this aspiration. In that way as referred in Article 10(2) of Regulation (EU) 2020/852 we consider this activity as transitional, as there are no technologically and economically feasible low-carbon alternatives for it, but the activity supports the transition to a climate-neutral economy in a manner that is consistent with a pathway to limit the temperature increase to 1.5 degrees Celsius above pre-industrial levels.

[29] Based on the Article 16 of Regulation (EU) 2020/852 the EV charger activity of MOL Group is covering the enabling economic activity category, since it enables other activities to make a substantial contribution to one or more of the environmental objectives, as it enables the operation of low-carbon road transport and public transport. Furthermore, the activity does not lead to a lock-in in assets that undermine long-term environmental goals, considering the economic lifetime of its assets, as currently there is no better widespread technology, which enables the operation of electric vehicles. Furthermore, the technology supports the European environmental target to phase out the ICE motors. In addition, the activity has a substantial positive environmental impact on the basis of lifecycle considerations, since the components of the EV chargers are over 90% recyclable.

[30] Status as of 31 December 2024

Financial year 2024		Year 2024		Substantial contribution criteria						DNSH (Do No Significant Harm) (h)									
Economic activities	Code (a)	Turnover (USD mn)	Proportion of Turnover, year 2024	Climate change mitigation	Climate change adaptation	Water and marine resources	Circular economy	Pollution	Biodiversity and ecosystem	Climate change mitigation	Climate change adaptation	Water and marine resources	Circular economy	Pollution	Biodiversity and ecosystem	Minimum safeguards	Proportion of Taxonomy aligned (A.1.) or -eligible (A.2.) turnover, year 2023	Category (E: enabling activity)	Category (T: transitional activity)
				Y; N; N/EL (b)(c)	Y; N; N/EL (b)(c)	Y; N; N/EL (b)(c)	Y; N; N/EL (b)(c)	Y; N; N/EL (b)(c)	Y; N; N/EL (b)(c)	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	%	E	T
A. TAXONOMY-ELIGIBLE ACTIVITIES																			
A.1. **Environmentally sustainable activities (Taxonomy-aligned)**																			
Collection and transport of non-hazardous and hazardous waste	CE 2.3	10.7	0.0%				Y				Y	Y		Y		Y	0.0%		
Depollution and dismantling of end-of-life products	CE 2.6	17.2	0.1%				Y				Y	Y		Y	Y	Y	0.0%		
Sorting and material recovery of non-hazardous waste	CE 2.7	52.6	0.2%				Y				Y	Y		Y	Y	Y	0.0%		
Manufacture of plastics in primary form	CCM 3.17	10.3	0.0%	Y							Y	Y		Y	Y	Y	0.0%		T
Electricity generation using solar photovoltaic technology	CCM 4.1	6.3	0.0%	Y							Y		Y		Y	Y	0.0%		
Material recovery from non-hazardous waste	CCM 5.9	17.1	0.1%	Y							Y				Y	Y	0.1%		
Operation of personal mobility devices, cycle logistics	CCM 6.4	0.0	0.0%	Y							Y		Y			y	0.0%		
Transport by motorbikes, passenger cars and light commercial vehicles	CCM 6.5	2.4	0.0%	Y							Y		Y	Y		Y	0.0%		T
Infrastructure enabling low-carbon road transport and public transport	CCM 6.15	1.4	0.0%	Y							Y	Y	Y	Y	Y	Y	0.0%	E	
Turnover of environmentally sustainable activities (Taxonomy-aligned) (A.1)		118.0	0.5%														0.2%		
Of which enabling		1.4	0.0%														0.0%	E	
Of which transitional		12.7	0.1%														0.1%		T
A.2 **Taxonomy-Eligible but not environmentally sustainable activities (not Taxonomy-aligned activities)**(g)																			
				Y; N/EL (f)	N/EL (f)	N/EL (f)	N/EL (f)	N/EL (f)	N/EL (f)										
Collection and transport of non-hazardous and hazardous waste	CE 2.3	217.6	0.9%				Y										1.1%		
Treatment of hazardous waste	CE 2.4	0.0	0.0%				Y										0.0%		
Recovery of bio-waste by anaerobic digestion or composting	CE 2.5	0.0	0.0%				Y										0.0%		
Depollution and dismantling of end-of-life products	CE 2.6	27.3	0.1%				Y										0.1%		
Sorting and material recovery of non-hazardous waste	CE 2.7	265.5	1.1%				Y										0.3%		
Manufacture of organic basic chemicals	CCM 3.14	566.8	2.3%	Y													2.7%		
Manufacture of plastics in primary form	CCM 3.17	1110.9	4.4%	Y													4.9%		
Cogeneration of heat/cool and power from bioenergy	CCM 4.20	7.7	0.0%	Y													0.0%		
Electricity generation from fossil gaseous fuels	CCM 4.29	0.1	0.0%	Y													0.0%		
Composting of bio-waste	CCM 5.8	0.0	0.0%	Y													0.0%		
Material recovery from non-hazardous waste	CCM 5.9	0.0	0.0%	Y													0.2%		
Transport by motorbikes, passenger cars and light commercial vehicles	CCM 6.5	27.0	0.1%	Y													0.1%		
Turnover of Taxonomy-eligible but not environmentally sustainable activities (not Taxonomy-aligned activities) (A.2)		2222.9	8.8%														9.4%		
Turnover of Taxonomy eligible activities (A.1+A.2)		2340.9	9.3%														9.6%		
B. TAXONOMY-NON-ELIGIBLE ACTIVITIES																			
Turnover of Taxonomy-noneligible activities		22 789.68	90.7%																
TOTAL		25 130.54	100%																

Proportion of Turnover / Total Turnover		
	Taxonomy-aligned per objective	**Taxonomy-eligible per objective**
Climate change mitigation (CCM)	32%	75%
Climate change adaptation (CCA)	0%	0%
Sustainable use and protection of water and marine resources (WTR)	0%	0%
Transition to a circular economy (CE)	68%	25%
Pollution prevention and control (PPC)	0%	0%
Protection and restoration of biodiversity and ecosystems (BIO)	0%	0%

Table 1: Proportion of turnover from products or services associated with Taxonomy eligible and aligned economic activities

Operating expenditure (OpEx)

The eligible OpEx proportion in 2024 is 28.4%, which is significantly higher than in the previous financial year (19.4%). The aligned OpEx proportion is 5.5% , which is five times of the value than what was reported in the previous year (0.9%). The significantly higher eligible OpEx result in 2024 FY compared to last year is due to a more sophisticated OpEx methodological approach by MOHU. Furthermore, MOHU is reported on alignment level for the first time, hence the significant increase in aligned OpEx. The same aligned activity categories are valid in the case of OpEx as in the turnover.

For details, please see *Table 2*.

Financial year 2024	Year 2024			Substantial contribution criteria						DNSH (Do No Significant Harm) (f)									
Economic activities	Code (a)	OpEx (USDmn)	Proportion of OpEx, year 2024	Climate change mitigation	Climate change adaptation	Water and marine resources	Circular economy	Pollution	Biodiversity and ecosystem	Climate change mitigation	Climate change adaptation	Water and marine resources	Circular economy	Pollution	Biodiversity and ecosystem	Minimum safeguards	Proportion of Taxonomy-aligned (A.1.) or -eligible (A.2.) OpEx, year 2023	Category (E: enabling activity)	Category (T: transitional activity)
				Y; N;N/EL (b)(c)	Y; N;N/EL (b)(c)	Y; N;N/EL (b)(c)	Y; N;N/EL (b)(c)	Y; N;N/EL (b)(c)	Y; N;N/EL (b)(c)	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	Y/N	%	E	T
A. TAXONOMY-ELIGIBLE ACTIVITIES																			
A.1. **Environmentally sustainable activities (Taxonomy-aligned)**																			
Collection and transport of non-hazardous and hazardous waste	CE 2.3	10.1	0.6%				Y				Y	Y		Y		Y	0.0%		
Depollution and dismantling of end-of-life products	CE 2.6	14.8	0.9%				Y				Y	Y		Y	Y	Y	0.0%		
Sorting and material recovery of non-hazardous waste	CE 2.7	56.3	3.4%				Y				Y	Y		Y	Y	Y	0.0%		
Manufacture of plastics in primary form	CCM 3.17	2.5	0.2%	Y							Y	Y		Y	Y	Y	0.2%		T
Electricity generation using solar photovoltaic technology	CCM 4.1	0.9	0.1%	Y							Y		Y		Y	Y	0.0%		
Material recovery from non-hazardous waste	CCM 5.9	5.8	0.3%	Y							Y				Y	Y	0.5%		
Operation of personal mobility devices, cycle logistics	CCM 6.4	0.0	0.0%	Y							Y		Y			Y	0.0%		
Transport by motorbikes, passenger cars and light commercial vehicles	CCM 6.5	0.6	0.0%	Y							Y		Y	Y		Y	0.0%		T
Infrastructure enabling low-carbon road transport and public transport	CCM 6.15	0.3	0.0%	Y							Y	Y	Y	Y	Y	Y	0.0%	E	
OpEx of environmentally sustainable activities(Taxonomy-aligned) (A.1)		91.3	5.5%														0.9%		
Of which enabling		0.3	0.0%														0.0%	E	
Of which transitional		3.2	0.2%														0.3%		T
A.2 **Taxonomy-Eligible but not environmentally sustainable activities (not Taxonomy-aligned activities)** (f)																			
				Y;N/EL (e)	Y;N/EL (e)	Y;N/EL (e)	Y;N/EL (e)	Y;N/EL (e)	Y;N/EL (e)										
Treatment of hazardous waste	PPC 2.2	4.8	0.3%					Y									0.2%		
Collection and transport of non-hazardous and hazardous waste	CE 2.3	192.4	11.7%				Y										10.0%		
Treatment of hazardous waste	CE 2.4	0.0	0.0%				Y										0.1%		
Recovery of bio-waste by anaerobic digestion or composting	CE 2.5	0.0	0.0%				Y										0.2%		
Depollution and dismantling of end-of-life products	CE 2.6	26.8	1.6%				Y										0.8%		
Sorting and material recovery of non-hazardous waste	CE 2.7	104.6	6.3%				Y										2.8%		
Manufacture of organic basic chemicals	CCM 3.14	8.6	0.5%	Y													0.6%		
Manufacture of plastics in primary form	CCM 3.17	23.6	1.4%	Y													2.3%		
Cogeneration of heat/cool and power from bioenergy	CCM 4.20	0.0	0.0%	Y													0.2%		
Electricity generation from fossil gaseous fuels	CCM 4.29	0.0	0.0%	Y													0.0%		
Construction, extension and operation of waste water collection and treatment	CCM 5.3	9.3	0.6%	Y													0.9%		
Transport by motorbikes, passenger cars and light commercial vehicles	CCM 6.5	7.2	0.4%	Y													0.5%		
OpEx of Taxonomy-eligible but not environmentally sustainable activities (not Taxonomy-aligned activities) (A.2)		377.3	22.9%														18.6%		
OpEx of Taxonomy eligible activities (A.1+A.2)		468.6	28.4%														19.4%		
B. TAXONOMY-NON-ELIGIBLE ACTIVITIES																			
OpEx of Taxonomy-noneligible activities		1182.4	71.6%																
TOTAL		1651.0	100.0%																

Proportion of OpEx / Total OpEx		
	Taxonomy-aligned per objective	**Taxonomy-eligible per objective**
Climate change mitigation (CCM)	11.1%	12.6%
Climate change adaptation (CCA)	0.0%	0.0%
Sustainable use and protection of water and marine resources (WTR)	0.0%	0.0%
Transition to a circular economy (CE)	88.9%	86.4%
Pollution prevention and control (PPC)	0.0%	1.0%
Protection and restoration of biodiversity and ecosystems (BIO)	0.0%	0.0%

Table 2: Proportion of OpEx from products or services associated with Taxonomy eligible and aligned economic activities

Capital expenditure (CapEx)

The eligible CapEx proportion is 21.0% in 2024, which is slightly lower than what was reported in the previous year (24.1%). The aligned CapEx proportion is 7.3% , which is similar to the last year's alignment rate (8.6%). Some of the significant EU taxonomy aligned projects started in the previous years have reached the state of mechanical completion in 2024. Nearly half of the aligned CAPEX is due to MOHU, which is reported on alignment level for the first time this year. Most of the CAPEX spending is in the collection and transportation of non-hazardous and hazardous waste category. In line with our strategy, MOL Group is committed towards the smart green transition, due to that reason in the upcoming years the company is planning to further develop its low-carbon and EU Taxonomy aligned project portfolio in nearly all of the segments.

Aligned investments are associated with the following activity categories:

- *CE 2.3. Collection and transport of non-hazardous and hazardous waste,* related to projects in the Circular Economy Services segment of MOL Group, specifically related to MOHU operations. The most significant projects were the Deposit Refund System (DRS) and the purchase of waste management vehicles. MOL group is committed to the renewal of the waste management fleet with new, modern and sustainable vehicles as well as constructing state of the art waste yards to ensure the most efficient utilization of waste, channelling back to circular economy as much of it as possible.
- *CE 4.1. Provision of IT/OT data-driven solutions and software,* related to downstream. The project aims to provide continuous digital support for bio-compliance with the RED III directive.
- *CCM 3.10. Manufacture of hydrogen*, related to projects in green hydrogen production technology. In April 2022 MOL Group announced the building of a 10MW green hydrogen plant in Százhalombatta, Hungary. The total investment will be around EUR 22mn, allowing MOL Group to produce 1600 tons per annum of green hydrogen, resulting in around 25 thousand tons of CO2 saving with the use of renewable electricity. Furthermore, a new hydrogen unit in INA Rijeka Refinery, Croatia is under construction to supply the market with 1500 tonnes of hydrogen per year.
- *CCM 3.14. Manufacture of organic basic chemicals,* covering a new Olefins Conversion Technology (OCT) Unit construction at MOL Petrochemicals' site in Tiszaújváros, Hungary. The unit will have a production capacity of 100,000 tons/year of polymer grade propylene. The project was expected to reach its mechanical completion in 2024, however due to reasons outside of our control, the expected date of mechanical completion is modified to 2026.
- *CCM 4.1. Electricity generation using solar photovoltaic technology*, related to solar power plant constructions in Hungary and Slovakia, supporting our operations with green electricity generation.
- *CCM 4.13. Manufacture of biogas and biofuels for use in transport and of bioliquids*, linked to INA, is a project aiming to place advanced biofuel on the market in line with the RED III directive of EU. The project is still in its early phase, but once it is completed it will be able to produce 3kt of biomethane per annum in Sisak industrial site.
- *CCM 4.14. Transmission and distribution networks for renewable and low-carbon gases,* linked to our gas midstream operation, focusing on pipeline development related investments enabling transportation of hydrogen blended natural gas, including installation of hydrogen resistant equipment.
- *CCM 4.16. Installation and operation of electric heat pumps*, linked to the reconstruction of industrial heating and cooling systems with efficient, sustainable and environmentally friendly technologies.
- *CCM 4.25. Production of heat/cool using waste heat*, linked to the new hazardous waste incinerator unit in Danube Refinery, estimated to be completed in 2027.
- *CCM 6.15. Infrastructure enabling low-carbon road transport and public transport*, related to the extension of our electric vehicle charging station network in the CEE region.
- *CCM 6.5. Transport by motorbikes, passenger cars and light commercial vehicles* is linked to the purchase of new vehicles for our mobility services.
- *CCM 7.3. Installation, maintenance and repair of energy efficiency equipment* is related to the energy efficiency improvement of buildings in the core countries of MOL Group.
- *CCM 9.1. Close to market research, development and innovation* is linked to GINOP project, which aims to set up a site level methane emission monitoring system suitable for gas delivery stations and hubs.

For details, please see *Table 3*.

Financial year 2024		Year 2024		Substantial contribution criteria						DNSH (Do No Significant Harm)									
Economic activities	Code (a)	CapEx (USDmn)	Proportion of CapEx (%)	Climate change mitigation	Climate change adaptation	Water and marine resources	Circular economy	Pollution	Biodiversity and ecosystem	Climate change mitigation	Climate change adaptation	Water and marine resources	Circular economy	Pollution	Biodiversity and ecosystem	Minimum safeguards	Proportion of Taxonomy aligned (A.1.) or eligible (A.2.) CapEx, 2023	Category (E: enabling activity)	Category (T: transitional activity)
				Y; N/N/EL (b)(c)	Y; N/N/EL (b)(c)	Y; N/N/EL (b)(c)	Y; N/N/EL (b)(c)	Y; N/N/EL (b)(c)	Y; N/N/EL (b)(c)	(Y; N)	(Y; N)	(Y; N)	(Y; N)	(Y; N)	(Y; N)	(Y; N)	%	E	T
A. TAXONOMY-ELIGIBLE ACTIVITIES																			
A.1. **Environmentally sustainable activities (Taxonomy-aligned)**																			
Collection and transport of non-hazardous and hazardous waste	CE 2.3	68.1	3.3%				Y				Y	Y		Y		Y	0.0%		
Provision of IT/OT data-driven solutions and software	CE 4.1	0.1	0.0%				Y				Y	Y		Y		Y	0.0%	E	
Manufacture of hydrogen	CCM 3.10	2.4	0.1%	Y							Y	Y		Y	Y	Y	1.0%		
Manufacture of organic basic chemicals	CCM 3.14	51.8	2.5%	Y							Y	Y		Y	Y	Y	6.5%		T
Electricity generation using solar photovoltaic technology	CCM 4.1	9.1	0.4%	Y							Y		Y		Y	Y	0.3%		
Manufacture of biogas and biofuels for use in transport and of bioliquides	CCM 4.13	1.4	0.1%	Y							Y	Y		Y	Y	Y	0.0%		
Transmission and distribution networks for renewable and low-carbon gases	CCM 4.14	7.1	0.3%	Y							Y	Y		Y	Y	Y	0.4%		
Installation and operation of electric heat pumps	CCM 4.16	0.2	0.0%	Y							Y	Y	Y	Y		Y	0.0%		
Production of heat/cool using waste heat	CCM 4.25	3.1	0.1%	Y							Y		Y	Y	Y	Y	0.0%		
Transport by motorbikes, passenger cars and commercial vehicles	CCM 6.5	2.9	0.1%	Y							Y		Y	Y		Y	0.2%		T
Infrastructure enabling low-carbon road transport and public transport	CCM 6.15	1.4	0.1%	Y							Y	Y	Y	Y	Y	Y	0.1%	E	
Installation, maintenance and repair of energy efficiency equipment	CCM 7.3	3.9	0.2%	Y							Y			Y		Y	0.1%	E	
Close to market research, development and innovation	CCM 9.1	0.6	0.0%	Y							Y	Y	Y	Y	Y	Y	0.0%	E	
CapEx of environmentally sustainable activities (Taxonomy-aligned) (A.1)		152.0	7.3%														8.6%		
Of which enabling		6.0	0.3%														0.1%	E	
Of which transitional		54.7	2.6%														6.7%		T
A.2 **Taxonomy-Eligible but not environmentally sustainable activities (not Taxonomy-aligned activities)** (g)																			
				Y;N/EL (F)	Y;N/EL (F)	Y;N/EL (F)	Y;N/EL (F)	Y;N/EL (F)	Y;N/EL (F)										
Collection and transport of non-hazardous and hazardous waste	CE 2.3	6.6	0.3%				Y										4.0%		
Manufacture of organic basic chemicals	CCM 3.14	201.4	9.7%	Y													6.6%		
Transmission and distribution networks for renewable and low-carbon gases	CCM 4.14	5.6	0.3%	Y													0.0%		
Electricity generation from fossil gaseous fuels	CCM 4.29	1.8	0.1%	Y													0.2%		
Renewal of water collection, treatment and supply systems	CCM 5.2	1.6	0.1%	Y													0.1%		
Transport by motorbikes, passenger cars and commercial vehicles	CCM 6.5	45.7	2.2%	Y													1.7%		
Installation, maintenance and repair of energy efficiency equipment	CCM 7.3	21.9	1.1%	Y													1.0%		
CapEx of Taxonomy-eligible but not environmentally sustainable activities (not Taxonomy-aligned activities) (A.2)		284.7	13.7%														15.5%		
CapEx of Taxonomy-eligible activities (A.1+A.2)		436.8	21.0%														24.1%		
B. TAXONOMY-NON-ELIGIBLE ACTIVITIES																			
CapEx of Taxonomy-non-eligible activities		1644.0	79.0%																
TOTAL		2080.8	100%																

Proportion of CapEx / Total CapEx		
	Taxonomy-aligned per objective	**Taxonomy-eligible per objective**
Climate change mitigation (CCM)	55%	83%
Climate change adaptation (CCA)	0%	0%
Sustainable use and protection of water and marine resources (WTR)	0%	0%
Transition to a circular economy (CE)	45%	17%
Pollution prevention and control (PPC)	0%	0%
Protection and restoration of biodiversity and ecosystems (BIO)	0%	0%

Table 3: Proportion of CapEx from products or services associated with Taxonomy eligible and aligned economic activities

Complementary Delegated Act

Based on the modifications implemented by Delegated Regulation (EU) 2022/1214 (Complementary Climate Delegated Act)[31] MOL Group – in accordance with Article 8 paragraphs 6,7 and 8 of Delegated Regulation (EU) 2021/2178 – performed also an assessment and identified activities, which could be possibly eligible or aligned with the specific nuclear and gas energy activities. In the case of MOL Group activities, relevancy was identified only for gas-related activities, due to the lack of a nuclear portfolio. For details, please see *Table 4*.

	Fossil gas related activities	TURNOVER		OPEX		CAPEX	
4,	The undertaking carries out, funds or has exposures to construction or operation of electricity generation facilities that produce electricity using fossil gaseous fuels.	**YES**	NO	**YES**	NO	**YES**	NO
5,	The undertaking carries out, funds or has exposures to construction, refurbishment, and operation of combined heat/cool and power generation facilities using fossil gaseous fuels.	YES	**NO**	YES	**NO**	YES	**NO**
6,	The undertaking carries out, funds or has exposures to construction, refurbishment and operation of heat generation facilities that produce heat/cool using fossil gaseous fuels.	YES	**NO**	YES	**NO**	YES	**NO**

Please note that taking into account that MOL Group does not have nuclear energy related activities, row 1-3 from above table have been excluded.

Table 4: Nuclear and fossil gas related activities

	Economic activities	TURNOVER		OPEX		CAPEX	
		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)	
		USDmn	%	USDmn	%	USDmn	%
4.	Amount and proportion of taxonomy-aligned economic activity referred to in Section 4.29 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	-	-	-	-	-	-
5.	Amount and proportion of taxonomy-aligned economic activity referred to in Section 4.30 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	-	-	-	-	-	-
6.	Amount and proportion of taxonomy-aligned economic activity referred to in Section 4.31 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	-	-	-	-	-	-
7.	Amount and proportion of other taxonomy-aligned economic activities not referred to in rows 1 to 6 above in the denominator of the applicable KPI	37.6	0%	10.1	6%	83.8	7%
8.	**Total applicable KPI**	25 130.5	**100%**	1 651.0	**100%**	2 080.8	**100%**

Please note that taking into account that MOL Group does not have nuclear energy related activities, row 1-3 from above table have been excluded.

Table 5: Taxonomy-aligned economic activities (denominator)

[31] Amending Delegated Regulation (EU) 2021/2139 as regards economic activities in certain energy sectors and Delegated Regulation (EU) 2021/2178 as regards specific public disclosures for those economic activities ((EU 2022/1214)

	Economic activities	TURNOVER		OPEX		CAPEX	
		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)	
		USDmn	%	USDmn	%	USDmn	%
4.	Amount and proportion of taxonomy-aligned economic activity referred to in Section 4.29 of Annexes I and II to Delegated Regulation 2021/2139 in the numerator of applicable KPI	-	-	-	-	-	-
5.	Amount and proportion of taxonomy-aligned economic activity referred to in Section 4.30 of Annexes I and II to Delegated Regulation 2021/2139 in the numerator of applicable KPI	-	-	-	-	-	-
6.	Amount and proportion of taxonomy-aligned economic activity referred to in Section 4.31 of Annexes I and II to Delegated Regulation 2021/2139 in the numerator of applicable KPI	-	-	-	-	-	-
7.	Amount and proportion of other taxonomy-aligned economic activities not referred to in rows 1 to 6 above in the numerator of the applicable KPI	37.6	100%	10.1	100%	83.8	100%
8.	**Total amount and proportion of taxonomy-aligned economic activities in the numerator of the applicable KPI**	37.6	**100%**	10.1	**100%**	83.8	**100%**

Please note that taking into account that MOL Group does not have nuclear energy related activities, row 1-3 from above table have been excluded.

Table 6: Taxonomy-aligned economic activities (numerator)

	Economic activities	TURNOVER		OPEX		CAPEX	
		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)	
		USDmn	%	USDmn	%	USDmn	%
4.	Amount and proportion of taxonomy-eligible but not taxonomy-aligned economic activity referred to in Section 4.29 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	0.1	0%	0.0	0%	1.8	0%
5.	Amount and proportion of taxonomy-eligible but not taxonomy-aligned economic activity referred to in Section 4.30 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	-	-	-	-	-	-
6.	Amount and proportion of taxonomy-eligible but not taxonomy-aligned economic activity referred to in Section 4.31 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	-	-	-	-	-	-
7.	Amount and proportion of other taxonomy-eligible but not taxonomy-aligned economic activities not referred to in rows 1 to 6 above in the denominator of the applicable KPI	2 222.7	100%	377.3	100%	283.0	99%

8.	**Total amount and proportion of taxonomy eligible but not taxonomy- aligned economic activities in the denominator of the applicable KPI**	2 222.9	**100%**	377.3	**100%**	284.7	**100%**

Please note that taking into account that MOL Group does not have nuclear energy related activities, row 1-3 from above table have been excluded.

Table 7: Taxonomy-eligible but not taxonomy-aligned economic activities

In the case of the classification of non-eligible activities ("*taxonomy non-eligible fossil gas related activities*")[32] a full value chain approach has been applied. Figures reflect the following methodology, including elements: E&P gas related activities, gas midstream, gas trading and gas sales through the service station network. For details, please see *Table 8*.

	Economic activities	TURNOVER		OPEX		CAPEX	
		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)		Climate Change Mitigation (CCM)	
		USDmn	%	USDmn	%	USDmn	%
4.	Amount and proportion of economic activity referred to in row 4 of Template 1 that is taxonomy-non-eligible in accordance with Section 4.29 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	1561.4	6%	101.3	6%	47.4	2%
5.	Amount and proportion of economic activity referred to in row 5 of Template 1 that is taxonomy-non-eligible in accordance with Section 4.30 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	-	-	-	-	-	-
6.	Amount and proportion of economic activity referred to in row 6 of Template 1 that is taxonomy-non-eligible in accordance with Section 4.31 of Annexes I and II to Delegated Regulation 2021/2139 in the denominator of the applicable KPI	-	-	-	-	-	-
7.	Amount and proportion of other taxonomy-non-eligible economic activities not referred to in rows 1 to 6 above in the denominator of the applicable KPI	21 228.3	84%	1 081.1	65%	1 596.6	77%
8.	**Total amount and proportion of taxonomy-non-eligible economic activities in the denominator of the applicable KPI**'	22 789.7	**91%**	1 182.4	**72%**	1 644.0	**79%**

Please note: (1)Taking into account that MOL Group does not have nuclear energy related activities, row 1-3 from above table have been excluded. (2) All gas value chain related non-eligible activities are allocated under point 4. in above table.

Table 8: Taxonomy non-eligible economic activities

[32] Article 2 (1) 7. (c) point of the Amending Delegated Regulation (EU) 2021/2139 as regards economic activities in certain energy sectors and Delegated Regulation (EU) 2021/2178 as regards specific public disclosures for those economic activities ((EU 2022/1214)

POLLUTION

/E2/

IMPACTS AND RISKS RELATED TO POLLUTION

/E2. IRO-1/

ESRS	Disclosure Requirement related to ESRS 2 IRO-1
GRI	GRI 3, 3-3 b
IFRS	

MOL Group's 2024 double materiality assessment examined how pollution from the company's operations impacts environment and people (see: Chapter S3 of this report), as well as the financial implications of these effects on the company. The general methodology and consultation process are detailed in section ESRS 2 IRO-1 of this report, while specific procedures for identifying actual and potential pollution-related impacts and risks are outlined in Element 2: Risk & Change Management (please see details in Chapter ESRS 2 of this report) and in Appendix 7/A of the ***HSE MS***. This process involves site assessments and hazard mapping to evaluate emissions to air and soil and groundwater conditions, supported by site inventories and categorization. Hazard rankings based on pollution levels are conducted to prioritize environmental and technology-related risks and determine necessary mitigation actions. Insights from this process are integrated into the double materiality assessment through engagement with internal environmental protection experts, ensuring a comprehensive evaluation of pollution-related risks and impacts.

MOL Group has identified 3 pollution related impacts, 1 risk and no opportunities in the 2024 double materiality assessment. As a result, we concluded the topic Pollution to be material from impact perspective. From financial perspective, currently (on the short- and medium term) we consider pollution as non-material topic due to the low likelihood and low magnitude of the financial effect.

The list of impacts and risks which are described in the tables below:

Table IM-03: Effect on air quality

Severity	Moderate negative impact
Scope	Local (in potentially territorial)
Likelihood	Actual impact
Description	MOL Group's industrial operations and actors in its value chain emit gases which negatively affect the health of people and other living organisations, such as Sulphur Dioxide (SO2), Nitrogen Oxides (NOX), Volatile Organic Compounds (VOC), Carbon Monoxide (CO) and Particulate Matters (PM) and pollutants specified by the E-PRTR regulation.
Mitigation actions & remendability	MOL Group is committed to monitoring and controlling emissions, as well as actively implementing emission reduction actions. This commitment involves tracking emission levels, analysing sources, and adopting measures designed to reduce the overall environmental impact. The company is dedicated towards improving air quality and to restoring and enhancing the surrounding environment to the fullest possible extent, but irremediable cases are possible.
Time horizons	We consider the matter material on all time horizons for all oil and gas assets.
Relevance in the value chain	Pollution is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical and in the Circular Economy Services business segments (currently under integration – therefore related disclosures are primarily qualitative).

Table IM-04: Spills

Severity	Moderate negative impact
Scope	Local (in potentially territorial)
Likelihood	Potential impact, medium likelihood
Description	MOL Group, as an oil, gas and petrochemical company is involved in the production, use, distribution and commercialisation of chemical substances. MOL Group puts great emphasis on operational safety when handling materials posing threat to the environment. However, malfunctions or accidents during operation might lead to spills or leaks of such materials to the environment adversely affecting the quality of water, soil and thereby living organisms.
Mitigation actions & remendability	MOL Group adheres to strict safety protocols and handling procedures, prioritizes education, performs maintenance actions, conducts regular controls, and takes remediation actions where necessary. These practices ensure a high standard of safety and operational efficiency. In the event of a spill, the company recognizes that effective remediation is essential. MOL Group's comprehensive response plans are designed to swiftly contain and clean up spills, minimizing environmental impact and restoring affected areas.
Time horizons	We consider the matter material on all time horizons for all oil and gas assets.

Relevance in the value chain	Pollution is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical, Logistics and in the Circular Economy Services business segments (currently under integration – therefore related disclosures are primarily qualitative).

Table RK-05: Risk of increased cost of environmental load reduction

Type	Operational and legal risk
Likelihood	Low
Magnitude of financial effect	Low
Description	MOL Group puts great emphasis on controlling the emission of pollutants. However, as a consequence of increasingly stringent environmental regulation (e.g., IED) and during unusual industrial activates (such as turnarounds, asset replacements, maintenance or accidents) the risk of increased environmental impact can lead to financial consequences to the company in the form of increased CAPEX, OPEX and potential compensations or liabilities.
Related impact & dependencies	Related environmental impacts relate to air quality (IM-03) and water discharges (IM-05). Impact on affected communities are detailed in IM-17.
Mitigation actions	See mitigation action in: Tables IM-03 & IM-04 above, and DR E2-2 below in this chapter.
Financial effect & time horizons	Identified financial effects include mitigation and remediation actions and expenditures on projects to ensure compliance with more stringent emission limits due to IED & related national implementations. As the aforementioned increase of the stringency environmental regulations are likely to only materialize after 2030, we only consider this risk financially material on the long-term.
Relevance in the value chain	Pollution is material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical, Logistics and in the Circular Economy Services business segments (currently under integration – therefore related disclosures are primarily qualitative).

The pollution related impacts and risks has strong interconnections with other environmental and social topics, such as water, waste, affected communities and biodiversity. Please see these described in the respective chapters:

- IM-05: Water discharges (Chapter E3)
- IM-06: Operations in areas in or near areas with high environmental value (Chapter E4)
- IM-08: Waste generation (Chapter E5)
- IM-17: Disturbance from operations (Chapter S3)

Description of how MOL Group manages its pollution related impacts and risks is described in the remainder of this chapter.

POLICIES RELATED TO POLLUTION

/E2-1/

MOL Group recognises the potential environmental impacts associated with its industrial operations, particularly in relation to pollution risks such contamination, air emissions and spills. To mitigate these risks and ensure the protection of air, soil and groundwater, the company has established comprehensive policies and practices that prioritise prevention, effective risk management, and long-term remediation. The following section outlines the MOL Group's relevant policies.

General policy commitments related to HSE are outlined in the ***Group HSE and Social Impact Policy*** and ***Health Safety and Environment Area Book***. For general information in these policy documents please refer to Chapter E1.

Pollution-specific process-based regulations addressing mitigating negative impacts related to pollution of air, water and soil are outlined in the Environmental Stewardship element of the HSE MS. General principles of MOL Group's Environmental Stewardship include:

- All the operated technologies are in compliance with the associated emission limits (BAT-AEL) and associated emission performance levels (BAT-AEPL) included in the relevant Best Available Technique conclusions, as transposed to individual permits (e.g. integrated permits), and the relevant best available technology standards where Best Available Techniques Reference Documents are not available.
- The best available techniques with the lowest emission level are considered during the design of new technology or purchase of new equipment, ensuring compliance with the strictest limits and performance levels.
- All operated sites undergo a regular check in order to identify the non-compliances, action plans are prepared and followed up.

Policies related effect on air quality (IM-03, RK-06) are described in the 'Air protection' section of HSE MS:

- Technology related pollutants are measured or calculated, and an action plan is prepared and implemented to reduce air emissions where it is relevant.
- Air emission data is regularly assessed and the results are used to support the maintenance and adjustment of equipment.

Policies related to reducing contamination and handling issues such as spills (IM-04) and financial risks due to environmental load (RK-06) are described in the 'Soil and groundwater' section of HSE MS:

- Desktop risk assessment is performed (and updated after relevant changes) for all operated sites, action plans/remediation programs – describing the necessary actions, foreseeable financial demands, responsibilities and a timeline – are prepared for high risk findings.
- The first priority is always prevention, with a risk based mechanical integrity program that includes regular checks and risk-based actions both on-site and off-site.
- Environmental performance must be considered when selecting remediation technologies.
- Long-term remediation programs are subject to regular independent reviews.
- Design limits are based on the requirements of the local regulations, where applicable; where local regulations or limits do not exist, the regulation refers to the limits to be kept.
- When selling assets, it is ensured that risks associated with soil and groundwater contamination are assessed and necessary risk mitigation measures are implemented.
- For acquisitions, a risk-based approach is adopted as part of the environmental due diligence process.

In its industrial processes, MOL Group handles substances of concern that may pose significant risks to human health and the environment. Recognizing these potential hazards, the company places a strong emphasis on the careful management of these substances and the prevention of associated risks. This report adopts an output-focused approach, providing details on the quantities of substances of concern that leave our facilities as products, components of products, or emissions, as well as outlining the policies and principles guiding their management. **Process-based regulations related substances of concern** are outlined in Element 8: Information & Documentation within the HSE MS:

- The company has established a robust process for documenting and managing hazardous materials in line with legal and HSE requirements. Information related to hazardous substances, including their identification, associated risks, and necessary controls, is systematically maintained, regularly reviewed, and kept up-to-date to ensure compliance and effective risk management. These documents are accessible in appropriate languages and supported by guidance or training to ensure proper implementation by all relevant stakeholders.
- Product stewardship local processes identify risks related to dangerous substances/products at an early stage and manage those risks along the value chain (i.e. development, authorization, registration and restrictions on their manufacture, market distribution, use, disposal or recycle), thereby enabling adequate protection of human health and the environment.
- New product assessments are locally conducted prior to introduction of product to market to identify and address HSE hazards and risk associated with their normal use and potential misuse.
- Periodic re-assessments are conducted if product specifications change, including the identification and review of adverse effects that are reported or experienced. All the information that the company possesses throughout manufacturing and distribution for all dangerous products is collected and kept updated.
- Local control processes are in place and operating to cover all aspects of the introduction of new products or substances into manufacturing or operational processes.
- Processes are in place and operational to ensure that operating conditions and risk management measures as defined in relevant Exposure Scenarios materials and substances are included in relevant risk assessments.
- Preparation and handling of Safety Data Sheets, packaging and labelling of products/goods is locally defined and controlled.
- Local processes are developed to include a REACH-relevant (REACH Regulation (EC) No 1907/2006) clause in contracts for all chemicals that are procured.

Disclosures related to avoiding, controlling and limiting (both environmental and health-related) impacts of incidents and emergency situations can be found in Chapter S1-B of this report (Process Safety & Management).

ACTIONS AND RESOURCES RELATED TO POLLUTION

/E2-2/

ESRS	Disclosure Requirement E2-2
GRI	GRI 3, 3-3

The section outlines the pollution-related actions, the key steps taken to meet policy objectives focusing on how they relate to managing the identified impacts and risks, and resources allocated to these efforts.

- To minimise emissions and maintain air quality (IM-03), MOL Group's regular actions include regulatory-compliant emission and air quality measurements such as discontinuous, continuous, and Leak Detection and Repair (LDAR) programs, as well as additional monitoring tailored to internal technological needs. Air-related studies and documentation to support compliance and the development of effective emission control strategies are regularly prepared. In 2024, the total cost of these regular processes were USD 1.6 million (with no significant change in costs compared to 2023 on similar matters).

- In 2024, MOL Group implemented regular soil and groundwater management measures (IM-04, RK-06), including remediation services such as intervention planning, licensing, monitoring, post-monitoring, soil excavation, replacement, and other related investment projects. Site remediation and monitoring activities were supported by laboratory analyses of monitoring samples to ensure effective oversight. The company also engaged experts for waste excavation supervision during emergency situations or soil replacement efforts. Additionally, geological and hydrogeological studies, surveys, and related documentation are conducted regularly to support soil and groundwater protection initiatives. Total cost of management actions accounted for USD 5.2 million, 26.8% more than in 2023 (USD 4.1 million).
- To ensure safety and compliance with REACH and other hazardous material and product safety regulations, MOL Group implemented actions with a total cost of USD 0.24 million, 26.9% lower compared to USD 0.33 million in the previous year. These included visual signs, product stewardship and regulatory documentation.

Besides the above listed regular operative measures, MOL Group has multiple projects under implementation which has relevancy with pollution prevention and other environmental objectives. Ensuring that our assets align with Best Available Technology (BAT) regulations is a key priority. BAT represents the most effective and advanced stage of development in industrial techniques, ensuring that facilities operate efficiently while meeting the highest environmental standards.

MOL Group is investing in advanced waste incineration facilities, significantly reducing the need for landfilling and related greenhouse gas emissions. One prominent project is in Százhalombatta, where a state-of-the-art mixed waste utilization facility is being developed with an annual capacity of 360,000 tons. The facility will feature a closed system to prevent odor, dust, and noise load of the environment, with waste unloaded directly into enclosed spaces. Equipped with five-stage flue gas cleaning technology, the facility will operate in compliance with the BAT associated emission levels. Additionally, inert slag from incineration will be reused based on proven international practices. The facility will also provide energy to replace a significant portion of the Dunai Refinery's natural gas and electricity consumption. With support from an experienced Danish partner, the facility is expected to be operational by mid-2028.

MOL Group is undertaking multiple projects to enhance wastewater treatment processes, including the implementation of scrubber equipment and caustic oxidation units. These investments, targeting the refinery at Százhalombatta and the petrochemical plant in Tiszaújváros, aim to reduce the burden on wastewater treatment plants and to further improve the quality of discharged water. By adopting advanced technologies, MOL Group minimizes its impact on local water bodies.

INA has been actively addressing historical pollution at the Urinj Peninsula, caused by decades of hydrocarbon accumulation in permeable karst subsoil. The major remediation activities started in 2023, and continued until November 2024 with approximately an EUR 4.5 million in these remediation budget. Drilling 21 new wells (including four outside the refinery perimeter) and 20 submersible pumps has been installed to enable more efficient hydrocarbon extraction from the subsoil, reducing the potential for pollutants to reach the sea. 220 meters of new, durable ocean dams were contracted to protect the sea from pollution during adverse weather conditions. Sewage systems, tanks and bund has been rehabilitated to prevent hydrocarbon leakage from refinery infrastructure.

In Slovakia, Slovnaft has intensified remediation at Klacany logistics depot to prevent aromatic contamination migration. Furthermore, Slovnaft obtained permanent operation permits for 12 new GWPS wells, and implemented innovative sludge management techniques at its waste water treatment facility.

In 2024, 40 incidents of spilling more than 1 bbl of hydrocarbon content have been registered on Group-level, with a total of 538 m^3 spilled to the environment. By far the biggest spill happened due to a leak on the 190 km long product pipeline between Százhalombatta and Pécs. The malfunction was found in the outskirts of Gárdony on October 16. A crack of barely 10 centimeters formed on the pipeline, which lies nearly two meters deep, through which up to 487 m^3 of diesel leaked into the soil at the site of the incident. The damaged section of the pipeline was immediately shut down, the leak was stopped within two days, and the faulty part was replaced. According to the investigations (still ongoing by the closure of this report), the contamination can be detected in an area of 50 meters and does not pose a threat to the fish pond or Lake Velence. After the closure of the investigation MOL will submit the intervention plan for review and approval to the relevant authority, and as always and will inform those affected.

TARGETS RELATED TO POLLUTION

/E2-3/

In line with the commitments and policy objectives laid down in the previous section, MOL Group has set 2 measurable, timebound targets in 2025 related to pollution mitigation:

- **Maintaining SOx Emissions at Baseline Levels by 2040:** MOL Group is committed to maintaining its SOx (sulfur oxides) emissions in 2040 at the same level as the average emissions recorded in 2021 and 2022. The baseline value for this target is determined as the mean of SOx emissions during these years, calculated at **4,026 tonnes** (2021: 3,409 tonnes; 2022: 4,643 tonnes).

- **Maintaining NOx Emissions at Baseline Levels by 2040:** MOL Group aims to keep its NOx (nitrogen oxides) emissions in 2040 consistent with the average emissions levels recorded in 2021 and 2022. The baseline for this target is the mean of emissions from these years, calculated at 5,433 tonnes (2021: 5,324 tonnes; 2022: 5,541 tonnes).

These voluntary targets reflects MOL Group's dedication to minimizing the environmental impact of its operations, particularly in areas prone to air quality challenges, by focusing on operational efficiency and maintaining stringent control over emission sources in all operated companies.

METRICS RELATED TO AIR, WATER AND SOIL POLLUTION

/E2-4/

ESRS	Disclosure Requirement E2-4
GRI	GRI 305, 305-7

This section details the pollutants emitted by MOL Group to air, water, and soil. It includes consolidated emissions from facilities under financial or operational control and provide details on measurement methodologies and data collection processes.

- During 2024, sulphur dioxide (SO_2) emissions significantly decreased by 20.8% compared to 2023 levels, dropping from 4,647 tonnes to 3,678 tonnes. This reduction was mainly driven by the Refining segment, where SO_2 emissions declined by 21.7%.
- Nitrogen oxides (NO_x) emissions slightly decreased by 0.8% to 5,370 tonnes in 2024 from 5,413 tonnes in 2023.
- Volatile Organic Compounds (VOC) emissions decreased by 3.7%, from 7,851 tonnes in 2023 to 7,560 tonnes in 2024.
- Carbon monoxide (CO) emissions, on the other hand, increased by 8.5% in 2024, reaching 1,114 tonnes compared to 1,026 tonnes in 2023. This increase was primarily driven by the Refining segment, where CO emissions rose by 22.4%.
- Particulate Matter (PM) emissions decreased significantly by 24.5% from 212 tonnes in 2023 to 160 tonnes in 2024.

Particulate Matter (PM) emissions decreased significantly by 24.5% from 212 tonnes in 2023 to 160 tonnes in 2024.

AIR EMISSIONS[33]	UNIT OF MEASURE	2024	2023	ESRS
Sulphur Dioxide (SO_2)	**tonnes**	3 678	**4 647**	E2-4_02
o/w Refining	tonnes	2 554	3 262	E2-4_02
o/w Petrochemicals	tonnes	44	40	E2-4_02
o/w Upstream	tonnes	28	29	E2-4_02
Nitrogen Oxides (NO_X)	**tonnes**	5 370	**5 413**	E2-4_02
o/w Refining	tonnes	2 204	2 237	E2-4_02
o/w Petrochemicals	tonnes	1 039	985	E2-4_02
o/w Upstream	tonnes	407	461	E2-4_02
Volatile Organic Compounds (VOC)	**tonnes**	7 560	**7 851**	E2-4_02
o/w Refining	tonnes	2 347	2 211	E2-4_02
o/w Petrochemicals	tonnes	128	178	E2-4_02
o/w Upstream	tonnes	3 146	3 600	E2-4_02
Carbon Monoxide (CO)	**tonnes**	1 114	**1 026**	E2-4_02
o/w Refining	tonnes	783	640	E2-4_02
o/w Petrochemicals	tonnes	54	138	E2-4_02
o/w Upstream	tonnes	224	202	E2-4_02
Particulate Matter (PM)	**tonnes**	160	**212**	E2-4_02
o/w Refining	tonnes	124	158	E2-4_02
o/w Petrochemicals	tonnes	15	11	E2-4_02
o/w Upstream	tonnes	2	2	E2-4_02
Hydro-fluorocarbons (HFCs)	**tonnes**	0	-	E2-4_02
Ammonia (NH_3)	**tonnes**	0	-	E2-4_02
PCDD + PCDF (dioxins + furans)	**tonnes**	0	-	E2-4_02
Nickel and compounds (Ni)	**tonnes**	0.4	-	E2-4_02
o/w Power and Heat Generation	tonnes	0.4	-	E2-4_02
Benzene	**tonnes**	17	-	E2-4_02
o/w Refining	tonnes	17	-	E2-4_02

WATER CONTAMINANTS	UNIT OF MEASURE	2024	2023	ESRS
Total Petroleum Hydrocarbons (TPH)	tonnes	19	20	E2-4_03

[33] The breakdown by business segments includes only the main segments, therefore their sum is not equal to the value in the summary row.

WATER CONTAMINANTS	UNIT OF MEASURE	2024	2023	ESRS
Chemical Oxygen Demand (COD)	tonnes	1 943	1 791	E2-4_03
Biological Oxygen Demand (BOD)	tonnes	329	281	E2-4_03
Suspended Solid (SS)	tonnes	821	766	E2-4_03
Chromium and Compounds (Cr)	tonnes	0.1	-	E2-4_03
Tetracloroethylene (PER)	tonnes	0	-	E2-4_03
Trichloroethylene	tonnes	0	-	E2-4_03
Trichloromethane	tonnes	0	-	E2-4_03
Total nitrogen	tonnes	1.2	-	E2-4_03
Anthracene	tonnes	0	-	E2-4_03
Benzene	tonnes	0	-	E2-4_03
Cadmium and compounds (Cd)	tonnes	0	-	E2-4_03
Copper and compounds (Cu)	tonnes	0.7	-	E2-4_03
Naphthalene	tonnes	0	-	E2-4_03
Phenols (as total C)	tonnes	2	-	E2-4_03
Lead and compounds (Pb)	tonnes	0.1	-	E2-4_03
Zinc and compounds (Zn)	tonnes	6.3	-	E2-4_03
Polycyclic aromatic hydrocarbons (PAHs)	tonnes	0	-	E2-4_03
Toluene	tonnes	0	-	E2-4_03
Phosphorus	tonnes	0.1	-	E2-4_03
Mercury and compounds (Hg)	tonnes	0	-	E2-4_03
Xylenes	tonnes	0	-	E2-4_03
Fluoranthene	tonnes	0	-	E2-4_03
Chlorides (as total Cl)	tonnes	0	-	E2-4_03
Nickel and compounds (as Ni)	tonnes	0.2	-	E2-4_03
Benzo(g,h,i)perylene	tonnes	0	-	E2-4_03

Air emission calculation methodology

MOL Group calculates air emissions based on its internal Reporting Handbook. The organization can use one of the following methods:

- **Direct Measurement**: Using periodic measurements or online analyzers.
- **Site-Specific Data**: Calculations based on data specific to the site.
- **Published Emission Factors**: Using established emission factors.
- **Estimation**: If default figures are unavailable, estimations can be used. The basis for these estimations must be indicated.

Water Emission Calculation Methodology

Water emissions must be reported based on regular laboratory analysis. The frequency of this analysis is usually specified in the environmental permit for each site. If not, the frequency should be based on the variability of the sources and the reproducibility of the test methods.

- Equivalent Test Methods: These can be used with appropriate conversions.
- Record Keeping: Maintain full records of all assumptions, calculation procedures, and test methods for inspection and audit purposes.
- Extrapolation: Use only when justified and no legal requirement for regular analysis exists.
- Detection Limits: If emission measurements are below the detection limit, record the emission as 0.
- Irrelevant Indicators: Sites where these indicators are irrelevant (e.g., office activities) and/or no defined obligation exist to measure pollutants (eg. in some service stations in Retail) will report a zero value.

Reporting Coverage

Relevant MOL Group Operating Companies must report the total quantity of air emissions from routine operations, emergencies, start-ups, and shutdowns, including fugitive emissions. This includes:

- Total Quantities: Emissions covered by environmental permits, international conventions, or national laws/regulations.
- Routine Process Emissions: Regular emissions from standard operations.
- Abnormal Process Emissions: Emissions from start-ups, upsets, well testing, extended well tests, etc.
- Maintenance Activities: Emissions from activities like tank purging.

- Emergencies/Accidental Releases: Emissions from incidents like loss of primary containment (LOPC), emergency flaring, equipment failure, etc.
- Combustion Emissions: Emissions from product transportation by company-owned shipping (tankers, boats, barges). Shipping by contracted haulers is excluded.
- Fugitive Emissions: Non-channelled emissions to air.

Inventory of Air Polluting Sources

Each MOL Group Operated Companies must identify and maintain an inventory of its specific air polluting sources, including:

- Stationary Sources: Boilers, fired heaters, waste incinerators, gas turbines, gas engines, diesel engines, and other emission sources.
- Diffuse Sources: Non-channelled emissions, including fugitive and non-fugitive emissions from shipping operations, process vents, storage tanks, loading/unloading of hydrocarbon liquids, flaring, cooling towers, and other non-combustion particulate sources.

Volatile Organic Compounds (VOC) includes a broader category of emissions, including benzene and toluene. While the reporting of specific pollutants is based on regulatory requirements related to point source emissions, VOC is a broader category which includes not only point source emissions, but fugitive emissions as well.

Water Emission Reporting

For internal reporting, MOL Group sites and business units will monitor and report the following water discharge data:

- TPH (Total Petroleum Hydrocarbon)
- COD (Chemical Oxygen Demand)
- BOD (Biological Oxygen Demand)
- TSS (Total Suspended Solids)
- All pollutants listed in the European Pollutant Release and Transfer Register (E-PRTR), established under Regulation (EC) No 166/2006

General Principles

- Reporting Unit: Chemical concentrations of water emissions are reported in tonnes (t).
- Reporting Requirements: Only units that discharge treated or untreated wastewater outside MOL Group boundaries (e.g., surface water, groundwater, public sewers, external wastewater treatment plants) must report.
- Laboratory Analysis: Figures must be based on regular laboratory analysis. If no environmental permit specifies the frequency, it should be based on the variability of sources and test method reproducibility. Equivalent test methods can be used with appropriate conversions.
- Record Keeping: Maintain full records of all assumptions, calculation procedures, and test methods for inspection and audit purposes.
- Detection Limits: If emission measurements are below the detection limit, record the emission as 0.
- Irrelevant Indicators: Sites where these indicators are irrelevant (e.g., office activities) will report a zero value.
- Mass Emission Estimation: Annual mass emissions are usually calculated based on periodic measurements of parameters or species concentration and flow rate.

INFORMATION ON SUBSTANCES OF CONCERN & SUBSTANCES OF VERY HIGH CONCERN

/E2-5/

MOL Group produces, transports, and commercializes a wide range of fossil fuels and refined oil and gas products, many of which have the potential to impact the environment and human health. Certain products fall within the categories of Substances of Concern (SOC) and Substances of Very High Concern (SVHC) as defined by the ESRS.

The potential risks associated with spills and accidental releases of these substances have been identified as material topics for MOL Group under Impact Metric IM-10 (Spills). To mitigate these risks, MOL Group implements stringent policies and risk management measures in accordance with REACH and other relevant local regulations, as detailed in Section E2-1 (Policies Related to Pollution). Despite these efforts, system integrity failures and accidental leaks may still pose hazards to the environment and human health.

The table below lists the key product groups containing SOC and SVHC, along with their respective hazard classifications. The quantities of procured, produced, and commercialized products are detailed in Chapter E5-4 (Resource Inflows) and E5-5 (Resource Outflows).

Product group	Hazard classes	Amount (2024)
Crude oils	• Carcinogenicity Category 1A • Chronic hazard to the aquatic environment category 2 • Germ Cell Mutagenicity Category 1B • Specific Target Organ Toxicity - Repeated Exposure Category 2 • Substances of very high concern	• Total Group production: 39,77 mboe/day • Refinery processing: 13 306 kt • Purchased and sold products: 4 615 kt
Naphtha products	• Carcinogenicity Category 2 • Reproductive Toxicity Category 2 • Specific Target Organ Toxicity - Single Exposure Category 2 • Hazardous to the Aquatic Environment - Chronic Category 1 • Substances of very high concern	• Refinery production: 391 kt • Sales: 348 kt
Motor gasolines	• Germ Cell Mutagenicity Category 1B Carcinogenicity Category 1B • Reproductive Toxicity Category 2 • Hazardous to the Aquatic Environment - Chronic Category 2 • Substances of very high concern	• Refinery production: 3 154 kt • Sales: 3 802 kt
Diesel and heating oils	• Carcinogenicity categories 1 and 2 • Specific Target Organ Toxicity - Repeated Exposure Category 2 • Hazardous to the Aquatic Environment - Chronic Category 2	• Refinery production: 6 702 kt • Sales: 11 505 kt
Kerosenes	• Hazardous to the Aquatic Environment - Chronic Category 2	• Refinery production: 537 kt • Sales: 713 kt
Fuel oils	• Reproductive Toxicity Category 2 • Germ Cell Mutagenicity Category 2 • Carcinogenicity Category 1B • Specific Target Organ Toxicity - Repeated Exposure Category 2 • Hazardous to the Aquatic Environment - Chronic Category 1 • Substances of very high concern	• Refinery production: 279 kt • Sales: 237 kt
Butadiene	• Germ Cell Mutagenicity Category 1B • Carcinogenicity Category 1A	• Petrochemical production: 74 kt • Sales: 76 kt
Raffinate	• Germ Cell Mutagenicity Category 1B • Carcinogenicity Category 1A • Specific Target Organ Toxicity - Single Exposure Category 3 • Hazardous to the Aquatic Environment - Chronic Category 2	• Petrochemical production: 114 kt • Sales: 0 kt

Please note only that the above table includes the material product groups which has SOC or SVHC content. Comprehensive list of all produced and commercialised material in 2024 cannot be provided on Group level as compliance with relevant regulations are managed locally at different companies within MOL Group's portfolio. Group level data collection process is under development.

WATER STEWARDSHIP

/E3/

IDENTIFIED WATER-RELATED IMPACTS

/E3. IRO-1/

ESRS	Disclosure Requirement 2 IRO-1
GRI	GRI 303-1-a;b GRI 303-1-c
IFRS	IFRS S1.55(b)(i)

MOL Group's double materiality assessment conducted in 2024 covered how the use of water and marine resources by the company affect people and the environment, and what is the financial effect of these impacts and the dependencies on water and marine resources for the company. The general methodology and consultation process are detailed in section *Impact, risk and opportunity management related to materiality assessment process* of this report, while specific procedures for identifying actual and potential water-related impacts and risks are outlined in Element 2: Risk & Change Management and in see *Section E3-1 - Policies: Water use* of this chapter.

MOL Group's 2024 double materiality assessment concluded that the company has a moderate impact on the environment due its water withdrawal, therefore, the topic is considered material from impact perspective. Since no significant risks or opportunities have been identified related to water or marine resources, we do not consider it material from financial perspective. Identified impact of MOL Group on the environment due to water discharges is described in the table below.

Table IM-05: Water discharges

Severity	Moderate negative impact
Scope	Territorial
Likelihood	Low
Description	For its industrial operations, MOL Group withdraws significant amount of water (ca. 100 million m3 in 2024). MOL Group constantly monitors and controls the content of water discharges to minimize the risk of potential adverse effects of any polluting materials ending up in the environment.
Mitigation actions & remendability	MOL Group prioritizes the monitoring and control of water discharge content to ensure environmental compliance and minimize the impact on water quality. This involves regular testing and management practices to maintain standards and prevent contamination. In terms of remendability, adverse effects from water discharges can often be addressed through effective restoration strategies, such as rehabilitating affected water bodies and enhancing filtration systems.
Time horizons	We consider the matter material on all time horizons for all oil and gas assets.
Relevance in the value chain	Impact of water discharge potentially material at the Upstream, Refining, Petrochemical, Logistics and in the Consumer Services business segments of the company.

The use of water resources has strong interconnections with other environmental and social topics, such as pollution, resource use, and biodiversity. Please see these described in the respective chapters:

- IM-05: Spills (Chapter E2)
- RK-05: Risk of increased cost of environmental load reduction (Chapter E2)
- IM-06: Operations in areas in or near areas with high environmental value (Chapter E4)

Description of how MOL Group manages its water related impacts is described in the reminder of this chapter.

POLICIES RELATED TO WATER USE

/E3-1/

ESRS	Disclosure Requirement E3-1
IFRS	IFRS S2.14(a)(i)

This section outlines the MOL Group's policies for managing the impacts related to water resources. It aims to provide a clear understanding of the company's approach to identifying, assessing, managing, and remediating these issues. General policy commitments related to HSE are outlined in the ***Group HSE and Social Impact Policy*** and ***Health Safety and Environment Area Book***.

Water management is a key part Mol Group's environmental stewardship commitments, with the purpose to reduce the negative environmental impact on the surface and subsurface water bodies. Relevant process-based regulations are outlined in the Environmental Stewardship element of the HSE MS:

- Risk-based quantity measurement is in place for water withdrawal and discharge. Over medium risk, what means 10% water withdrawal of MOL Group, measurements are highly recommended.
- Fresh water usage impact and economic assessment is prepared and risk based reduction plan is in place and implemented.
- Risk assessments are performed concerning water scarcity, particularly related to climate change impacts.
- Minimization of water consumption and freshwater intake is prioritized, especially in high and extremely high water-stressed areas.
- Efficient water usage practices are in place, including closed cooling circuits, tank cooling, and pressure tests. Grey water usage is preferred at owned office buildings and facilities.
- Quality standards are maintained for industrial waste water.
- Regular waste water quality data assessment is in place, feedback is provided to operators.
- Internal limits and operational discipline are maintained for wastewater treatment plants. It is ensured that waste water is not diluted. Implementation of best available techniques for wastewater treatment plants are ensured.
- Separated sewage system is established (contaminated/potentially contaminated and non-contaminated lines) in case of new and refurbished technologies.
- Water emergency drills are conducted. The frequency and the scenario has to be defined in local level regulations based on the main operational risks and business/site specifications.
- Water quality risks, are addressed through pollutant reduction plans.

ACTIONS RELATED WATER USE

/E3-2/

ESRS	Disclosure Requirement E3-2

IFRS	IFRS S2.14(a)(i)

The oil and gas industry consumes large amounts of water for the production facilities but it also produces large amounts of water due to the extraction of oil and gas. MOL Group is constantly focused on finding ways to improve the handling methods of these large quantities of water. These efforts include various regular measures to safeguard water resources, including projects aimed at reducing water intake and discharges, developing water pollution prevention plans, conducting surface water-related studies, water permitting, and monitoring and laboratory analyses of water and sewage releases as part of self-monitoring efforts. Emergency response initiatives are also established to protect surface water from pollution incidents. Allocated resources (annual HSE supervised operational expenses) to these actions were USD 5.9 million in 2024, 4.8% down from USD 6.2 million in 2023 (excluding soil and groundwater protection stated in the Actions: Pollution section).

On top of these regular activities, in 2024, MOL Petrochemical initiated a project to enhance the circularity of water by reusing purified wastewater from its Wastewater Treatment Units, which would otherwise be discharged into River Tisza. The project aims to optimise water use by utilizing existing pipelines and upgrading manual shut-off valves to motorized ones. This initiative brings multiple environmental and operational benefits: By recirculating wastewater, the project reduces the overall water extraction and minimizes the discharge load on the river. Additionally, significant energy savings can be achieved by optimizing pump operations, while the heat content of the purified wastewater can be utilized to reduce primary energy consumption, particularly natural gas, and chemical use. Another advantage is the automation of the firefighting system at MOL Petrochemical through the installation of motorized assemblies. While the current cost of natural surface water remains relatively low, future price increases are anticipated, making water reuse an economically sustainable solution. The project is financed through MOL Group's Green Fund, an internal financial mechanism designed to support investments with significant environmental benefits. The fund operates as an internal competition, prioritizing environmentally focused projects that have longer payback periods but remain economically viable.

Further information on actions related to water pollution mitigation and waste water treatment can be found in Section 'E2-2: Actions and resources related to pollution'.

TARGETS RELATED TO WATER

/E3-3/

ESRS	Disclosure Requirement E3-3
GRI	GRI 3-3 GRI 303-1-d GRI 303-1-d

In line with the commitments and policy objectives laid down in the previous section, MOL Group is targeting to achieve a 10% reduction in freshwater withdrawal by 2040 compared to the average withdrawal recorded in 2021 and 2022. The baseline for this target is the average of 76.4 million cubic meters. The target is voluntarily set and helps preserve water resources nearby MOL Group's operations, and prevent potential negative impacts on communities and water ecosystems.

METRICS RELATED TO WATER USE

/E3-4/

ESRS	Disclosure Requirement E3-4
GRI	GRI 3-3 GRI 303-5-a GRI 303-5-b GRI 303-5-c GRI 303-5-d GRI 303-3-a GRI 303-4-a

Total water withdrawal increased by 4.2% from 99.9 million m^3 to 104.1 million m^3 in 2024. A portion of this came from higher freshwater withdrawals, which grew by 3.5%, reaching 81.9 million m^3 in 2024 compared to 79.2 million m^3 in the previous year. Similarly, total water discharge also higher by 2.8%.

	UNIT OF MEASURE	2024	2023	ESRS
Water Consumption - Total	th m³	21 544	20 167	E3-4_01
Upstream	th m³	855	741	E3-4_09
- *o/w in regions with High or Extremely High Baseline Water Stress*	%	0	0	E3-4_02
Downstream Production (Refining and Petrochemicals)	th m³	17 230	15 690	E3-4_09
- *o/w in regions with High or Extremely High Baseline Water Stress*	%	0	0	E3-4_02
Midstream	th m³	3	-	E3-4_09
- *o/w in regions with High or Extremely High Baseline Water Stress*	%	0	-	E3-4_02
Other	th m³	3 459	**3 737**	E3-4_09
- *o/w in regions with High or Extremely High Baseline Water Stress*	%	0	0	E3-4_02
Water Withdrawal - Total	th m³	104 094	99 912	E3-4_11
Upstream	th m³	4 494	4 358	
Refining	th m³	76 475	70 664	
- *o/w Freshwater*	th m³	57 432	53 044	
Petrochemicals	th m³	13 459	15 173	
Other	th m³	9 666	9 716	
Water Discharge - Total	th m3	115 634	112 478	E3-4_12
o/w water discharge after primary treatment	th m³	59 306	55 466	
o/w water discharge after secondary treatment	th m³	7 507	7 644	
o/w water discharge after tertiary treatment	th m³	18 103	18 723	
o/w water discharge with no treatment	th m³	28 219	25 984	
o/w water transferred to third parties for treatment	th m³	2 506	1 840	

Measurement methodologies and assumptions regarding water Consumption, water withdrawal, and discharges are regulated in our Reporting Handbook as such:

Guidelines for Measuring and Reporting: The oil and gas industry handles substantial quantities of water from various sources. Of particular interest is the amount of fresh water utilized and ultimately consumed as a result of operations. This fresh water consumption metric is crucial for assessing resource efficiency. However, relying solely on fresh water intake volumes does not provide an accurate picture of actual water consumption, as some intake water passes through the facility without being depleted. Fresh water is consumed directly through evaporation and losses, been consumed by humans or incorporated into products. Evaporation and losses are estimated using the difference between intake and discharge volumes.

Fresh Water Consumption Calculation: Fresh water consumption is calculated by subtracting the amount of fresh water returned to a fresh water body from the total fresh water withdrawn by the MOL Group operated companies. Fresh water returned to fresh water bodies remains available to other users downstream, thus not removed from the regional water cycle.

Ensuring Accurate Consumption Calculations:

- Include water present in discharge streams in the total water withdrawal.
- Report only waters used for site purposes or produced waters in total withdrawal volumes, using measuring/metering or invoices.
- In the absence of measuring devices, volumes based on the best estimation (e.g. the pump's nominal capacity and operating hours)

Exclusions from Withdrawal Volumes:

- Water sold or used by third parties.

- Water processed by MOL Group Operated Companies for third parties.
- Fresh water taken over from another MOL reporting unit.

Inclusions in Withdrawal Volumes:

- Water from municipal supplies, utilities, tankers, and similar sources.
- Produced fresh water from refining operations, if not already included.
- Non-fresh water withdrawal, including seawater and water with total suspended solids greater than 1000 mg/L.
- Water used for once-through cooling systems and returned unchanged.
- Fresh water for household use.

Water Discharges:

- Wastewater removed by tankers is reported as discharge.
- Water processed or discharged by MOL Group Operated Companies for third parties is excluded from discharge reporting.
- Water transferred for treatment or reuse is included in the appropriate discharge field.
- Wastewater handed over to MOL Operated Companies' treatment plants is excluded from total fresh water discharge.
- Volumes are reported using measuring/metering or invoices, and based on the best estimation (eg. the pump's nominal capacity and operating hours

BIODIVERSITY

/E4/

IMPACTS, RISK AND OPPORTUNITIES RELATED TO BIODIVERSITY

/E4. IRO-1; E4. SBM-3/

ESRS	Disclosure Requirement related to ESRS 2 IRO-1; Disclosure Requirement E4.SBM-3
GRI	GRI 304-1-a-iv

The term biodiversity refers to the variability among living organisms from all sources and the ecological complexes of which they are part. However, it shall not be understood as a mere measure of variety, but as an indicator of the health of the environment. Loss of biodiversity due to human activity is a leading global concern. Based on the Kunming-Montreal Global biodiversity framework, the main direct drivers of biodiversity loss are changes in land and sea use, direct exploitation of organisms, climate change, pollution and the spread invasive alien species.

MOL Group acknowledges that its business model contributes to multiple of these drivers of environmental impact, primarily in the areas of climate change, pollution, and land use change. This chapter focuses on the latter—specifically outlining our policies, actions, targets, and indicators related to monitoring and mitigating the negative impacts of our operations on ecosystems due to land use changes. For disclosure on the other drivers please see Chapter E1 on Climate change, and Chapter E2 on Pollution.

MOL Group's double materiality assessment conducted in 2024 concluded that the company's upstream operations has material impact on the extent and condition of ecosystems– see details in Table IM-06 below. However, we have not identified risk and opportunities exceeding our financially materiality threshold stemming from this impact, or from any dependencies related to biodiversity and ecosystem. Description of the methodology is described in section ESRS 2 IRO-1 of this report. As a conclusion, topic biodiversity and ecosystem is considered material from impact perspective, but not from the financial perspective.

Table IM-06: Operations in areas in or near areas with high environmental value

Severity	Moderate negative impact
Scope	Local (i.e. at upstream operational sites)
Likelihood	Medium
Description	To obtain its main raw material, crude oil, MOL Group and its suppliers engage in exploration & production activities temporarily changing the land-use of certain areas, and potentially causing the disturbance of wildlife through light and noise pollution.
Mitigation actions & irremediability	MOL Group's approach includes preliminary screening, implementing mitigation measures to ensure minimal disturbance, and taking remediation actions when necessary. This helps to effectively manage potential impacts and address any issues that arise. MOL Group recognizes that while some impacts on

	high-value environmental areas can be remedied through effective restoration practices, others may be more challenging to reverse. The company is committed to restore any affected areas to their natural state whenever possible, guided by best practices and regulatory requirements.
Time horizons	We consider the matter material across all time horizons in case of oil exploration & production activities.
Relevance in the value chain	MOL Group's Upstream activities has material impact on the extent and condition of ecosystems. Relevant sites are described in section E4-5 of this chapter.

POLICIES RELATED TO BIODIVERSITY AND ECOSYSTEMS

/E4-2/

Establishment of new facilities, mainly related to exploration & production activities affect the land-use of certain areas, and potentially cause the disturbance of ecosystems. Element 7 of the **HSE MS** requires to regularly conduct biodiversity impact assessments and Action Plans (BAPs) for all sites in protected areas and next to water sources, and to minimise the biodiversity impacts of greenfield developments during the design.

MOL Group recognizes that while some impacts on high-value environmental areas can be remedied through effective restoration practices, others may be more challenging to reverse. However, the company is committed to restore any affected areas to their natural state whenever possible, guided by regulatory requirements and best practices as the Management and Remediation of Sites in the Petroleum Industry, issued by IPIECA. Appendix 2/A of the **HSE MS** provides detailed rules for the remediation and liability management of abandoned sites, with the primary goal of achieving an environment where manmade contaminants do not significantly impact human health and ecosystems. (IM-06). The document is applicable for owned, leased, or sold sites and facilities where the liability has been retained. In summary, the process description requires the following process:

Site assessment, hazard mapping and ranking: Entities are required to have site inventories which include owned and leased sites and to know the status of soil and groundwater for each site/location prior to the site assessment and hazard ranking process. For sites where information is not available about soil and groundwater status, or at sites with known contamination but without corrective action, a hazard ranking shall be performed. The output scores of the assessment should be weighted and sites categorized according hazard ranking levels.

Remediation action plan development: A remediation action planning involves identifying necessary actions for high/medium risk sites, revising the plan annually based on new information, and using baseline studies and statutory resolutions for production sites under the Industrial Emission Directive (IED). The remediation action plan shall include:

a) Actions to be implemented for each ranked site;
b) The required timeline for the remediation action plan is 12 years. Remediation actions shall be scheduled and actions must be identified at all high risk category sites. The businesses concerned are liable for tasks described in the relevant laws, regulations, and statutory resolutions.
c) Actions plans must include a prioritized, up-to-date register of remediation liabilities and their financial demands for the next 12 years to act as input for business planning and to be a source of reliable data for annual balance sheets and financial reports, as IAS37 and IFRS specifications. According to Accounting policy, major future liabilities such as environmental obligations shall be covered by provisions. Environmental obligations shall mean any and all such environmental tasks taken or to be taken in order to reach the performance of which is required by necessity of an external regulation (for example, the laws of the country concerned, compulsory EU regulations, or official decisions) or by the constructive obligation of the Company. Other refinements based on the details prescribed in laws and regulations; statutory resolutions, and business processes.

Project implementation: For the management of sites under remediation, the principles of Risk-Based Corrective Action must be applied. This risk-based approach recognises the diversity of oil & gas industry sites, and describes a three-tiered approach to decision-making in which site assessment, risk assessment and corrective action activities are appropriately tailored to site-specific conditions and hazards. After the identification of an unacceptable risk associated with a site, a number of risk management strategies may be considered. The works may vary from simple risk mitigation measures to large-scale site remediation. The following corrective measures might be used:

a) Traditional remediation techniques that can reduce the concentrations of contaminants;
b) Exposure pathway elimination methods, such as capping and hydraulic containment;
c) Land-use restrictions (administrative and institutional controls - these are especially important at larger facilities);
d) Monitoring of natural attenuation between sources and receptors (for the purpose of validating the decision to take no further action).

Aftercare activities: After implementing the corrective actions, a site monitoring system should be put in place, as part of the corrective action assurance process. Monitoring phase can include a wide range of activities, including quality and quantity control of the given medium; photo-monitoring and data based monitoring.

ACTIONS RELATED TO BIODIVERSITY AND ECOSYSTEMS

/E4-3/

Monitoring activities in both protected areas and areas of high biodiversity value outside protected areas are essential for mitigating risks and managing biodiversity impacts. Continuous monitoring is conducted for all HSE-relevant activities in line with the HSE MS (HSE MS) and locally applicable policies, which are adapted to specific business activities, regulatory requirements, and environmental conditions. Where applicable, Biodiversity Impact Assessments are carried out, and if a negative impact is identified, Biodiversity Action Plans are developed and implemented. These efforts are reported to the Group level annually. In 2024, five Biodiversity Impact Assessments and 49 Biodiversity Action Plans were prepared for Exploration and Production activities. In these cases, environmental protection measures have been implemented to mitigate impacts on air, water, and soil to minimise effect on the natural environment and on local communities, if any. Air emissions from point sources are monitored through accredited measurements every one and five years. The disposal of produced water has been conducted in compliance with water law operating permits, with key water components analysed and results evaluated according to regulatory requirements. Groundwater contamination has been monitored at main collection stations to enable early detection and mitigation. Soil contamination resulting from technical failures has been addressed immediately, with affected areas rehabilitated as soon as possible. The technological system operates under pressure with continuous on-site supervision, while corrosion protection measures prevent underground pipeline perforation.

MOL Group operates across more than 200 companies and 2,000 sites, making it unfeasible to consolidate biodiversity actions or financial resource allocations at the Group level. Biodiversity measures are managed locally, tailored to regulatory requirements and environmental conditions, and integrated into decentralized environmental management systems. Consequently, defining "key actions" with a uniform scope, time horizon, or financial breakdown is not possible.

There is no standardized methodology to quantify or allocated financial resources for biodiversity-related actions across the Group. While impact assessments and action plans are conducted as required, these are managed at the entity or site level. As a result, MOL Group reports on biodiversity efforts at an aggregate level but does not provide a consolidated financial breakdown. For further financial information, please refer to the EU Taxonomy report, while noting that it does not fully reflect the actual efforts and allocated resources. For specific actions related to the protection and preservation of nature, please see case studies published on our website.

TARGETS RELATED TO BIODIVERSITY AND ECOSYSTEMS

/E4-4/

MOL Group has currently not adopted any targets on measurable biodiversity indicators. However, with MOL Group thrives to minimise its impacts on biodiversity and the ecosystem with stringent processes, and with targets related to the drivers of the biodiversity and ecosystem degradation – such as climate change, pollution and water-use. Please refer to the Targets section in other Environmental standards for further information.

METRICS RELATED TO BIODIVERSITY AND ECOSYSTEMS

/E4-5/

Table: Sites in or near protected areas:

Business unit	Number of sites	Area of sites (km²)	ESRS
Upstream	55	204,8	E4-5_01; E4-5_02
Downstream	4	16,6	E4-5_01; E4-5_02
Retail & Logistics[34]	188	1,6	E4-5_01; E4-5_02
Total	247	223	E4-5_01; E4-5_02

Upstream activities has the biggest area covered in protected and biodiversity rich areas, and based on our materiality assessment, exploration and production activities are negatively effecting biodiversity due to temporal land-use change. Given the scale of these activities, it is important for the company to carefully consider potential impacts on biodiversity and integrate environmental factors into decision-making processes. In 2024, the following protected areas were affected by the upstream activities of MOL Group:

Hungary	• Hortobágy National Park • Körös-Maros National Park • Őrség National Park • Balaton Uplands National Park • Duna-Dráva National Park • Kiskunság National Park • Bükk National Park

[34] Excluded 108 Retail & Logistics sites (0,9km²) of MOL Polska, which are currently not under the scope of MOL Group's HSE MS due to the integration period.

Croatia	• Regional Park Mura-Drava • Special Reserve Đurđevački Pesci and Crni Jarki • Nature Park Lonjsko Polje • Žutica Forest
Pakistan	• Kohat Darwazai Banda Game Reserve • Kohat Marchungi Game Reserve • Kohat Dhoda Paya Game Reserve

Definitions (MOL Group Reporting Handbook):

- **Site:** Operational sites, including wells, and other gathering stations and establishments that are above the surface; active/open and operated by MOL Group in the reporting period. Standalone pipelines, roads, and third-party areas are excluded.
- **Impact:** The effect an organization has on the economy, the environment, and/or society, indicating its contribution (positive or negative) to sustainable development.
- **Critical/Significant Impact on Biodiversity**: An impact that can adversely affect the integrity of a geographic area or region, either directly or indirectly, by substantially changing its ecological features, structures, and functions across its whole area, and over the long term, so that habitat, its population levels, and the particular species that make the habitat important cannot be sustained.
- **Protected Area:** A geographic area designated, regulated, or managed to achieve specific conservation objectives.

RESOURCE USE AND CIRCULAR ECONOMY

/E5/

In our 2024 double materiality assessment, we identified the following impacts, risks, and opportunities related to resource use and circular economy:

- Providing waste management & circular economy services (IM-07)
- Waste generation (IM-08)
- Risks due to waste handling & recycling capacity bottlenecks (RK-06)
- Risks of shortage of services, feedstock, products to be obtained from market (RK-08)
- Waste management services (OP-02)
- Sustainable chemicals (OP-03)
- Waste-based fuel usage and production (OP-08)
- Sustainable aviation fuel (OP-10)
- Biogas production (OP-11)

As a result, we concluded the topic Resource use and circular economy to be material from both impact and financial perspective. Description of the methodology and consultations conducted are described in section ESRS 2 IRO-1 of this report, whilst additional information is available in topical IRO-1 section in the beginning of each sub-chapter.

The aim of this chapter is to describe how MOL Group manages the listed IROs, focusing on material usage across various value chains, waste generation and treatment, and the adoption of circular economy practices. Resource use influences broader environmental issues like climate change, pollution, water resources, and biodiversity. Management of IROs related to these issues are addressed in previous chapters of this report.

MOL Group is involved in various different value chains (see ESRS 2 SBM-1 for details) which use different resources and need different approaches to manage IROs. Therefore, this chapter is divided into three sub-chapters which cover distinct aspects of managing the resource flows in MOL Group and its value chains:

- **Sub-chapter A** addresses own waste generation and treatment within MOL Group. It covers waste from all business segments, emphasizing the environmental, health, and safety aspects of waste management.
- **Sub-chapter B** highlights managing the risks and opportunities of MOL Group's downstream activities (including oil refining, petrochemical production, and gas transportation), which have both the highest exposure to resource-use risks and the greatest potential for circularity opportunities.
- **Sub-chapter C** focuses on managing the impacts, risks, and opportunities within MOL Group's circular economy services segment, which operates under the state waste management concession in Hungary.

Each sub-chapter starts by providing a detailed description of IROs relevant for the topic, then details of the policies, action, targets and metrics on outlining how these IROs are managed by MOL Group.

SUB-CHAPTER A: MANAGEMENT OF IMPACTS AND RISKS RELATED TO OWN WASTE GENERATION AND TREATMENT

IDENTIFIED IMPACTS AND RISKS RELATED TO OWN WASTE GENERATION AND TREATMENT

/E5. IRO-1; E5. SBM-3/

ESRS	Disclosure Requirements related to E5.IRO-1, SBM-3
GRI	GRI 3, 3-3;
IFRS	IFRS S1 B1

MOL Group's 2024 double materiality assessment included assessing impacts, risks and opportunities related to own waste – following a similar methodology as in other environment related issues. Please refer to *Chapter E2.IRO-1: Impacts and risks related to pollution* for detailed information. **Identified impacts and risks are outlined in Table IM-08 and Table RK-06 below:**

Table IM-08: Waste generation

Severity	Potential negative impact
Scope	Local
Likelihood	Medium
Description	Via its own operations, activities of its sub-contractors and suppliers and through the disposal of its sold products MOL Group directly and indirectly contributes to the generation of waste, including hazardous materials & chemical substances. Waste can adversely affect the environment nearby disposal / landfilling sites. Besides putting great emphasis on the safe and environmentally friendly disposal of waste at all of its sites and increasing recycling rates, MOL Group is dedicated to contributing to EU's target of reducing the landfilling of waste below 10% by 2035 as a concession commitment through its subsidiary, MOHU Ltd. in Hungary.
Mitigation actions & irremediability	MOL Group follows strict safety protocols and handling procedures, emphasizes education, conducts maintenance actions, performs regular controls, and takes remediation actions where necessary to ensure environmental recovery.
Time horizons	We consider the issue material on all time horizons, and dedicated to the transition towards a cirular economy.
Relevance in the value chain	Waste generation in material in all of MOL Group's business activities and value chains, therefore the issue has a Group-level overview.

Table RK-06: Risks due to waste handling & recycling capacity bottlenecks

Type	Operational risk
Likelihood	Medium
Magnitude of financial effect	High
Description	Significant amount of waste is produced during O&G activities, which poses the liability for safe disposal on the company. MOL Group has well-developed polices to ensure the safe disposal of waste, however, increasingly stringent regulation and EU-level recycling and landfilling targets requires significant investments from the company.
Related impact & dependencies	Associated impact related to the generation of waste – mainly during heavy industrial activities (IM-08) and in the form of waste management services in Hungary under the circular economy services segment (IM-07).
Mitigation actions	Mitigation of risks related to negative impacts on people and the environment include safety protocols and handling procedures, education, maintenance actions, regular controls and remediation actions where necessary – see DR E2-1, DR E2-2, E5-1 and DR E5-2.
Financial effect & time horizons	Financial effect stem from both the handling of waste generated by MOL Group and waste handled by CES. The estimation on the magnitude of financial effect includes the associated CAPEX to ensure regulatory compliance and reduce environmental impact; and OPEX to ensure safe waste disposal (see DR E5-2 and DR E5-6), It excludes revenues associated with providing waste management services – see OP-02 for relevant information. Since circular economy is a key part of Mol Group's business strategy, the topic is considered crucial from financial materiality perspective on all time horizons.
Relevance in the value chain	The risk is material for all oil & gas value chains and waste management activities.

Further impacts, risks and opportunities related to resource use and circular economy are outlines in Chapter E5-B (related to oil & gas-related activities) and in Chapter E5-C (related to waste management related activities).

POLICIES RELATED TO WASTE GENERATION AND TREATMENT

/E5-1/

ESRS	Disclosure Requirement E5-1
GRI	GRI 3, 3-3 GRI 2, 2-23 & 2-24
IFRS	IFRS S2.22 (b) (ii)

This section outlines the MOL Group's policies for handling waste generated during own activities (policies, actions and other disclosures on the waste management services provided by MOL Group are described in Chapter E5-C of this report). General policy commitments

related to HSE are outlined in the ***Group HSE and Social Impact Policy*** and ***Health Safety and Environment Area Book*** (please refer to Chapter: E1 of this report for more information).

Waste handling is a key element in MOL Group's environmental stewardship commitments, with the purpose to reduce the negative environmental impact and mitigating risk associated with generated waste. Relevant process-based regulations are outlined in the **Environmental Stewardship element of the *HSE MS***:

- Waste minimization strategies are followed in line with the 5R principles (refuse, reduce, reuse, repurpose and finally, recycle) to lessen the amount of waste that will end up in landfill and to optimise recycling programs.
- When selecting waste treatment technology, its environmental performance is considered based on the waste pyramid.
- Waste collection is conducted without environmental pollution, and selectively, EU-level guidelines (Commission Decision 2000/532/EC).
- Project planning includes the establishment of a waste minimization plan and waste storage facilities, waste collection and treatment solutions.
- Efforts are made to minimize environmental disturbances at existing landfills.
- Waste transportation protocols are in place based on legal requirements.
- It is ensured that waste is not diluted.
- Priority is given use existing own facilities or establishing facilities based on a thorough cost-benefit analysis and business case for transport and treatment of the waste.

ACTIONS RELATED TO WASTE GENERATION AND TREATMENT

/E5-2/

MOL Group regularly carries out extensive waste management measures, including the excavation, loading, transportation, and treatment of hazardous and non-hazardous waste. These efforts were supported by related studies, documentation, and laboratory analyses, including re-qualification of waste to ensure compliance and proper handling. Operational fees for waste yards, managed by external operators, were incurred to facilitate efficient waste processing and disposal. In total, cost of these general operative actions in 2024 were USD 15.5 million, 10.2% more compared to USD 14.1 million in 2023.

Besides the above listed regular operative measures, MOL Group regularly implementing projects to ensure safe handling of waste and compliance with Best Available Technology (BAT) requirements. Prominent examples are ongoing investments in advanced waste incineration facilities and increasing recycling capacities. Please find information on relevant actions in Section E2 – Pollution, and Sub-chapter E5-B.

TARGETS RELATED TO WASTE GENERATION AND TREATMENT

/E5-3/

ESRS	Disclosure Requirement E5-3
GRI	GRI 3, 3-3

MOL Group is committed to achieve EU-level targets related to waste handling – see more details in Chapter E5-C on MOL Group's waste management services. Regarding handling of own waste, MOL Group's approach is ensuring following all BAT requirements, and do not plan to implement other public targets related to handling own waste in the near future.

METRICS RELATED TO WASTE GENERATION AND TREATMENT

/E5-3/

ESRS	Disclosure Requirement E5-3
GRI	GRI 306-2 GRI 306-3 GRI 306-4 GRI 306-5

The total waste generated on MOL Group-level increased by 0,6%, primarily due to higher waste generation from well drilling and maintenance activities. Overall, 65% of the total waste generated was diverted from disposal through recovery operations. Hazardous waste diverted from disposal through recovery operations increased significantly by 22.1%, reaching 33.4 thousand tonnes in 2024. Non-hazardous waste diverted from disposal saw an even more substantial rise of 44.4%, increasing from 56.1 thousand tonnes in 2023 to 81.0 thousand tonnes in 2024. Conversely, hazardous waste directed to disposal decreased by 28.7%, from 60.1 thousand tonnes to 42.8 thousand tonnes. Non-hazardous waste directed to disposal also declined by 23.0%, totalling 35.7 thousand tonnes in 2024 compared to 46.4 thousand tonnes in 2023. Waste streams are listed in the below tables based on their EWC (European Waste Codes) classification.

WASTE	UNIT OF MEASURE	2024	2023	ESRS
Total waste generated	tonnes	176 779	**175 744**	E5-5_07
Non-recycled waste	tonnes	78 511	**106 452**	E5-5_10
Percentage of non-recycled waste	%	44	**61**	E5-5_10
Total hazardous waste	tonnes	76 258	**87 468**	E5-5_15
Total waste diverted from disposal by recovery operation	tonnes	114 458	**83 487**	E5-5_08
Hazardous waste	tonnes	33 446	**27 394**	E5-5_08
Preparation for reuse	tonnes	9 201	1 790	E5-5_08
Recycling	tonnes	22 471	24 704	E5-5_08
Other recovery options	tonnes	1 775	900	E5-5_08
Non-hazardous waste	tonnes	81 012	**56 093**	E5-5_08
Preparation for reuse	tonnes	17 181	9 356	E5-5_08
Recycling	tonnes	59 411	43 135	E5-5_08
Other recovery options	tonnes	4 419	3 602	E5-5_08

WASTE	UNIT OF MEASURE	2024	2023	ESRS
Total waste directed to disposal by disposal operation	tonnes	78 511	**106 452**	E5-5_09
Hazardous waste	tonnes	42 812	**60 074**	E5-5_09
Incineration (with energy recovery)	tonnes	7 070	14 460	E5-5_09
Incineration (without energy recovery)	tonnes	3 921	20 088	E5-5_09
Landfilling	tonnes	2 696	2 566	E5-5_09
Other disposal operations	tonnes	29 124	22 960	E5-5_09
Non-hazardous waste	tonnes	35 700	**46 378**	E5-5_09
Incineration (with energy recovery)	tonnes	3 497	4 620	E5-5_09
Incineration (without energy recovery)	tonnes	30	28	E5-5_09
Landfilling	tonnes	23 095	33 199	E5-5_09
Other disposal operations	tonnes	9 078	8 531	E5-5_09

WASTE BY COMPOSITION	UNIT OF MEASURE	2024	2023	ESRS
Wastes resulting from exploration, mining, quarrying, and physical and chemical treatment of minerals (EWC 01)	tonnes	16 698	21 080	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	9 649	16 105	
Waste directed to disposal	tonnes	11 120	3 527	
Wastes from agriculture, horticulture, aquaculture, forestry, hunting and fishing, food preparation and processing (EWC 02)	tonnes	67	28	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	20	0	
Waste directed to disposal	tonnes	47	28	
Wastes from wood processing and the production of panels and furniture, pulp, paper and cardboard (EWC 03)	tonnes	0	0	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	0	0	
Waste directed to disposal	tonnes	0	0	
Wastes from petroleum refining, natural gas purification and pyrolytic treatment of coal (EWC 05)	tonnes	8 434	16 505	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	1 232	4 255	
Waste directed to disposal	tonnes	7 469	12 098	
Wastes from inorganic chemical processes (EWC 06)	tonnes	207	29	E5-5_12

WASTE BY COMPOSITION	UNIT OF MEASURE	2024	2023	ESRS
Waste diverted from disposal / waste prevented	tonnes	125	10	
Waste directed to disposal	tonnes	82	19	
Wastes from organic chemical processes (EWC 07)	tonnes	552	5 425	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	0	4 926	
Waste directed to disposal	tonnes	549	492	
Wastes from the manufacture, formulation, supply and use (mfsu) of coatings (paints, varnishes and vitreous enamels), adhesives, sealants and printing inks (EWC 08)	tonnes	68	15	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	2	21	
Waste directed to disposal	tonnes	66	50	
Wastes from the photographic industry (EWC 09)	tonnes	1	1	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	0	0	
Waste directed to disposal	tonnes	1	1	
Wastes from thermal processes (EWC 10)	tonnes	201	295	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	1	4	
Waste directed to disposal	tonnes	200	293	
Wastes from chemical surface treatment and coating of metals and other materials; non-ferrous hydrometallurgy (EWC 11)	tonnes	21	59	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	0	0	
Waste directed to disposal	tonnes	21	59	
Wastes from shaping and physical and mechanical surface treatment of metals and plastics (EWC 12)	tonnes	315	149	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	156	76	
Waste directed to disposal	tonnes	159	73	
Oil wastes and wastes of liquid fuels (except edible oils, and those in chapters 05, 12 and 19) (EWC 13)	tonnes	18 110	19 292	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	7 847	6 059	
Waste directed to disposal	tonnes	10 195	28 492	
Waste organic solvents, refrigerants and propellants (except 07 and 08) (EWC 14)	tonnes	154	137	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	6	4	
Waste directed to disposal	tonnes	148	133	
Waste packaging, absorbents, wiping cloths, filter materials and protective clothing not otherwise specified (EWC 15)	tonnes	4 439	3 251	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	3 112	2 452	
Waste directed to disposal	tonnes	1 334	1 342	
Wastes not otherwise specified in the list (EWC 16)	tonnes	9 197	11 101	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	15 577	8 257	
Waste directed to disposal	tonnes	4 186	2 830	
Construction and demolition wastes (including excavated soil from contaminated sites) (EWC 17)	tonnes	74 847	44 335	E5-5_12

WASTE BY COMPOSITION	UNIT OF MEASURE	2024	2023	ESRS
Waste diverted from disposal / waste prevented	tonnes	65 299	31 344	
Waste directed to disposal	tonnes	10 884	10 974	
Wastes from human or animal health care and/or related research (except kitchen and restaurant wastes not arising from immediate health care) (EWC 18)	tonnes	0	0	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	0	0	
Waste directed to disposal	tonnes	0	0	
Wastes from waste management facilities, off-site waste water treatment plants and the preparation of water intended for human consumption and water for industrial use (EWC 19)	tonnes	9 106	12 484	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	3 037	1 921	
Waste directed to disposal	tonnes	6 061	12 162	
Municipal wastes (household waste and similar commercial, industrial and institutional wastes) including separately collected fractions (EWC 20)	tonnes	34 363	41 558	E5-5_12
Waste diverted from disposal / waste prevented	tonnes	8 463	8 051	
Waste directed to disposal	tonnes	25 921	33 878	

Categories for Waste Management Reporting:

- Waste generation
- Waste diverted from disposal
- Waste disposal
- Recollected waste
- Cross border hazardous waste exported and/or imported

Methods of Measurement and Estimation:

- **Direct Measurement On-Site**: Measuring the mass of waste directly on-site using a calibrated weighing device.
- **Contractor Measurement**: Direct measurement by a waste management contractor.
- **Periodic Measurement**: Periodically measuring the mass of waste to facilitate estimations based on volume. This process covers a wide range of waste types over a representative period. Since waste mass can vary significantly, estimation factors are regularly verified, and records are kept to maintain accuracy and traceability.
- **Estimation When Exact Data is Unavailable**: If exact weight data isn't available, estimating the weight using available information on waste density and volume collected, mass balances, or similar information. The current waste density is determined and recorded regularly (e.g., monthly or quarterly). Measurement intervals are adjusted based on expected variations in waste density to balance accuracy and efficiency. If high density variations (over 10%) are noticed, measurement intervals are shortened. Conversely, if measurements are very similar, intervals are increased. Additionally, density measurement is reassessed each time there is a suspicion that the waste composition has changed or if there are visible indications of such change. This continuous process helps improve the overall accuracy of volume/weight measurement.

Classification of Reported Quantities:

- Hazardous Waste
- Non-Hazardous Waste

General Reporting Principles:

- Report all quantities as the gross weight of the waste in metric tonnes. Convert volume to metric tonnes if only volume data is available.
- Include all waste generated by MOL Group operations, whether recovered or disposed of by MOL Group or third parties (including office waste where possible).
- Use waste registries for local authority reporting as the primary data source.
- Additional data sources include external waste audits, waste balance sheets from disposal service providers, internal billing, accounting systems, and the procurement department.
- Report waste generated by contractors on MOL Group premises unless other contractual arrangements exist.

- Report waste as it is generated by MOL Group entities and handed over to contractors. For example, if hazardous waste is generated on MOL premises but later transformed into non-hazardous waste by a contractor, report it as hazardous.
- Report quantities of pre-treated waste after pre-treatment.
- Do not report wastewater discharged to water treatment plants as waste; follow the Recommended Practice Water Reporting. Do not report aqueous waste/wastewater stored in tanks prior to treatment as waste.
- Split reported quantities based on categories defined in section 2.2 (hazardous and non-hazardous, arising from operations, special measures, regular remediation activities, construction/demolition, recollection, and waste from E&P drilling, well completion, and workover activities).
- Exclude remediation drilling and associated waste from hazardous waste arising from drilling activities, well completion, and workover activities.
- To provide information about the composition of waste, use the European Waste Catalogue as the basis for the reporting structure. All waste-related data is reported under the main group codes of the catalogue.

SUB-CHAPTER B: CIRCULAR ECONOMY & RESOURCE USE IN THE DOWNSTREAM SEGMENT

IDENTIFIED RISKS AND OPPORTUNITIES RELATED TO CIRCULAR ECONOMY & RESOURCE USE IN THE DOWNSTREAM SEGMENT

/E5. IRO-1/

MOL Group's Downstream operations, including oil refining and petrochemical production, present substantial resource-use risks along with significant opportunities for circular economy initiatives. During our 2024 double materiality assessment, we identified 1 risk and 4 opportunity related to the resource use in our Downstream segment, making the topic *E5: Circular Economy & Resource use* financially material. Description of the methodology and consultations conducted are described in section ESRS 2 IRO-1 of this report.

This section outlines MOL Group's approach on managing these risks and opportunities listed below, emphasizing how MOL Group can leverage circular economy strategies to address resource-related risks while maximizing potential for sustainable growth.

Table RK-08: Risks of shortage of services, feedstock, products to be obtained from market

Type	Operational risk
Likelihood	Low
Magnitude of financial effect	High
Description	Albeit MOL Group operates in an integrated model, where all major elements of the oil & gas value chain are within its operating boundaries (from oil exploration to retails sales); the company is dependent on a large supply chain, from many different industries and geographies to obtain its input materials (raw materials for feedstock, input products) and a wide range of services for its operations. Major disturbances in the value chain due changes in the macro environment, emerging regulations, social problems, armed conflicts or other external factors can have significant potential impact on its business.
Related impact & dependencies	Since MOL Group is a major company and fuel supplier in the CEE region, it has a significant impact to on the regional supply chains - see IM-09 and IM-15.
Mitigation actions	MOL Group has an elaborated the crude diversification strategy; alternative crude slate was defined, relevant capex projects defined and started. Supply chain risks are mitigated by stock, supply chain and supplier management actions.
Financial effect & time horizons	Due to the significant spending on inputs materials & services (7,360,586 million HUF on Raw materials and consumable goods) in 2024, we consider this risk financially material on all time horizons.
Relevance in the value chain	Risks of shortage of services, feedstock, products to be obtained from market is a material risk across all levels of MOL Group's value chain.

Table OP-03: Sustainable chemicals

Maturity at MOL Group	Pilot
Magnitude of financial effect	High
Description	A key element if MOL Group's business strategy is the diversification from fossil fuels and skewing downstream production towards petrochemicals. Chemicals have a lower product carbon footprint and can be made from recycled materials or be recycled themselves.
Related impact, risks & dependencies	The opportunity is an important enabler of reducing the dependency of the company's business model on the fossil fuel demand. Furthermore, it helps MOL Group to reduce its GHG emissions on the long term (IM-02) and contributes to a low carbon, circular economy (IM-01, IM-07, IM-19), and mitigate and associated risks (RK-01, RK-02, RK-05, RK-06).

Financial effect & time horizons	MOL Group has key investment on track related to petrochemicals, including a Polyol and metathesis facility at Tiszaújváros and an increased polypropylene production at the Bratislava refinery. Focus of further development will shift from large-scale projects to medium size investments until 2030. The cost of current and planned investments and associated EBIDTA makes the topic material to a „high" degree on all time horizons.
Relevance in the value chain	Sustainable chemicals are a material opportunity in the Petrochemicals and Circular Economy Services segment of MOL Group.

Table OP-08: Waste-based fuel usage and production

Maturity at MOL Group	Assessed/planned
Magnitude of financial effect	Medium
Description	Utilizing waste as a feedstock for fuel production can help reduce reliance on conventional resources and lower carbon emissions. MOL Group is already involved in the production, co-processing and/or sales of several types of biofuel and has further plans for co-production of diesel with waste materials, UCOME production and recycled carbon fuels.
Related impact, risks & dependencies	By pursuing this opportunity, MOL Group reduces its impact of climate change (IM-02) and contributes to a low carbon, circular economy (IM-01, IM-07, IM-19), and reduces its dependency on raw materials (mainly crude oil) and associated risks (RK-01, RK-02, RK-05, RK-06).
Financial effect & time horizons	Related investments and EBIDTA makes the financial effect of this opportunity „medium". It is considered financially material in all time horizons, but mainly on the long term due to its increasing significance.
Relevance in the value chain	Waste-based fuel usage and production is a material opportunity in the Refining, NSB and Circular Economy Services segment of MOL Group.

Table OP-10: Sustainable aviation fuel

Maturity at MOL Group	Assessed/planned, pilot
Magnitude of financial effect	High
Description	Developing and marketing sustainable aviation fuels (SAF) derived from renewable sources can help reduce the carbon footprint of the aviation industry, where oil and gas companies can play a significant role in the transition to greener alternatives.
Related impact, risks & dependencies	By pursuing this opportunity, MOL Group reduces its impact of climate change (IM-02) and contributes to a low carbon, circular economy (IM-01, IM-07, IM-19), and reduces its dependency on raw materials (mainly crude oil) and associated risks, especially renewable fuel related regulatory compliance (RK-01, RK-02, RK-05, RK-06).
Financial effect & time horizons	MOL Group is already actively marketing of SAF products (short term), whilst own production projects are considered on the medium term. Therefore, the opportunity is considered material on all time horizons.
Relevance in the value chain	Sustainable aviation fuel is a material opportunity in the Refining and NSB segment of MOL Group.

Table OP-11: Biogas production

Maturity at MOL Group	Assessed/planned, Implemented at scale
Magnitude of financial effect	Medium
Description	Biogas – and its most advanced form, biomethane, as a greener alternative to natural gas - is steadily gaining ground as an energy source due to its contribution to the energy transition and decarbonization. MOL Group has a biogas facility[2] at Szarvas, and is also planning to invest in biomethane[1] production capacities as part of its Shape Tomorrow strategy.
Related impact, risks & dependencies	Biomethane is a key enabler to reduce CO2 emissions and regulatory compliance regarding renewable energy use (RED III). Therefore, it contributes to a low carbon, circular economy (IM-01, IM-07, IM-19), and reduces its dependency on raw materials (mainly crude oil) and associated risks (RK-01, RK-02, RK-05, RK-06).
Financial effect & time horizons	Due to the planned ramp-up of waste-based gas production, the opportunity is considered financially material on the medium-term.
Relevance in the value chain	Biogas production is a material opportunity in the NSB part of MOL Group's value chain.

POLICIES RELATED TO RESOURCE USE

/E5-1/

Our commitment to sustainable resource use guides our approach to managing risks and leveraging opportunities within our Downstream segment. The policies described in this chapter are designed to address key risks, including the potential impact of disruptions (such as regulatory changes, social challenges, or geopolitical factors) within our diverse supply chain, spanning multiple industries and geographies.

In response, MOL Group's ***Shape Tomorrow Strategy*** is centered on becoming a sustainable company providing materials for the economy and energy for mobility. Alongside reducing the carbon footprint of our product portfolio, we will enhance the sustainability of industrial activities, and integrate circular economy technologies into the core business by transitioning away from virgin resources. Key enablers of this transition are increased the use of secondary (recycled) materials and waste-based feedstocks in our production processes and prioritising sustainable sourcing practices to ensure responsible use of renewable resources. Through investments in petrochemicals, biofuels, and biomethane, we aim to contribute to lower-carbon, resource-efficient solutions and support the broader energy transition.

These principles are integrated into MOL Group's process-based policies, captured by three key area books:

- The ***Downstream Development Area Book***, managed by the Group Downstream Production and Development Senior Vice President, defines the strategy and roadmap for the Downstream business and ensures its implementation through efficient processes. It supports large and strategic projects by providing conceptual solutions, centralizing resources, and building team competencies focused on fossil fuel reduction, petrochemical growth, alternative energy solutions, and CO_2 footprint reduction. Development projects are evaluated using long-term economic modelling and technical feasibility assessments, forming the basis for early decision-making. This approach integrates new projects into existing assets to optimize business benefits and ensure sustainability. The centralized, integrated team ensures efficient resource allocation for maximum impact.
- The ***Optimisation, Sales and New Businesses Area Book*** emphasises, that besides the maximization of profitability on existing markets, disciplined cost control and enhancing digitalization and -driven and efficiency focused mindset, the introduction of new services and products is also a key priority. It outlines the main processes of key business fields supervised by the Group DS Executive Vice President:
    - **Group Value Chain Management (VCM)** with the main objective to manage the long-term planning and strategy about how we use and develop existing assets within Downstream.
    - **Group Fuels** and **Group Chemicals** with the main objective to manage the existing Downstream businesses and ensure the success of transformation under increased volatility of markets.
    - **Group New and Sustainable Businesses** (hereinafter: NSB) with the main objective to ramp-up to progress in developing sustainable solutions and new businesses and to create a new way of managing these initiatives.
- Lastly, the ***Downstream Production Area Book*** establishes the Group-level framework for MOL Group's hydrocarbon refining and petrochemical production sites, which are key assets of the company. Its primary objective is to create value for customers by transforming raw materials into high-quality, marketable products through safe, sustainable, and efficient operations. Implementation is supervised by the Group Downstream Production Senior Vice President.

MOL Group's internal policies ensure a responsive risk management system enabling the company to react to supply chain risks, such as shortage of services, feedstock, products to be obtained from market (RK-08). Through the ERM process, supply chain disruptions were identified as operational risks. Maintaining crude supply security and flexibility is a key pillar of the strategy and integrated into the ***Optimisation, Sales and New Businesses Area Book's*** processes.

Besides managing the risks associated with the supply chains of its legacy business, embracing EU's 2025 long term strategic objectives and national policies pushing towards a green energy transition is a must. Therefore a cornerstone of the ***Shape Tomorrow Strategy*** is to play a key role in shaping the low-carbon circular economy with investments in new businesses and actively pursuing opportunities to diversify towards alternative energy sources:

- **Sustainable chemicals:** MOL Group's commitment to transitioning from fuels to sustainable chemicals is embedded in our ***Shape Tomorrow Strategy*** and operationalized through the ***Downstream Production Area Book*** and the ***Optimisation, Sales and New Businesses Area Book***. **Sustainable chemicals:** MOL Group's commitment to transitioning from fuels to sustainable chemicals (OP-03) is embedded in our ***Shape Tomorrow Strategy*** and operationalized through the ***Downstream Production Area Book*** and the ***Optimisation, Sales and New Businesses Area Book***. Guided by a shift toward medium-sized investments, we are prioritizing downstream production to diversify away from fossil fuels while delivering key projects like Polyol and expanding the value chain with mid-scale investments in circular chemicals. This includes processing mixed waste plastics into petrochemical feedstocks, integrating circular economy solutions into our operations. The Product and Asset Portfolio Management framework defines our product and asset strategies, focusing on polymer recycling, low-carbon chemical businesses, and emerging value chains to meet regulatory and market demands while enhancing long-term competitiveness.

- **Bio- and waste-based fuels for road transport**: The renewable share obligations of transportation fuel (RED III and FQD[35]) are continuously increasing, accordingly the biocomponent content expectations have also increased across MOL Group's fuel markets, which have so far been met mainly by blending bioethanol and biodiesel, with plans to increase the waste-based fuel production capacities as part of the ***Shape Tomorrow Strategy*** (OP-08). MOL Group has an **ISCC certification** for co-processing of waste materials, ETBE production and trading and storage of biofuels. Processes related to the biofuel compliance strategy of MOL Group are included in the ***Optimisation, Sales and New Businesses Area Book*****:** MOL Group continuously monitors regulations to ensure compliance and inform country-level bio blending and compliance plans. Compliance strategies are shaped by analysing market trends and optimizing a cost-effective bio compliance matrix, supported by the exploration and testing of new bio feedstocks and components, while maintaining seamless refinery and logistical operations through monthly biofuel flow scheduling. Post-evaluation involves reconciling biofuel inventories and sales to prepare compliance reports, with adjustments made to supply plans as needed, alongside providing Proof of Sustainability in alignment with customer and business unit requirements.
- **Sustainable Aviation Fuels:** Supplying SAF is mandatory starting from 2025 as per the ReFuelEU Aviation. Slovnaft and INA are mandated parties as aviation fuel suppliers, and MOL is providing wholesale supply for mandated parties in Hungary, which parties are interested in MOL supplying them with SAF in addition to jet.
- **Biogas:** Utilisation of biogas and biomethane as an energy source (OP-11) is an key element of the ***Shape Tomorrow Strategy*** and integrated into the ***Downstream Development Roadmap 2025*** (as described in the *Downstream Development Area Book*). It also support Mol Group's compliance with the above mentioned EU's Renewable Energy Directive (RED III).
- **Green hydrogen production** (OP-01) is also a prominent case of our sustainability & diversification efforts - see relevant disclosures in Chapter E1.

ACTIONS RELATED TO RESOURCE USE

/E5-2/

This section describes the key step in 2024, and planned actions related to the identified risks and opportunities of the Downstream segment.

Supply chain risk management & crude diversification actions

MOL Group is dedicated to ensuring a stable and sufficient market supply within its core region while adhering to EU sanctions. To address identified risks in the crude oil value chain (RK-07), particularly due to sanctions on Urals crude, MOL Group has accelerated its crude diversification efforts. On top of the regular processes in place for tactical planning to secure customer supply (as described in the *Tactical Planning & Margin Management* element of the ***Optimisation, Sales and New Businesses Area Book*** and in the ***Downstream Tactical Planning and Margin Management Process Description***) a crude diversification program has been launched in 2022. It includes an investment of USD 500 million with the aim to achieve 100% capability to process alternative crude oil by 2026 at the landlocked refineries in Százhalombatta and Bratislava, thereby ensuring regional supply security. Actions include a continuously development of technological capabilities to increase the intake of non-Russian crude. Since 2022, MOL Group has tested over 10 different alternative crude types, with Slovnaft processing close to 1 million tons of alternatives in 2023. Our diversification efforts also aims to mitigate potential disruptions from interruptions in the Eastern crude supply via the Druzhba pipeline or the Adria supply route. To enhance the utilization of the Adriatic pipeline, MOL Group has entered into a partnership with JANAF, the pipeline's owner and operator.

Sustainable chemicals

As part of its commitment to advancing sustainable chemical solutions (OP-03), in May 2024, the Polyol complex, MOL Group's largest organic investment has been inaugurated, further strengthening the company's downstream capabilities. The chemical recycling facility at MOL Petrochemicals Co. Ltd. in Tiszaújváros, Hungary, planned to process 40,000 tons of mixed waste plastics annually, will reduce reliance on fossil raw materials for plastic production and aligns with the company's goals of increasing circularity and mitigating environmental impact. MOL Group has partnered with Lummus Technology to advance sustainable chemical solutions, focusing on the chemical recycling of plastics. This collaboration involves establishing a facility that utilises Lummus' Green Circle pyrolysis technology to transform plastic waste into high-value petrochemical feedstocks, promoting circularity. The plant will also feature advanced greenhouse gas (GHG)

[35] The Commission adopted in June 2023 new rules establishing the share of biofuels and biogas in mixed fuels, co-processed using bio-based and fossil-based raw materials, and that can count towards the Renewable Energy Directive target for renewables in transport. The Delegated Regulation (EU/2023/1640) was published in the Official Journal of the EU on 18 August 2023 and has been subject to public feedback, several consultations and scrutiny from the European Parliament and the Council. The revised Renewable Energy Directive establishes binding targets for the share of renewable energy in the transport sector, including maritime and aviation. By 2030, EU countries are required to either achieve a share of 29% of renewable energy in transport, or to reduce the emissions intensity of transport fuels by 14.5%, as well as a combined sub-target for renewable hydrogen and advanced biofuels of 5.5%.

reduction design elements, including a fully electric pyrolysis reactor which will result in zero direct scope 1 emissions from the unit during normal operation. Integrating these new processes with MOL's existing facilities optimizes the value chain and enhances sustainability. The design phase of the chemical recycling plant commenced in 2024, with subsequent project phases yet to be announced. This project exemplifies the application of circular business practices, transforming waste plastics into feedstocks that are reintegrated into production and reducing reliance on virgin materials. Innovative technologies, such as electric pyrolysis reactors, lower emissions and further MOL Group's commitment to sustainability and the circular economy. Supporting these efforts, MOHU's initiative to collect and treat up to 5 million tonnes of municipal solid waste provides critical feedstock for the pyrolysis unit. By addressing the recycling gap for typically non-recyclable plastics, the project closes the loop in material usage. The recycled feedstocks are reintegrated into production lines, while the zero-emission reactor technology enhances environmental sustainability, aligning with MOL Group's strategic focus on circularity and sustainable growth.

Bio- and waste-based fuels for road transport

In line with EU's biofuel mandate (as explained in the Policy section of this chapter) MOL Group has blended over >600 kilotons of biofuels into its fuel products sold in 8 countries in 2024, saving approximately 2 200 000 tons CO2 emissions. Blended biofuels include food- & waste based bioethanol and fatty acid methyl esters obtained from the market and via joint-venture operations (Meroco, Rossi Biofuels). Furthermore, since March 2020, after several years of research and development, MOL Group has stepped up the value chain and has become a biofuel producer, through the realisation of an investment in the Danube Refinery. At its facility in Százhalombatta, over 15 kilotons of renewable feedstocks (for example vegetable oil) were co-processed together with fossil materials in 2024, increasing the renewable share of diesel, reducing up to 55 000 tons /year CO2 emission. A key advantage of this innovative method is that the resultant biodiesel can be still blended with a maximum 7 percent of fatty acid methyl esters in line with diesel standards, allowing the overall bio-share of the fuel to be higher without negatively affecting fuel quality.

Sustainable Aviation Fuel

MOL Group is also advancing sustainable aviation fuel (SAF) initiatives to support the aviation industry's transition to greener alternatives and align with its low-carbon, circular economy goals (OP-10). MOL Group has conducted a tender to purchase sustainable blending components (SBC), to be used for SAF-containing jet A-1 fuel. These purchases support SAF distribution either wholesale or directly into planes across Slovakia, Hungary, and Croatia, sourced from major European providers. This initiative addresses imminent regulatory changes, as relevant legislation take effect on January 1, 2025. The tender process is expected to occur annually, with its structure adapting to market developments. Spot purchases are also anticipated throughout 2025 to ensure total demand is met. The required SBC must achieve a minimum of 80% carbon emission savings, showcasing the environmental benefits of this initiative. MOL Group's current operating expenditure (OPEX) for these activities is estimated at EUR 75 thousand, reflecting costs specifically associated with infrastructure development for SAF, demonstrating that MOL is not only engaged in trading but is also actively investing in system development. These measures highlight MOL Group's commitment to reducing emissions and delivering higher value for consumers in the aviation sector. These developments gave the Group the ability to load road tank cars with SAF at a logistic depot that also has rail loading and unloading capabilities, which ability uniquely connects on rail the CEE consumers supplied on road with SAF distribution centers.

Biogas and biomethane

MOL Group is advancing its position in the biogas value chain with the ambition to become a regional leader by 2030. (OP-11). Biogas production contributes to CO2 reduction, waste-to-energy conversion, and economic benefits like job creation in the feedstock supply chain. The biogas and biomethane initiative exemplifies circular business practices by converting bio-waste into renewable energy and minimising methane emissions. The waste-to-energy model integrates sustainability by reusing resources, enhancing efficiency, and leveraging byproducts like digestate in agriculture. Stakeholder collaborations with local waste management, agriculture industries, and gas distributors ensure broad benefits while fostering a circular economy.

The Group has prepared a biogas roadmap and initiated strategic steps, including the acquisition of its first biogas plant near Szarvas, Hungary in 2023. This facility processed over 100,000 tons of residual waste from regional food producers, farmers, and livestock producers, yielding more than 12.5 million cubic meters of biogas in 2024.

Additionally, INA Group plans to establish a biogas and biomethane plant in Sisak, Croatia, using agricultural waste to expand the company's renewable energy portfolio, delivering advanced, sustainable fuel for the transportation sector. The project will have an annual production capacity of 3 kilotons (approximately 4.2 million cubic meters of biomethane) by processing 75 kilotons of bio-waste feedstocks each year. The biomethane will be injected into the local gas grid. Progress milestones include plans for mechanical completion by Q2 2026. Financial resources for the project are allocated to CAPEX investments of EUR 45 million with projected annual operational expenses of EUR 2.5 million covering feedstock, utilities, workforce, and maintenance. The project will contribute 0.4% (double-counted) of INA's total fuel pool, replacing fossil fuels with biomethane and supporting regulatory compliance and reaching the EU's renewable energy targets.

METRICS RELATED TO RESOURCE IN- AND OUTFLOWS OF THE DOWNSTREAM BUSINESS SEGMENT

/E5-4; E5-5/

The tables below present the main inputs and outputs of MOL Group's Downstream segment in 2024. Background information can be obtained from section Strategy & Business model of this report.

Main resource inflows /E5-4/:

Input materials	Refinery processing (kt)
Own produced crude oil	858
Imported crude oil	12 448

Main resource outflows /E5-5/:

Refining:	Refinery production (kt)	External sales (kt)
LPG	391	348
Naphta	1 423	38
Motor gasoline	3 154	3 802
Diesel and heating oil	6 702	11 505
Kerosene	537	713
Fuel oil	279	237
Bitumen	571	569 (+ 0.7 rubber bitumen)
MOL Group internal transfer for petrochemical feedstock	1 821	-
Petrochemicals	**Petchem production by product type (kt)**	**Petchem sales by product group (kt)**
Olefin products	1 530	178
Polymer products	864	848
Butadiene products	74	76
Raffinate	114	0

SUB-CHAPTER C: MANAGEMENT OF IMPACTS, RISKS AND OPPORTUNITIES RELATED TO CIRCULAR ECONOMY SERVICES

IDENTIFIED IMPACTS, RISKS AND OPPORTUNITIES RELATED TO CIRCULAR ECONOMY SERVICES

/E5. SBM-3/

This section outlines the impacts, risks and opportunities associated with the Circular Economy Services (CES) segment of MOL Group:

Table IM-07: Providing waste management & circular economy services

Severity	Significant, actual positive impact
Scope	Country level (Hungary)
Likelihood	Actual
Description	As part of its strategy, MOL Group diversifies its portfolio towards waste management & circular economy services, to convert waste streams into valuable products such as chemicals, fuels or plastics, and become a driver of transitioning to a circular economic model. Activities within CES segment include collection and treatment of waste generated; waste recycling; waste energy recovery, and supporting Group entities by providing feedstock, such as biofuel production from waste-based biological materials. As an impact, MOL Group contributes to decreasing pollution from waste disposal & reducing virgin material need, by reaching EU-wide targets set in the matter. This means all CES ventures support to comply with the requirement of landfilling maximum 10% and preparing for reuse or recycling 65% of all solid municipal waste generated in Hungary, by 2035/2040.
Actions	MOL Group's actions focus on ensuring business continuity and making investments in emerging green technologies and efficient business solutions.
Time horizons	We consider the matter material across all time horizons, to an increasing extent.
Relevance in the value chain	Approximately one fifth* of all waste generated in Hungary consists scope of MOHU Zrt.'s concessionary activities – being responsible for the collection and treatment of solid municipal waste via its partners. Other entities of the segment either contribute to these activities, or shall take part in the value chain of secondary raw materials.

* Hungarian Central Statistical Office

Table RK-06: Risks due to waste handling & recycling capacity bottlenecks

Type	Operational risk
Likelihood	Medium
Magnitude of financial effect	High
Description	Significant amount of waste is produced during O&G activities, which poses the liability for safe disposal on the company. MOL Group has well-developed polices to ensure the safe disposal of waste, however, increasingly stringent regulation and EU-level recycling and landfilling targets requires significant investments from the company. Furthermore, by establishing the CES (Circular Economy Services) segment of the Group, the entry into the waste management and circular economy activities means novel risks related to other than only waste producing operational areas. For MOHU Zrt., to manage and organize the national waste handling system with 10+ thousand employees and 1+ thousand sites of subcontractors poses operational and legal risks, as non-compliance in any area can have far-reaching consequences for the firm.
Related impact & dependencies	Associated impact related to the generation of waste – mainly during heavy industrial activities (IM-08) and in the form of waste management services in Hungary under the CES segment (IM-07).
Mitigation actions	Mitigation of risks related to negative impacts on people and the environment include safety protocols and handling procedures, education, maintenance actions, regular controls and remediation actions where necessary – see DR E2-1, DR E2-2, E5-1 and DR E5-2. Actions related to reducing the ratio of waste landfilled and increasing the ratio of waste recycled in Hungary are incorporated into the business principles of the CES segment, and the concession agreement of MOHU Zrt. – see DR E5-3 and OP-2 for more details. The segment's strategy and activities are ultimately directed towards meeting the relevant EU targets set for the nation.
Financial effect & time horizons	Financial effects stem from both the handling of waste generated by MOL Group and waste handled by CES. The estimation on the magnitude of financial effect includes the associated CAPEX to ensure regulatory compliance and reduce environmental impact; and OPEX to ensure safe waste disposal (see DR E5-2 and DR E5-6). It excludes revenues associated with providing waste management services – see OP-02 for relevant information. Since circular economy is a key part of MOL Group's business strategy, the topic is considered crucial from financial materiality perspective on all time horizons.
Relevance in the value chain	Risks related to the handling of waste generated by organization is relevant across all value chains related to MOL Group's industrial activities. However, this sub-chapter is focused on how risks due to waste handling & recycling capacity bottlenecks is managed related to MOL Group's CES segment. For disclosures of own waste, see E5 - sub-chapter A.

Table OP-2: Waste management services

Maturity	Implemented at scale
Likelihood	High
Description	By integrating waste management into its operation, MOL Group can be a driving force for reaching a circular modus operandi. MOHU Zrt., the concession company for waste management in Hungary can push for national recycling targets while providing valuable feedstock for various businesses of the Group or the CES segment, thus facilitating compliance with EU legislation.
Related impacts, risks and dependencies:	The complexity of the waste management concession and all affected parties create a landscape where it becomes challenging to exert a positive impact on the whole system. While there are inherent risks associated with this task (RK-06), by carrying out the strategy of the segment, these risks can be mitigated and consequently, a positive impact can be fostered (IM-07). Thus, a more sustainable national economy can be achieved, as progressively decreasing the dependency on virgin materials and efficiently utilizing waste-to-energy technologies pave the way towards a more circular economy.
Financial effect & time horizons:	This opportunity is already pursued by MOL Group since the kick-off of its activities related to the waste concession in 2023. As part of its commitment to the concession, MOHU Zrt. is to invest USD 0.9 billion in the Hungarian waste management industry to its further development. Additionally, material, strategy-driven investments are to be made into utilizing this feedstock, and into recycling and medium-scale chemical technologies in other Group areas as well. Therefore, it is considered financially material in all time horizons.
Relevance in the value chain	In Hungary, MOL Group, by MOHU Zrt., is solely responsible for all residential waste generated. MOHU can positively influence the industry through the complete value chain that is defined by the concession agreement. It can also provide feedstock for other segments, for CES and Petrochemicals, to replace virgin materials in production processes, or energy generation.

POLICIES RELATED TO CIRCULAR ECONOMY SERVICES

/E5-1/

For the Circular Economy Segment, the main guiding policies in the daily operation are:

- **Circular Economy Services Area Book**,
- **Concession Contract for MOHU Zrt.** (hereinafter: Concession Contract),
- **Integrated Management System of MOHU**.

As of the scope of this report, MOHU Zrt. (hereinafter: MOHU) is the primary entity with active operations, while other subsidiaries under the segment are either companies with joint ownership structure (e.g., MOHU Budapest Zrt., hereafter: MOHU BP), or without any operations currently. Segment-level policies apply to all of them, nonetheless.

The **main guiding policy for the CES segment is the *Circular Economy Services Area Book***, which is the highest-level process-based regulation, focusing on end-to-end processes describing the operation model and rules for operation of the segment, without any geographical limitation, and so is to be implemented at all companies of the division. Currently, due to CES being in early setup and or/immature phase of operations, this policy is only valid for Hungary, and via MOHU companies, it covers the value chain from end-users of products (i.e., waste producers, population and industry) to secondary raw material sales, including collection and treatment, with intent to build out recycling activities.

Affected stakeholders are all value chain partners, all relevant regulatory and industry associations, and other organizations of MOL Group – the policy aims to find collective optimum for all parties, to be beneficial in all bilateral relations. With all other stakeholders, defined goals and mission is appearing in “informal” way – through approach in contractual proceedings.

Due to its generality, it is valid for and includes approaches towards the identified impacts, risks, opportunities. Within CES, accountable level for implementation of policies is Head of CES.

The policy integrates the strategic direction of the Group by addressing all uncertainties and opportunities identified as relevant IROs in the materiality assessment. MOL Group’s strategic target is to expand its petrochemical product portfolio with recycled plastic feedstocks. In this effort, MOHU and CES leverage their influence within their respective value chains to standardize high-quality, homogeneous systems across all operations in Hungary. Furthermore, the firm is also committed to producing as much energy as possible from wastes that cannot be recycled, primarily through incineration.

Value chain definition applied in MOHU’s operation is that waste collection services shall be coordinated exclusively through subcontractors – legislation and official regulations are taken into account, as well as internal and external customers’ satisfaction is always considered, while at the same time, reliable and efficient solutions must be provided. The value chain is further defined or limited to the activities described in the Concession Contract.

With the introduction of the Extended Producers Responsibility (EPR) system in Hungary, and since MOHU operates the aforementioned system, it is important to ensure the proportionate financial burden of the relevant producers through EPR fees. Actions and measures with EPR relevance shall strive for the maximum fulfilment of the targets relevant for the certain EPR product/waste category while keeping costs at a reasonable and proportionate level. In order to meet CES Strategy fitting parallelly to EU and National waste management directives, and KPIs set in the Concession Contract with the Government, CES and within that MOHU shall plan, develop and implement investment projects. In case of all investment projects, all relevant internal stakeholders and contributors shall evaluate the proposed project’s strategic fitting in order to eliminate duplications and contradictions with CES strategy, and so this project management approach shall resonate with identified material IROs.

In order to achieve MOL Group's Circular Economy objectives, the 4 Rs Concept, Reduce-Reuse-Recycle-Recover, is integrated into the everyday approach and operation of the division, and so they should be applied in the businesses' operational processes. CES segment and belonging entities shall monitor the implementation continuously. One of the main declared aims of CES is moving towards higher level Rs by providing valuable secondary feedstock to the whole economy, thus supporting both MOL Group and external buyers transition away from virgin inputs as much as possible. This way, and by applying an objective-oriented secondary raw material trading approach, CES shall contribute to the achievement of national EU recycling targets. Furthermore, the 4 Rs of waste hierarchy are promoted through the value chain: a) for partners, by means of contracting, cooperation and investments, and b) for consumers, mainly via educational and awareness raising campaigns.

Through these principles and way of operation, CES influences partners (e.g., via contractual relations like regional coordinators [subcontractors], or indirectly population via DRS) in value chain towards a more sustainable, circular way of operating.

In terms of internal regulations and policies, there is no need to cover sourcing as MOHU is a service company (i.e., no material processing or manufacturing is taking place). Other CES entities are currently irrelevant from this point of view, since they are either non-operating, or are in the integration/setup phase.

The ***Concession Contract*** that is relevant to the core and largest company of the CES segment, MOHU, sets the framework for operation and limits the scope of activities. It relates to the identified impact and appears in the contract as commitment to EU targets and committed CAPEX spend (185 billion HUF). However, KPIs and targets set in the contract cover a wide array of topics, they all relate to the two main Waste Framework Directive targets of the EU. Nonetheless, not only impact but main risk also comes from the contract – if breach happens, consequences can/might range from monetary penalties to the possibility of the concession to be lost.

Due to the nature of the concession, operation and planning is monitored in a price regulated environment, by the Ministry of Energy and the Hungarian Energy and Public Utility Regulatory Authority, who scrutinize the efficiency and strategic direction of MOHU, which shall be directed towards delivering the KPIs set in the Contract. This includes the detailed investigation of the assets and the costs which takes place before every price regulatory cycles. According to the Concession Contract, a preparation period (28.07.2022 – 01.07.2023), a transition period (01.07.2023 – 31.12.2026), and price regulatory cycles (01.01.2027 - 31.12.2058) are separated. The preparation and transitional periods are based on estimated costs because of the lack of fact data and followed by four-year-long cycles based on factual eligible costs with an annual data request and annually updated fee proposal. Waste Act allows a possibility of fee modulation which involves the representatives of manufacturers and distributors, in a framework of a fee council. Fee modulation leads to a possibility of creating a specific modulated fee of a certain product stream involving ecological, social or product life cycle-based modifications, and aims to find a compromise between all relevant stakeholders, and simultaneously, develop the system towards reaching waste management targets.

A publicly available and stated manifestation of the principles set in the Concession Contract and internal regulations for MOHU is operating an ISO 9001, ISO 140001 certified **Integrated Management System**. The main goal of this policy is to increase use of secondary raw materials – reflection to MOHU impact and opportunity in this field. The aim is to cooperate with partners in a mutually beneficial way, and improve our processes by accepting their feedback. All our policies are updated based on reflections to internal and external changes, especially risks.

ACTIONS AND RESOURCES RELATED TO CIRCULAR ECONOMY SERVICES

/E5-2/

In case of the CES segment of MOL Group, measures taken are mostly, due to ownership structures and actual maturity phases of entities, relevant to and are in connection with MOHU.

MOL has been awarded the public waste management concession in July 2022 in Hungary, the ultimate aim of which was to enable the state to meet the recycling and landfilling targets set by the European Union until 2040 (if derogation is applied). MOL established the concession company, MOHU (MOHU MOL Waste Management Ltd.) to perform the following tasks in line with concession commitments:

- MOHU contracted 6 regional coordinators and 16 regional subcontractors, all 56 pre-treatment partners, and 217 institutional service providers in 2023.
- As the concession came into force in July 2023, the extended producer responsibility (EPR) system was introduced with MOHU as the operating entity.
- Besides crucial operation tasks, MOHU started to create the foundations for several main projects launching in 2024, such as the development of new separate collection of biodegradable household waste or the introduction of the deposit refund system (DRS) – the initiation of both being legal requirements and a consequence of state decisions. These projects aim that the various waste streams are to be collected in a clean and separate way, giving the opportunity to be directly recycled instead of incineration or landfilling.

In the frame of the current waste management operation of Hungarian waste system, there is a transition plan on how to change in the future. In terms of current and future financial resources, the aim is to have an organic investment roadmap for the upcoming five years amounting up to USD 0.9bn, mainly focusing on finishing the roll-out of deposit refund system, investing in the upgrade and development of waste collection and sorting system and infrastructure, as well as construction of a waste to energy plant.

This pipeline of projects, by spending 80% of capital expenditure on low carbon initiatives, supports the realization of all commitments made towards enhancing the Hungarian waste management scene – realize positive impact, mitigate risks, and lay groundwork for capitalizing on opportunities. Geographical scope of these investments and efficiency programs is currently Hungary only, focusing on activities from collection to processing of waste. Efficiency programs, current facility, logistics and other “short lifespan” projects need to take effect in short-term.

Whole waste system development plan, GFRT (“*rolling development system plan*”), is aligned to reach EU targets by 2040, it is a 10-year-long plan that is revised by MOHU and officially approved by bodies of the Hungarian government annually.

Cooperation with two of the main keyholders (Ministry of Energy in Hungary and the Hungarian Energy and Public Utility Regulatory Authority) is open and productive, in order to make it possible to reach strategic goals: shortly before and since July MOHU start, relevant legislative acts and methodologies were published, while on the other hand, a completely new, cost based price regulation has been established and fees for the EPR system have been announced, both in the previous years, 2023, and 2024.

EPR (Extended Producer Responsibility)

EPR system was launched on 1st July 2023. MOHU, in her capacity as the designated operating and coordinating organization, is responsible for the arrangement of collection, pre-treatment and handover for treatment that is necessary for reaching the recycling targets set by the EU, in case of the waste generated in circular product categories. Based on the Polluter Pays Principle, producers cover the related costs by means of the producer fees. Thus, a significant share of MOHU's activities is directed at planning, organizing, contracting, monitoring, and financing these EPR-related functions.

The Partner portal was launched for the registration of industrial/business partners, and IT development projects are under way to provide a more efficient process.

Within terms of the EPR system, MOHU has started an intensive communications and educational campaign to strengthen selective waste collection, and preparatory works have started for the technological development of pre-treatment and separational facilities. These, thanks to the educational efforts, will be able to contribute to a more efficient operation with higher recycling rates of growing volumes of cleaner, more homogeneous, selectively collected waste streams.

DRS (Deposit Refund System)

The system came into full effect on 1 January 2024, however – due to a 6-month transition period – only started real operation in July. With close cooperation with retail partners, more than 3,700 reverse vending machine units (RVMs) have already been procured and installed, available at retail networks, along with 1,500 contracted manual takeback points. Penetration of the system stabilized at 6 million beverage packaging returned per day in the fourth quarter.

Regarding the operation of the system, it is important to highlight, that:

- range of available RVMs is defined so retailers can select based on their needs and expected customer turnover,
- for those stores that cannot install fix RVMs for any reason, manual return is offered, supported by the so called mobile RVM service which collects, identifies and compacts material on the spot, avoiding transporting non-compacted material to counting centers (as it happens in any other DRS),
- stakeholder management and dialogue with industry associations is continuous for optimizing the DRS system,
- MOHU attends relevant industry events and conferences,
- campaigns have been launched for both retail partners and consumers.

Promotion of circularity with cooperation, by reach optimum with producers, retail partners, sorting facilities and finally, buyers of materials supporting the achievement of long-term targets.

Infrastructure and logistics developments

The first own waste yard investment in Esztergom had been completed and started its operation in May 2024 Further 9 are in preparation phase as part of the new concept – cooperation and discussion are ongoing with local municipalities. With wasteyards, goal is to promote selective waste collection among population, and create as many separate clean waste streams/categories as possible, which simplifies the waste treatment and increases recycling process efficiency afterwards.

Pilot phase for biological waste collection has started – based on evaluation of results of the pilot, and discussions with partners, MOHU will develop the system in the medium term. Procurement of additional assets is under preparation. MOHU hosted educational and awareness raising presentations about the bio collection system to support new collection roll-out efficiency.

Development of the textile waste collection infrastructure reached a significant milestone, having already approx. 850 textile containers installed across Hungary. Separate collection of textile waste, and the purchase of collection containers contributes to diverting used clothes not only from disposal to recovery, but towards higher waste hierarchy levels (reuse).

Procurement of new waste collection vehicles is in progress (was launched) in order to decrease the average age of vehicles park. Evaluation criteria are under discussion in order to provide partners with assets that can most effectively contribute to the requirements of a changing waste management landscape in Hungary.

Key approach in our asset investments is always aiming to opt for the most efficient solution. MOHU colleagues are regularly having contact with local communities, and, related to subsegments and waste streams. Flyers, online and offline communication campaigns are continuous towards relevant parties.

All investments are aligned with the Concession Contract committed HUF 185 bn plan. However, MOL intends to dedicate around USD 0.9 bn (HUF ~350-380 bn) capital into the development of the CES segment instead, almost double the original commitment.

Dialogue is continuous with regulator, by sharing data mutually, providing recommendations for regulation changes to make the waste management system more transparent and efficient (in terms of what else shall be regulated to be able to reach main EU targets)

In 2024, CES segment was extended with a joint venture, MOHU Budapest, between MOL and BKM Budapesti Közművek, in a 50-50% ownership structure. To partner up was a step towards implementing the strategy of the segment and moving closer to realizing targets and commitments that the concession entails, these actions being aligned with the identified IROs at the same time. The rationale behind establishing MOHU Holding was similar, inter alia to exert influence on regional and local waste management firms, harmonize and optimize their operations, and begin to transform these operations with the defined targets at the cornerstone.

However, there is a key general takeaway: while the largest CES segment company, MOHU operates in a tightly regulated market and a regulated price environment which define and limit the scope of activities that MOHU can do, other CES segment entities (wholly MOL-owned) can operate under free market conditions. As local laws, and the Concession Contract both define the framework in which MOHU conducts its business, there are investments imperative for circularity that can be taken by MOL Group, and potentially belong to CES division.

This price regulation methodology of the waste management public tasks covered by the concession is based on Section 53/N Hungarian Act CLXXXV of 2012 on Waste (Waste Act) in accordance with MEKH Decree 16/2022. (21 December 2022) of the Hungarian Energy and Public Utility Regulatory Authority (MEKH) on the principles and framework for the determination and regulation of the eligible costs of the concession company performing the public task of state waste management, the concessionary subcontractors (hereinafter „CS") and the municipalities, as well as the preparation of fee proposals on the fees to be collected for the service of the public task of state waste management.

The methodology contains the basic principles and framework rules for determining and regulating the eligible cost and expenses of the concession company and CS as well as in the public service and institutional subsystems like the extended producer responsibility (EPR) subsystem, the deposit refund subsystem (DRS), the subsystem of the separately collected waste of companies and the public cleaning waste subsystem (they are called 'subsystems').

Because of the setup of the waste management system, affected stakeholders exert a great influence. The Ministry of Energy of Hungary and the Hungarian Energy and Public Utility Regulatory Authority both closely monitor and regulate how the system is operated. Among others, they monitor compliance with the Waste Act, as it prescribes for MOHU that for valuable waste, compensation has to be paid for the waste generating undertaking – should the extent of the compensation be debated, MEKH might be requested to facilitate and decide based on their methodology. Furthermore, the regulation in effect puts emphasis for the affordability and service level of public services. Therefore, stakeholder management itself, and their priorities and requirements are heavily taken into account when designing a development roadmap for a more sustainable waste management system in Hungary.

TARGETS RELATED TO THE CIRCULAR ECONOMY SERVICES BUSINESS SEGMENT

/E5-3/

Main targets of the segment originate from the ***Concession Contract***, and commitments made there. Currently, only MOHU is concerned in terms of these indicators, as other subsidiaries with total control are in setup phase and so do not have any productive operations.

Highest level targets are related to the EU Waste Framework Directive (WFD), and relevant sections are the ratio of landfilling and ratio of recycling, of waste volumes with relevance under the directive. These targets are applicable for Member States and have been cascaded down to MOHU as official targets, and influence operations and decisions in the following way:

- Aforementioned targets have positive **impact** of making Hungary more sustainable and circular;
- MOHU aims to avoid the **risks** by making decisions that ensure business/industry continuity, and develop the Hungarian waste system so no facility shortcoming can threaten the reach of EU targets [e.g., have enough waste to energy (incineration) capacity as landfill target is unreachable without it; however, as this is out of the concession's scope, the parent company (MOL Group) can be the decision-making entity];
- as an indirect effect, by enhancing Hungarian waste management system, volume and pureness of secondary raw materials can be increased, thus it is easier to provide feedstock to be recycled and to realize **opportunities**.

In CES, and currently mainly in MOHU, policies and via that, actions are driven by these objectives, and actions are taken in line with the policies. These targets are coming through main stakeholders – regulatory and authority bodies EM (Ministry of Energy) and MEKH. Following targets are relevant and declared as of now:

Build a Minimum 100 kt Capacity Waste-to-Energy (W2E) Plant

MOL Group recognizes in its strategies and policies that certain materials cannot be recycled. These approaches have been approved by key stakeholders. Waste incineration helps us moving waste otherwise disposed to be used for energy recovery, which is a higher method in the waste hierarchy. Thereby, project is aligned with the two waste targets from the EU Waste Directive, ensuring compliance with regulatory requirements and helps supporting concession commitments.

EU Landfilling Target: Maximum 10% of Municipal Solid Waste (MSW)

The goal is to reduce landfilling by keeping waste management within the waste hierarchy, avoiding disposal wherever possible. The target supports circularity and mitigates risks of non-compliance with EU goals and concessions commitments. The target is based on Council Directive 1999/31/EC on the landfill of waste with a deadline until 2035, with a possible derogation extending to 2040 if granted. All CES firms contribute to meeting the requirement, which states that Member States must reduce MSW landfilling to 10% or less by 2035. This directive, strictly monitored by EM/MEKH, assigns responsibility primarily to MOHU. The target is relative, with 2023 as the baseline, when landfilling was around 50%. MOHU's operations started in 2023, marking the start of progress measurement.

EU Reuse or Recycling Target: Minimum 65% of MSW

The target relates to nearly all levels of the waste hierarchy, above energy recovery, emphasizing the importance of reuse and recycling. The target is based on Directive 2008/98/EC, which mandates Member States to achieve a minimum of 65% reuse and recycling of municipal waste by 2035 and represents a significant business opportunity for MOL Group. All CES firms contribute to achieving this objective, enabling a high level of resource efficiency within a European circular economy. MOHU holds the primary responsibility, with other CES firms benefiting and contributing. The target is relative, with 2023 as the baseline, when reuse and recycling rates were approximately 34%, as MOHU had just initiated operations.

Investment Commitment: 185 Billion HUF

This investment is designed to promote recycling and recovery, with potential implications for reuse. The commitment addresses impacts and risks identified during the materiality assessment, while providing a foundation for new business opportunities for MOL Group segments. The investment must align with the concession agreement with the Ministry of Energy, reflecting a joint understanding of objectives. The deadline is 2033, covering the firm concession period (2023–2033). The target is absolute and rolling/cumulative, with the baseline being the concession start in 2023. By the end of 2024, the investment reached 53 billion HUF. MOHU bears the primary responsibility, with Holding and MOHU BP benefiting as receivers of developed assets.

METRICS RELATED TO RESOURCE IN- AND OUTFLOWS OF THE CIRCULAR ECONOMY SERVICES BUSINESS SEGMENT

/E5-4; E5-5/

Current metrics are defined according to the commitments MOHU made. These metrics are integral to targets and relate to all 3 IROs, and for waste volumes, have a 1-year lag in reporting due to legal limitations, and resulting process in cooperation with Ministry of Energy.

Data point	UoM	Target	2024	2023	2022
Ratio of MSW prepared for reuse or recycling	%	65%*	n/a	33.7%***	32.8%****
Ratio of MSW landfilled	%	10%*	n/a	49.5%	55.3%****
Committed CAPEX spending (rolling/ cumulative value)	HUFbn (USDmn)	185** (cca. 490)	53 (146)	21 (63)	n/a

* By 2035 (2040, if derogation is applied)
** Between 2023 and 2033
*** Based on 2023 half-year data
**** Not under influence of MOHU or CES entities

Methodologies and assumptions of relevant metrics are as follows:

- The two relative metrics stem from EU definitions, while capital expenditure (CAPEX) is only MOHU relevant – concession commitment spending spent by the sole concessionaire entity of CES.
- Ratio of municipal solid waste (MSW) prepared for reuse or recycling:
    - numerator: it is the sum of
        - waste prepared for reuse or recycling (handed over or into inventory), paper, plastics, metal, glass, from public service and institutional (i.e., separate collection of businesses' waste) subsystems
        - other wastes prepared for reuse or recycling, from selective collection (HAK/EWC 20, except 20 03)
        - green waste delivered for composting
        - green waste in home composting
    - denominator: it is the sum of
        - total MSW collected

        - green waste in home composting
        - LESS end-of-life vehicles, end-of-life tyres, demolition-construction waste
    - base unit of measure: kg per calendar year

- Ratio of MSW landfilled:
    - numerator: it is the sum of
        - MSW disposed of via landfilling
        - LESS ash and residue from incineration
    - denominator: it is the sum of
        - total MSW collected
        - green waste in home composting
    - base unit of measure: kg per calendar year

- *These two ratios are validated by the competent governing body, the Ministry of Energy annually, as part of legal data provision requirements*

- Committed CAPEX spending
    - validated through the auditor in the financial statements, all organic CAPEX spent by MOHU in a given financial year (reported as part of CES in Chapter 2. Segmental information of Consolidated Financial Statements 2024)

Regarding further disclosure requirements: from own operations, there is currently no own waste production, there is no resource inflow for own processes, and only resource outflow is clean secondary raw materials – MOHU is non-waste-generating from this point of view:

- amount of non-recycled waste: not material (not only for MOHU, but all other CES firms),
- hazardous waste and radioactive waste: not material.

EXCLUDED DISCLOSURE REQUIREMENTS FROM ENVIRONMENTAL STANDARDS:

Topic	Relevant IDs	Explanation
Anticipated financial effect	E1-9 E2-6 E3-5 E4-6 E5-6	Quantification of anticipated financial effects is under phase-in based on Appendix C of ESRS.
Carbon credits	E1-7	In 2024, MOL Group has not financed any GHG removals and GHG mitigation projects through carbon credits.
Pollution targets	E2-3_02 E2-3_03 E2-3_04	Currently there are public no Group-level targets set in relation to water and soil pollution prevention, prevention and control of substances of concern and substances of very high concern.
Microplastics	E2-4_05 E2-4_06 E2-4_07	We have not identified any material IROs in relation to microplastics, therefore associated disclosures are not considered material.
Substances of concern / substances of very high concern	E2-5_02 E2-5_07 E2-5_08 E2-5_13	Data on substances of concern / very high concern are only reported from the outflow perspective, i.e., those amounts which leave the facilities either as emissions, as sold products or as part of sold products. No services where identified where the use of substances of concern / very high concern is material.
Marine resources	E3-1_09	Extraction and use of deep sea minerals, gravels and seafood products are not considered material for MOL Group.
Water risk	E3-4_02 E3-2_03 E3-1_07	Based on the AQUEDUCT Water Risk Atlas, MOL Group's operation do not affect or are reliant on any areas with high water stress. /E3-1_07/
Biodiversity	E4-1 ESRS 2 SBM-3 E4-2_03 E4-2_04 E4-2_05 E4-2_06 E4-3_02 E4-3_03 E4-3_04 E4-2_18 E4-2_19 E4-2_20 E4-3_02 E4-3_08 E4-3_09 E4-4 E4-6_03 E4-6_04	During the latest double materiality assessment, impact on the extent and condition of ecosystems (IM-06) has been identified as a material topic. Policies, actions and targets related to impacts of pollution and climate are addressed other topical standards (i.e., E2 and E1 respectively). Other topics related to biodiversity are not considered material (e.g., social consequences of biodiversity and ecosystems-related impacts; freshwater -use change and sea-use change; direct exploitation; invasive alien species; impacts on the state of species). No material dependency, risks or opportunity have been found in relation to biodiversity and ecosystems, therefore disclosures related to implications for MOL Group's strategy and business model are not considered material. Besides the policies and actions plans described in chapter E4 of this report, MOL Group has not published a comprehensive transition plan related to biodiversity and ecosystems, or set any public Group-level targets. MOL Group has not used any biodiversity offset mechanism is 2024.
Energy data	E1-5 E1-6_18-23	Reported renewable energy consumption and production on MOL Group-level has remained low, below 0.5%. Disclosed values are not inclusive energy management is managed locally by relevant entities. Development of a Group level approach – including data collection on small-scale renewable energy production (e.g., solar panels installed at office buildings and service stations) and incorporating contractual power purchase agreements with certified emission factors is currently under development. Consumption of energy from nuclear sources and coal is not reported, as MOL Group does not use these energy sources directly. Electricity purchased from utilities is classified as fossil-based, as the actual energy mix cannot be reliably accounted for at the Group level.
Data on resource inflows and outflows	E5-4_02 E5-4_03 E5-4_04 E5-4_05 E5-5_02 E5-5_03 E5-5_04 E5-5_05	MOL Group's main products are refined petroleum products and petrochemical products mainly to wholesale consumers – therefore disclosures related to the durability, reparability and recyclability are not material disclosures. For information on secondary material use, please refer to disclosures on Waste-based fuel usage and production (OP-08).

DISCLOSURES ON SOCIAL STANDARDS

WORKFORCE

/S1/

INTRODUCTION

In our 2024 double materiality assessment, we identified the following impacts and risks related to workforce:

- Secure employment on fair terms (IM-12)
- Training and skills development (IM-14)
- Work-related injuries and road accidents (IM-13)
- Operations in areas with low security (IM-19)
- Corporate culture (IM-11)
- Labour market risks - Employee attraction & retention capabilities (RK-07)
- Personal injury risk due to system integrity failure or accidents (RK-04)
- Exposure to security threats (RK-09)

Description of the methodology and consultations conducted are described in section ESRS 2 IRO-1 of this report. We concluded the topic 'Own workforce' to be material from both impact and financial perspective. We have identified one impact which is specific to the topic 'Worker in the value chain': Human rights & labour practices in the value chain (IM-15). MOL Group exposure to the risk of incidents of human rights abuse, forced labour, child labour, modern slavery and human trafficking is relatively minor given that most of the Group's activities are performed in European countries. Nevertheless, MOL Group is committed to lawful and fair employment and to respecting labour principles, and expects the same from business partners and external stakeholders via contractual arrangements described in the Business Partner Code of Ethics and other policies - as described throughout this chapter. MOL Group will not tolerate any form of forced, compulsory, bonded or child labour or any other kind of unethical employment practice such as withholding wages, denying sick leave or daily rest, abuse of alternative employment forms or evasion of health care contributions. We ensure that these forms of labour and slavery, servitude, and human trafficking do not take place within our business and supply chains.

Since value chain related information is currently in phase-in period under ESRS reporting, limited information is disclosed in this regard in 2024. Currently MOL Group is working on developing its methodology on supply chain due diligence to comply with upcoming requirements under the Hungarian Act CVIII of 2023 ("ESG Law") applicable from 2025, and the Corporate Sustainability Due Diligence Directive.

Impacts and risks related to workforce can be categorized into 3 interconnected, yet distinct groups. This also means that the management of these IRO groups require different approaches and expertise, therefore generally handled is separate policies and actions, and measured and monitored by different progress metrics. This chapter is divided into the following 3 sub-chapters with the aim to describe how MOL Group manages the listed IROs, outlining specificities of each group:

Sub-chapter A focuses on the impacts on the company's employees, such as wages & hiring (IM-12), trainings and skills development (IM-14); and risks related to human resource management, such as employee attraction & retention capabilities (RK-07). This sub-chapter is generally focused on MOL Group's employees – in line with ESRS definition – i.e. individuals in an employment relationship with MOL Group according to laws. Albeit our internal policies and the presented data and analysis only apply to those individuals, we acknowledge that other groups of workers such an non-employees (individual contractors and agency workers supplying labor to the company) or value chain workers are also impacted by our operations. As stated in MOL Group's HSE and Social Impact Policy and in the Code of Ethics and Business Conduct, we strive to consider business, social, environmental, health, physical and emotional consequences of actions and committed to accomplish business objectives in a manner that causes the least harm and the greatest positive good not only for own employees but also workers in our value chain, in our communities and in society at large.

Sub-chapter B describes how impacts and risks related to the health and safety of workers are assessed and mitigated (IM-13, IM-19, RK-04, RK-09). MOL Group has comprehensive Group-level management system to cover occupational health and safety both for workers who are in an employment relationship with one of its companies – hereinafter referred to as own staff – and workers supplying labour to the Group via individual contracts or through employment placement agencies - hereinafter referred to as contractors. Both own staff and contractors are covered within MOL Group's relevant policies, and included in our data collection. Any individual falling out of the scope of own staff and contractors are considered as 'third party' in our reporting practices. Individuals described as "value chain workers" by ESRS - who aren't considered neither own staff or contractors are not allowed to conduct any work in our sites, therefore they are not covered by MOL Group's occupational health and safety policies. Occasional visitors at our sites receive the necessary induction on safety rules, must be accompanied and receive any personal protection equipment if necessary – however, this chapter focuses on occupation health and safety, therefore safety aspects of any third-party individuals are not covered here.

Sub-chapter C highlights corporate culture and ethical aspects (IM-11), focusing on diversity, equal pay for equal value, inclusion and measures against unethical behaviour. MOL Group has implemented a range of binding policies to ensure that ethical standards are upheld and integrated into our everyday operations – including but not limited to human resource management. MOL Group also expects all of its stakeholders in its value chain to respect and have measures to assure compliance with these values.

Each sub-chapter starts by providing a detailed description of IROs relevant for the topic, then details of the policies, actions, targets and metrics on outlining how these IROs are managed by MOL Group.

SUB-CHAPTER A: HUMAN RESOURCE MANAGEMENT

IDENTIFIED IMPACTS AND RISKS RELATED TO HUMAN RESOURCE MANAGEMENT

/S1. IRO-1, S2. SBM-3/

ESRS	Disclosure Requirement related to ESRS 2 SBM-3, S1.IRO-1:
GRI	GRI 3, 3-3

MOL Group's double materiality assessment conducted in 2024 included the identification of impacts, risks and opportunities related to workers. The general methodology and consultation process are detailed in section ESRS 2 IRO-1 of this report. Identification of actual and potential impacts on and risk associated with our own employees, which are discussed in this chapter, is conducted by continuously collecting feedback from our workforce and regular engagement surveys. Please refer to the "HR Advisory" paragraph of the S1-A-1&2&3 section of this chapter for more information.

IROs related to human resources described in Table IM-12, IM-14, and RK-7 below:

Table IM-12: Secure employment on fair terms

Severity	Significant
Scope	CEE
Likelihood	Actual impact
Description	MOL Group is a key employer in the Central-Eastern European region. It provides stable employment to around 25,000 people in its own workforce, and indirectly to many contractors and others via its value chain. Besides this positive effect, in case of potential negative business performance of the Group, spill-over effect might not only impact own employees adversely, but also the local job markets due to the Group's high share in employment.
Mitigation actions & remendability	Besides regularly engaging directly with its own employees and monitoring satisfaction, the company actively engages in collective agreements and collaborates with trade unions to ensure fair employment practices. For details on policies, processes and key actions see DR S1-1, S1-2, S1-3, S1-4.
Time horizons	We consider the topic material on all time horizons.
Relevance in the value chain	Secure employment on fair terms is a material impact across all levels of MOL Group's value chain.

Table IM-14: Training and skills development

Severity	Moderate
Scope	CEE
Likelihood	Actual impact
Description	MOL Group is dedicated to investing in human capital via trainings and skills development programmes, emphasizing the importance of professional development, health, safety, well-being, and corporate ethics. MOL Group prioritizes hiring new entrants to the job market and recently graduated professionals. Through these initiatives, the company positively impacts human capital development and contributes to the availability of a trained and educated workforce in the region.
Mitigation actions & remendability	To support its commitment, the company offers a variety of training and development programs for its employees and contractors. In total, over 709 thousand hours of training were recorded in 2024, and USD 7.5 million euros were allocated for trainings and skills development. Additionally, the company collaborates with and funds institutions that provide vocational training and education programs. The company also provides apprenticeships, internships, graduate programs, and career orientation and pre-recruitment programs. For details on policies, processes and key actions see DR S1-1, S1-2, S1-3, S1-4.
Time horizons	We consider the topic material on all time horizons.
Relevance in the value chain	Training and skills development is material impact across all levels of MOL Group's value chain.

Table RK-07: Labour market risks - Employee attraction & retention capabilities

Type	Operational risk
Likelihood	High
Magnitude of financial effect	Medium
Description	Attracting and retaining a capable and diverse workforce to ensure the operation of its complex activities is a constant challenge for the company. Key risks in the labour market currently include high turnover and increasing wage pressure due to the current macro environment, aging population, and the availability of trained personnel in the market. This is especially critical for new and highly knowledge-intensive business lines requiring different capabilities and rapid upskilling/reskilling.
Related impact & dependencies	**Impacts:** MOL Group, as a key employer in the CEE region, has significant impacts on not only on its own workforce, but also workers in its value chain. Identified impacts related not only to providing employment (IM-12), but also to the development skills & capabilities of workers (IM-14) and working towards sustaining favourable working conditions (IM-11). **Dependencies:** Its approximately 25,000 workers is a key asset to MOL Group. The company is dependent on having sufficient number of employees with suitable skillset to ensure smooth operations.
Mitigation actions	Actions related to this impact (see IM-11, 13 & 15) are all important factors in strengthening employee attraction, retention and upskilling capabilities thus reducing risks stemming from the labour market. For details on policies, processes and key actions see DRs S1-1, S1-2, S1-3, S1-4.
Financial effect & time horizons	In 2023, the total employee benefits paid was over 870 million euros, thus we consider the topic *own workforce* financially material. Due to the aforementioned labour market trends (increasing wage pressure, aging population, fluctuation), we consider this a long-term risk.
Relevance in the value chain	Labour market risk is a material risk across all levels of MOL Group's value chain.

POLICIES & ENGAGEMENT RELATED TO OWN WORKFORCE

/S1-1; S1-2/

ESRS	Disclosure Requirement S1-1,S1-2
GRI	GRI 2, 2-12 GRI 2, 2-23 GRI 2, 2-25 GRI 2, 2-26 GRI 2, 2-29 GRI 3, 3-3 GRI 403, 403-2

To manage material impacts, risks, and opportunities related to the workforce, including specific groups within the workforce or the entire workforce, MOL Group has several policies and strategies in place. The key pillars of the updated **Group level People Strategy** which was presented to the MOL Group top management and Supervisory Board members in June 2024 - are:

- **Refine:** Refining & Digitalising HR processes and enhancing the ONE HR database
- **Attract:** Make MOL Group one of the most desired employers
- **Engage:** Ensuring employees know what we offer, cultivating talent and building a culture which retains our key people
- **Develop:** Helping our leaders grow, empowering our experts & blue collars to grow, paying special attention to talent
- **Build:** Strengthening the collaboration within the ONE HR community

These key principles are integrated into MOL Group's process-based policies. The aim of policies is to define the mandatory elements and steps in change management processes, risk assessments, and mitigation measures. The Group also focuses on attraction, retention, and development of people, whilst also ensuring the availability of workforce in sufficient quality and amount to enable the continuity and development of our business operations by mitigating labour market risks (RK-07).

The **Human Resources Area Book** is the highest level process-based policy in the field of Human Resources defining main HR processes, rules and requirements and strategic goals to ensure top quality HR services across the MOL Group, compliant with local legal and market requirements. The provisions of this policy are obligatory and binding for affected employees. The implementation – via incorporating them into local / entity specific policies (e.g. applicable specific subsidiaries), or topic specific process descriptions (e.g. recruitment & selection, renumeration, or talent management rules) is the common responsibility of the Group HR Senior Vice President, local CEOs and local HR Managers. To ensure affected stakeholders' awareness, MOL Group has mandatory trainings covering all key areas, whilst relevant policies are available to all employees on MOL Group's E-REG system. Human Resources Area Book describes the 6 core processes which must be implemented at all MOL Group companies (i.e. MOL Plc. and controlled operative subsidiaries involved into matrix operation):

1. Employee Attraction, Recruitment, and Selection

MOL Group focuses on building a robust talent pipeline to achieve its long-term strategic goals. Through strong relationships with educational institutions and strategic workforce planning, the company ensures a steady influx of skilled employees, particularly young talent, to meet mid- and long-term business needs. This directly addresses the challenge of labour market risks (RK-07) by strengthening MOL Group's ability to attract and retain a capable and diverse workforce, which is critical for maintaining operational excellence and adapting to rapidly evolving business demands; whilst has a positive social-economic impact by providing employment opportunities and helping the entry of young people into job market. (IM-12)

2. Reward and Benefits

To ensure secure employment on fair terms, MOL Group's remuneration structure is based on transparent principles of internal equity and external competitiveness. Job positions are evaluated using the Hay methodology and pay scales are benchmarked against international market standards. Employee benefits are designed to enhance physical, mental, social, and financial well-being, fostering engagement and retention. By aligning compensation and benefits with market trends and business strategy, MOL Group ensures fair and stable employment (IM-12) while attracting top talent (RK-07) in a competitive environment.

3. Learning and Development

MOL Group invests in continuous leadership, professional, and technical capability development for its employees. Training opportunities are tailored to meet individual and organizational needs through various methods, including classroom sessions, e-learning, mentoring, and coaching. Managers are encouraged to actively support employees' professional growth, ensuring alignment with business goals. By prioritizing skills development and professional advancement, MOL Group contributes to regional human capital development and secures a well-trained workforce capable of driving innovation and operational success (IM-14).

4. Workforce and Employment Management

Employment contracts are prepared in compliance with local legislation, guaranteeing clear terms and stable working conditions, and secure and fair employment terms for all employees. Flexible work arrangements are offered wherever feasible, supporting a balance between business requirements and employee well-being (IM-12).

5. HR Advisory

HR advisory processes focus on fostering an inclusive, ethical, and transparent workplace culture. MOL Group supports social dialogue through regular engagement with trade unions and workers' representatives; and by regularly monitoring employee satisfaction.

Work representatives in MOL Group play a crucial role in maintaining a harmonious and productive work environment. They act as a bridge between the employees and the management, ensuring that the concerns and suggestions of the workforce are heard and addressed. MOL Group supports fair treatment practices such as guaranteeing diversity, ensuring fair and equal remuneration and supporting freedom of association by partnering with trade unions and work councils that are active across the Group and engage the majority of the Group's employees. On Group-level all employees are represented by the European Works Council (EWC). The Council was re-elected in 2023 for a five-year mandate. European Work Council organizes a Senior Management Forum twice a year, where senior managers give updates regarding the actualities and the committee members ask their questions relevant & collected from the countries. Furthermore, trade unions are present in the following MOL Group countries: Hungary, Croatia, Slovakia, Bosnia and Herzegovina, Poland, Romania, Montenegro and Russia.

Besides engaging with worker's representatives, MOL Group also conducts direct assessment of the wellbeing and employee engagement via regular people surveys and pulse checks. Upon survey results, focus areas must be defined, and action plans shall be developed at company, business segment, and unit level to address critical areas. Furthermore, the company is also committed to provide financial support to individual workers facing unexpected challenges – for instance, via the Social Fund in MOL Hungary. The allocation of this fund is determined by the trade union.

MOL Group Employee Engagement Survey is launched every two years where they can monitor the engagement level of the workforce. Regarding the process, an external vendor, hired by Group Human Resources, provides the questionnaire based on previous years' questions and actualities which is preshared with business representatives and top management for review before the launch of the survey. After survey takes place in an external, online platform, MOL Group level results are presented for top management and the set directions and expectations are cascaded down.Besides the biennially launched survey, pulse check is available for the organizations to monitor the engagement and mood for their employees.

Besides the general process of Employee Engagement Survey and its action, other MOL Group HR processes are aiming for indirectly impact and increase engagement as well. These processes are regulated internally in the **Talent Management Process Description** - approved by the Head of Group Capability Development & Strategic HR, and applicable on the same scope as the **Human Resources Area Book**. The aim of this document is to ensure the strategic objective to increase overall company engagement by defining clear rules and processes to be followed. One of the key enablers are recognition and stay interviews: Recognition is one of the most important drivers of great work which helps to retain top Talent, enhance employee engagement and encourage performance. Recognizing Talents gives them positive reinforcement that their efforts are appreciated and valued. Furthermore, Stay Interviews are regularly conducted with a focus on understanding the Talent's drivers of staying with the company and triggers of leaving. Following up on these two angles of their engagement to the company provides arguments for improving our Talent retention strategy.

6. HR Process Design and Control

Two way communication is essential for HR processes to remain efficient, transparent, and responsive to organizational needs. Therefore, employees are encouraged to propose new ideas and improvements via multiple channels fostering an innovative HR environment. The flagship forum to ask questions from management, raise concern or propose ideas are the regular Townhall events within MOL Group divisions.

In case an employee's concerns are not addressed on local level or via public channels, they are encouraged to use the Group-level SpeakUp! mechanism accessible for all internal and external stakeholders for advice or to raise concerns ("whistle-blowing"). Reports can be made anonymously and will be treated as confidential, without risk of reprisal. For further details, please refer to Section S1-C-1&2&3 of this report.

ACTIONS RELATED TO HUMAN RESOURCES

/S1-4/

ESRS	Disclosure Requirement S1-4
GRI	GRI 3, 3-3, d GRI 403-9 GRI 403-10

On the back of rapid changes and long-term structural trends affecting labour markets as well as our industry and company transformation ahead, talent attraction and development programs are essential in order to ensure not only the necessary skills and competencies to execute the business strategy, but to continue building a strong employee pipeline whilst ensuring inter-generational knowledge sharing due to aging and retiring workforce in the core regions where MOL Group operates (RK-07).

Within talent management framework the focus is to support our leaders attract and identify, develop, retain and promote MOL Group Talents through impactful and efficient process and by using unified Talent Management language and terminology. Last year 1871 colleagues were identified as talents out of which 281 people are in senior expert or managerial roles, these numbers show similar trend compared to previous years. Talent MNG HUB, a platform serves as a one stop shop for MOL Group Leaders to educate themselves with short e-learning videos and materials, has been visited by 949 unique visitors, with 235 test completions with 70% success rate in period December 2023-February 2024. Overall, 58 People and Talent occasions have been organized as discussion platforms of MOL Group people and talents. We have registered 220 Stay interviews, which have confirmed the results from 2024 in terms of main drivers of key people and talents staying in the organization and triggers for leaving the organization. Based on career focus discussion 40% of survey sample showed the ambition to transition to a new role, both short and long term.

When it comes to talent development, there are many available solutions within MOL Group, e.g. mentoring, coaching, leadership and professional expert development program. Last year retention/engagement toolbox was rolled out in Hungary in order to further upskill our leaders of increasing talent retention efficiency and also handling well moments that matter. Over 250 managers participated at 7 live managerial workshops in MOL Campus (Budapest), the Százhalombatta Refinery, MOL Petrochemicals (Tiszaújváros). During the last 3 months, 180 colleagues visited the Retention toolkit pages.

MOL Group's premium leadership development program is LEAD, where the focus was on the ongoing LEAD2024 streams last year, including a newly introduced LEAD Transformational stream. Further emphasize was put on LEAD Alumni network, LEAD Alumni Conference will be organized for the 3rd time in Q1 2025.

In 2024, 92 fresh graduates from 8 countries were hired within Growww framework, reaching 48% female ratio.

In Hungary, Secondary school technical education stayed in focus – new classes started in Százhalombatta (SziSzKI), 4 MOL classes were created with our financial support in 2024. We had 191 dual high school students, out of which 46 finished their school, 43 dual engineers where the retention rate is 90% (meaning 90% of students stayed within MOL after completing their studies). More than 120 MOL colleagues are dedicated to share their knowledge and attract young talents by teaching at universities.

In Croatia, INA collaborated with 15 faculties and 2 student associations, 5 technical and 1 catering school. Regarding internship, 20 pupils took part in dual internship, 34 students on regular internship, 6 students started their internship on our gas stations, 8 lectures organised by INA Group experts on faculties.

In Slovakia, Slovnaft collaborated with 3 technologically focused secondary schools. A Memorandum of cooperation with two new schools was signed last year. Students have different practical trainings on site of the company, especially in the newly established training center in VURUP laboratories. Training center is utilized also for a new operators' theoretical education. In school year 24/25 we have 17 students included in the practical education.

MOL Group's reputation as a leading regional employer was further strengthened through recognition from more than 25 global and local external awards.

Besides efforts to continue building a strong employee pipeline to mitigate human resource related risks, MOL Group focuses on enhancing positive impacts, and preventing and mitigating negative impacts on workers' well-being. In recognition that regular assessments and data-driven measurements are key enablers of appropriate response and effective actions, employee engagement survey has been conducted in 2024 with the fulfilment rate between 92-95% of 40,000 employees in scope (MOL Group's 25,000 employees the addition 15,000 includes Retail colleagues with separately dedicated survey). Altogether 759 actions were registered to increase employee engagement. As centrally driven action of Employee Engagement Survey result, Group Business induction training extended for all interested audience in HU and ENG languages was piloted and successfully conducted in Q4.

MOL Group supports fair treatment practices such as ensuring fair and equal remuneration and supporting freedom of association. MOL Group partners with trade unions and work councils that are active across the Group and engage the majority of the Group's employees. (IM-12)

On Group-level all employees are represented by the European Works Council (EWC). The Council was re-elected in 2023 for a five-year mandate. Its Executive Committee (EC) meets on a quarterly basis to discuss employment and operational related issues. The EWC held two ordinary meetings in 2024 with the participation of the MOL Group senior management. In 2024, the percentage of employees covered by collective agreements remained high at 90.3%. Trade Unions are active at the majority of MOL Group companies employing the 96.7% of the total headcount. Relevant laws concerning collective agreements differ on a country-by-country basis, but the majority of MOL Group companies are covered by collective agreements. Focus of the held negotiations was ensuring higher income for operational and expert employees, either through increases of base salary or through increase of different material rights, with optimum distribution of the available budget through utilization of any non-taxable opportunities on local markets. Trade unions and MOL Group company representatives continued close cooperation and through positive social dialogue defined ways of working which are supporting business continuity and ensuring successful and stable operations. In 2024 we have continued focusing on further digitalization of our processes in order to ensure that any unnecessary operational work is avoided and we increase the efficiency of our operations. Given that MOL Group is diverse and covers multiple locations, our focus in 2024 in terms of digitalization efforts was on harmonizing different local databases and creating a set of clear and standardized HR KPI's. In parallel with that, with the support of IT team, HR Technology team started to define the processes and ways where Artificial Intelligence can be used to support further streamlining and simplification of workflows, with the several specific projects in focus of "AI for HR" stream (creation of HR chatbot, use of AI in recruitment, etc.).

MOL Group continues to keep focus on its employee wellbeing strategy and ensuring that all employees can fulfil themselves in every aspect of their life and achieve a healthy work-life balance. Through internal and external channels, continuous communication campaign towards employees is organized in order to ensure that they are informed on all available benefits, including health – both physical and mental, parental support, financial benefits, and professional development opportunities. MOL Group is specially focused on health of our employees and through the benefit platform we ensure life, accident and travel insurance for each MOL Group employee. Additionally, on 3 core markets (Hungary, Croatia and Slovakia) which are covering ~80% of total employee population, as well as in most other MOL Group companies, we are ensuring additional healthcare benefits for our employees such as providing private health coverage and regular annual medical check-ups. Focus of the Group's wellbeing strategy also remained on ensuring the high level of maternity/paternity entitlements for employees (with a note that maternity/paternity practices and benefits differ among member companies across the Group since they are defined in compliance with local rules and local practices). With number of different benefits supporting the parents in their care for children, MOL Group is investing efforts in maintaining the status of 'family friendly employer'. Also as part of the wellbeing strategy, MOL Group companies continued enabling their employees to use the possibility of remote work in line with an updated rules introduced from 2024.

Recognising the positive effect of skills development and continuous learning on both the employees and the organisations success, MOL Group put great emphasis and allocated significant resources on training and development activities in 2024 (IM-14).

MOL Group Academy (MGA), continued to operate in progressing trend as the key internal knowledge hub for all MOL Group employees. This internal academy platform, presents digital learning opportunities for actual business, professional, soft skills and leadership development in the form of E-learning materials, pre-recorded training sessions, internal trainings and workshops etc. Within MOL Group Academy Framework, 69 trainings were organized, covering 40 topics for 1894 participants in total 6343 completed learning hours. Accelerated focus on Strategy Shape Tomorrow and the raised need for upskilling/reskilling resulted in 13.3% increase in average training hours per employee (34 in 2024 vs 30 in 2023) followed with 9% increase in average training costs which shows a moderate increase trend having in mind average training vendor cost increase in 2024, which was around 15%. In 2024, based on the changing requirements of the leadership, the Technical Competence and Career Development Program within E&P discontinued their assessments with the PetroSkills system and got started with the program revamp. During this period of revamp while the new system and methodology was being developed, the E&P colleagues continued to focus on their development plans made on the basis of the previous evaluation cycle helping them overcome the already identified competency gap areas. The Growing Professional Skills Program within DS area, on the other hand, followed through with the assessment cycle launched in Q3 2023 with multiple calibration sessions conducted with the business regarding the identified gaps followed by individual development planning and training executions. Within MOL Group around 2,600 white collar colleagues are enrolled in the TCCD/GPS program, covering 12 countries, and involving in the program more than 400 Subject Matter Expert, Managers and Cross-assessors.

In 2024, a Customer Service Protocol was fully implemented in every sales and marketing campaign to ensure a standardized approach to serving customers, with the primary goal of increasing gastro product sales. The results showed improvement through the introduction of monthly focus items, which effectively boosted customer engagement and sales performance. For 2025, main goal is to focus on supporting Partners to overcome any obstacles they face with the Hosts and help them achieve desired sales results and perform operation proficiency. For this purpose, Captain-on Board project is designed, which emphasizes onboarding new Partners and retraining existing ones with tailored soft skills training, designed based on research into their specific challenges.

In 2024, we had 6,295 active learners in LEON "Learn online" among blue-collars, who used the microlearning platform in an average of 182 days during the year. The companies in MOL Hungary using LEON: DS: 1150 users; MPK: 1150; Petrolszolg: 950; Logistics: 850; Upstream: 800; MOL LUB: 300; MOLTrans: 300; FER: 250; Geoinform: 200. INA Logistics joined LEON with: 350 licences as a pilot outside of MOL Hungary. Not less than 17 net hours were spent on average with different learning-activities in LEON, focusing mostly on HSE-related contents. The general knowledge-growth achieved 15%, which clearly indicates how much the safety awareness increased within the company. The satisfaction-rate among LEON users reaches 75%, while a third of the responders is highly satisfied with the tool.

After two years from enrolment of digital learning library concept, LinkedIn Learning in 2024 we have enrolled cca. 1600 employees across MOL Group with a learning license. Digital learning behaviours and patterns of our employees showed a positive trend of spending on average 1.2h monthly and watching 25 videos monthly per user on average using the tool which we find cost and time efficient and supporting the overall wellbeing of the employees by having the access to knowledge when most suitable for them to consume it. Major content learned over off-the-shelf digital learning was Artificial Intelligence for business, Microsoft Excel, Project Management and Leadership. MOL Group continued to focus on leadership development to support Group leaders in executing the business strategy. In cooperation with SEED (School for Executive Education & Development) and Cotrugli Business Schools, the sixth generation of LEAD2024, a one-year long Group- level leadership development program has been successfully rolled out for three leadership streams engaging 50 leaders. 2 colleagues started and 7 other completed their Corvinus-MSM SEED Executive MBA in 2024, and 11 started and 10 completed their Cotrugli MBA. Further 42 talents participated in different SEED leadership development courses. In 2024 we have continued with the Leader of Leaders Program in Hungary with 31 participants; also, we continued the First Time Leader Program in all core countries and on Group level, with total 129 participants. As integral part of the Group's leadership development portfolio, the Intensity modular development courses were attended by 119 colleagues in 2024. In addition, we have rolled out 8-month long Downstream Leadership Succession Program in all core markers participated by 57 colleagues, preparing them to step up into senior leadership role. Following successful start of the program at MOL and INA in 2023, Slovnaft identified 28 expert talents who joined the expert talents development journey Future@Slovnaft and MOL and INA continued with a second generation of the Future program with 175 participants in total in 2024.

Beside the above mentioned actions, MOL Group implemented several action related to diversity and inclusion. Find more details in Sub-chapter C of this chapter, in the 'Actions related to diversity and inclusion' section.


TARGETS RELATED TO HUMAN RESOURCES

/S1-5/

ESRS	Disclosure Requirement S1-5
GRI	GRI 3, 3-3

MOL Group' primary target in the field of human resources is to keep **sustainable employee engagement** level at minimum 75% at all times. As described in the Policies section of this chapter, Employee Engagement Survey is a biennial exercise where all MOL Group employees are asked to rate their satisfaction with their work experience at the company alongside various aspects. The target is met, if at least 75% of the employees select favourable ratings (typically the top 2 options from 5) for a set of key questions during this survey. The results are always assessed against international industry benchmarks as well. Since 2015, the following results have been measured:

Table: Sustainable Employee Engagement levels



METRICS RELATED TO COLLECTIVE BARGAINING COVERAGE AND SOCIAL DIALOGUE

/S1-8/

Freedom of association /S1-8_04/	UNIT OF MEASURE	2024	2023	ESRS
Employees with potential coverage of collective bargaining agreements	%	90.3	92.8	S1-8_05
o/w Croatia	%	100.0	-	S1-8_05
o/w Hungary	%	85.2	-	S1-8_05
o/w Slovakia	%	100.0	-	S1-8_05
o/w Other EEA	%	74.0	-	S1-8_05
o/w Non-EEA	%	0.0	-	S1-8_06

90.3% of employees are covered by collective bargaining agreement. In the EEA, collective bargaining agreements are per company, and coverage is for all employees in the company.

Social dialogue /S1-8_04/	UNIT OF MEASURE	2024	2023	ESRS
Employees covered by workers' representatives	%	96.7	-	S1-8_05
o/w Croatia	%	100.0	-	S1-8_05
o/w Hungary	%	98.9	-	S1-8_05
o/w Slovakia	%	100.0	-	S1-8_05

96.7% of employees are covered by worker's representatives as per the above breakdown. This is based on trade-union coverage. Employees at MOL Group are also represented by an European Works Council (EWC).

ADEQUATE WAGES

/S1-10/

MOL Group pays an adequate wage to all its employees. Employees are paid above the minimum wage in all jurisdictions where such legislation is applied, and where there is no minimum wage requirement, employees are paid above the wage level needed for a decent standard of living.

SUB-CHAPTER B: WORKER HEALTH AND SAFETY MANAGEMENT

IDENTIFIED IMPACTS AND RISKS RELATED TO OCCUPATION HEALTH & SAFETY

/S1. IRO-1; S1.SBM-3/

ESRS	Disclosure Requirement related to ESRS 2 SBM-3, S1-IRO-1
GRI	GRI 3, 3-3

MOL Group has comprehensive Group-level HSE MS to cover – besides all other aspects of Health, Safety and Environment – occupational health and safety both for workers who are in an employment relationship with one if its member companies – hereinafter referred to as own staff – and workers of companies or any individuals engaged by a MOL Group Company to carry out specified work – hereinafter referred to as contractors. The latter are typically operational/construction contractors (companies providing operational or project-oriented type works such as maintenance, construction, demolition, rearrangement, equipment installation etc.), vendors on premises (contractors providing definable activities such as shipping operations, food services, medical services, manufacturing, drilling etc.) and

service contractors (companies performing installation and maintenance services). This definition includes all levels of subsequent subcontractors. All contractors that provide workers and tools for the execution of the work are under the supervision and instruction of HSE MS of the MOL Group. Therefore, both own staff and contractors are covered within MOL Group's relevant policies and included in our data. Any individual falling out of the scope defined as own staff and contractors are considered as 'third party' in our reporting practices. Individuals described as "value chain workers" by ESRS – who aren't considered neither own staff, or contractors are not allowed to conduct any work in our sites, therefore they are not covered by MOL Group's occupational health and safety policies. Occasional visitors at our sites receive the necessary induction on safety rules, in general must be accompanied and receive the relevant personal protection equipment if necessary – however, this chapter focuses on occupation health and safety, therefore safety aspects of any third-party individuals are not covered here.

During MOL Group's double materiality assessment conducted in 2024, we have examined the health and safety of workers aspect with distinct attention within the *S1 – Own workforce* topic since our earlier assessment identified it as one of the top priorities. Therefore, we have found it worthwhile to dedicate a separate section within our report for this topic. Whilst the general methodology and consultation process related to the double materiality assessment is outlined in section ESRS 2 IRO-1, MOL Group's processes for the identification of impacts and risks related to the health and safety of workers is described in the *Element 2: Risk & Change Management*, and in *Element 6: Operational and occupational safety* of the HSE MS (For details, please refer to Section E1.IRO-1 of this report). These documents outline MOL Group's approach and processes to identify potential impacts on workers' safety through comprehensive programs that assess operational and maintenance activities, identify safety-critical tasks and equipment, and evaluate risks related to hazardous energy (e.g. electrical, mechanical, hydraulic, pneumatic, chemical, thermal, etc.) and health exposures. Permit-to-work processes and deficiency tracking systems further support the identification of risks before tasks are executed.

IROs related to workers' health and safety described in Table IM-13, IM-19, RK-04 and RK-09 below:

Table IM-13: Work-related injuries and road accidents

Severity	Significant, potentially irremediable negative impact
Scope	Local (in potentially territorial)
Likelihood	Medium likelihood
Description	MOL Group's main activities are related to the oil, gas and petrochemical industry, representing special personal and process safety risks of safety events, injuries or traffic accidents. The aim is to identify and manage these risks at operational sites, including their maintenance, and during hazardous material transportation (including in its value chain) with high-standard stringent safety regulations and protocols on work safety, health protection, fire protection and process safety. Besides some other rare factors, the most common causes of injuries regularly are the slips&trips; cuts & pinches on hand; road accidents; minor splashes of hot or hazardous materials; injuries caused by equipment.
Mitigation actions & remendability	MOL Group has a remarkable Health, Safety and Environmental Management System (HSE MS), derived of which strict health & safety protocols are applied in place, which are regulated not only on Group-level, but with additional, locally tailored, detailed regulations as well. These include safety rules, mandatory trainings, annual HSE programs and action plans and many more, ensuring an overall Group level compliance with Group HSE framework and in parallel full local legal compliance as well. Regulations and programs do not only cover own employees but contractors too. Since in many cases effects of injuries at the affected person could even be not remediable, preventing incidents is a strong priority.
Time horizons	We consider the matter to be material at all time horizons, with the aim of reducing the incidence rate and severity of incidents to the lowest possible level.
Relevance in the value chain	Work-related injuries could be material impact of MOL Group's industrial operations, including the Upstream, Refining, Petrochemical, Gas Midstream and in the Consumer Services business segments.

IM-19: Operations in areas with low security

Severity	Significant negative impact
Scope	Local
Likelihood	Low likelihood
Description	MOL Group has operations in areas with low security (crime, potential of armed conflict, terrorist attacks, piracy), thereby staff and contractors could face the potential threat of violence, or accidents/incidents due to damage on the facilities.
Mitigation actions & remendability	Reduce risk include implementing security measures such as maintaining a presence of local security equipment, processes and staff. To decrease the risk of targeting, the security staff's uniforms have been changed to civilian attire. The scale of potential impact is considered significant due to potential irremediability of serious cases.
Time horizons	We consider the issue material on all time horizons, with the aim of reducing the possibility of incidents to the lowest possible level.

Relevance in the value chain	Operations in areas with low security is material impact of MOL Group's Upstream operations.

Table RK-04: Personal injury risk due to system integrity failure or accidents

Type	Operational and physical risk
Likelihood	Medium
Magnitude of financial effect	Medium
Description	Industrial activities in which MOL Group is engaged are exposed to the risk of Process Safety Events due to the potential loss of mechanical integrity, technical, technological or operational issues, natural disasters or human errors.
Related impact & dependencies	Potential incidents might cause environmental damage (products spills, leakage of hazardous substances – see IM-04) and personal injuries (see IM-13). Spills are reported in DR E2-4, whilst information on safety incidents is reported under DR S1-14.
Mitigation actions	To reduce the likelihood and mitigate severity of incident due to Process Safety Events, MOL Group regulates the area on Group, on Group business and on local levels as well, prioritises rigorous maintenance, timely asset replacement, and adherence to strict safety protocols – refer to DR E2-1, DR E2-2 and DR S1-3, DR S1-4 for related policies & actions.
Financial effect & time horizons	The consequences of aforementioned potential events can materialise as expenses for the company in the form of remediation costs, or in extreme cases, fines. Financial consequences of incident on workers health cannot be quantified – MOL Group's approach is to prevent such events by having strict health & safety protocols in place, which are regulated both on Group-level with additional, locally tailored regulations. This includes safety rules, mandatory trainings, annual HSE programs and action plans. Please refer to DR S1-4 for actions and relevant actions. Cost of these prevention actions is considered financially material based on historic spendings. Please refer to DR S1-4 for relevant actions. The number and severity of the aforementioned incidents and process safety events within a continuous approach aiming a decreasing long-term trend, slightly fluctuates year-by-year – see DR (number of spills, TIER events, injuries). Therefore, on the short term likelihood of occurrence and magnitude of financial effects is hard to be reliably estimated. On the long term, we expect the risk to be lower due to improving technology, more developed mitigation actions and phasing out of old assets.
Relevance in the value chain	Personal injury risk due to system integrity failure or accidents is a material risk across all levels of MOL Group's value chain.

RK-09: Exposure to security threats

Type	Physical risk
Likelihood	Low
Magnitude of financial effect	Medium
Description	MOL Group operates E&P assets in areas where exposure to criminality, social unrest, terrorism and acts of war is present, posing potential threat to employees and contractors.
Related impact & dependencies	Details on associated impact: *IM-19 - Operations in areas with low security*. MOL Group mitigates the risk of incidents by strict safety measures and with the presence of local security staff (changed from uniformed staff to decrease the risk of targeting)
Mitigation actions	
Financial effect & time horizons	Financial effect of the risk is not quantifiable, but the topic is considered material (medium) due to indirect financial effects such as reputational consequences.
Relevance in the value chain	Exposure to security threats is a material risk of MOL Group's Upstream operations.

POLICIES RELATED TO HEALTH, SAFETY AND SECURITY OF WORKERS

/S1-1; S1-2; S1-3/

ESRS	Disclosure Requirement S1-1, S1-2, S1-3
GRI	GRI 2, 2-12 GRI 2, 2-23 GRI 2, 2-29 GRI 3, 3-3 GRI 403, 403-1

The following section outlines MOL Group's policies for assessing and mitigating impacts and risks related to the health, safety and security of its workers, including incident prevention, engagement with workers and remedies for material negative impacts.

General policy commitments related to HSE are outlined in the Group HSE and Social Impact Policy and Health Safety and Environment Area Book. Whilst, as said above, specific process-based requirements related to Occupational Health & Safety (OHS) are outlined in different elements of the HSE MS. The provisions of HSE MS are mandatory and binding for all affected employees (own staff and contractors) for all types of operations and projects. The general processes and principles are listed below. In addition, detailed requirements are regulated in appendices of HSE MS and further process descriptions. The management system requirements (along with HSE legal compliance and regulatory requirements) are implemented through local regulations embedding HSE principles into operational activities. Given the integrated nature of the business, MOL Group is active in several industries though different businesses in different jurisdictions. As a result, in some cases, legislation requires to have some specific ISO/OHSAS related accredited certifications. A complete list is accessible on the following sites:

- MOL Plc. (Hungary): **Standard-based Management Systems**
- INA d.o.o (Croatia): **Certificates**
- Slovnaft a.s. (Slovakia): **Standard-based Management Systems**

Hazard identification, risk assessment, and incident investigation:

- Based on the hazards and risks that are identified, assessed and periodically (and if needed occasionally) reviewed, the appropriate risk assessment methodology must be applied by competent personnel. Risks and mitigation actions must be communicated to all affected parties. The risks of changes must be assessed and managed. All MOL Group-level and local-level Business Units/ Functional Units and legal entities must comply with local risk assessment legislation relevant to their activities (e.g., local SEVESO regulation, workplace risk assessment, etc.). All kinds of hazards and risks arising from the operation of any MOL Group Company must be identified, assessed, registered, controlled, and regularly reviewed to prevent or reduce the likelihood and consequence of incidents to as low level as reasonably practicable (ALARP). The following hierarchy of controls must be followed as far as it is reasonably practicable when defining risk mitigation measures:
    - elimination
    - substitution
    - engineering control
    - administrative control, and
    - adequate protection (e.g. collective or personal protective equipment).
- These processes in general follow the main group requirements but considering the very different legal obligations need to comply with local law. Accordingly, the competent personnel also fulfil both the group general and local legal requirements. Based on reviewed hazard identification, risk assessment and incident investigation results, the management system is continuously updated (at least bi-yearly by definition, but even more frequently – last update was released in January 2025) to ensure the continuous improvement, in parallel with industrial best practices. The updating starts from Group level, managed by the relevant professional area's experts and leaders, then it is followed by a wide, business and HSE professional commenting, to get the final consensus.
- In the case of HSE events, including near-miss cases, especially with high potential (HiPo) consequences, it is crucial to identify why and where things have gone wrong and how they can and must be corrected to prevent future recurrence, losses and interruptions to operations by improving the management system and organizational culture that allowed the incidents to occur in the first place. Based on HSE MS, Element 10: 'Incident management', all incidents must be reported, recorded and properly investigated, relevant preventive and corrective actions defined and implemented, finally all learnings communicated. All details of these steps are defined in the Appendix 8 (Detailed rules for Incident Management (Element 10). Thanks to this written rules workers are protected against any reprisals, furthermore, being promoted for reporting any events, near misses or even unsafe acts, unsafe conditions and safety rule violations.
- Element 10: Incident Management part of the HSE MS (used IT tool is the Enablon, like for the entire Group-level HSE data management) integrates immediate electronic reporting of incidents through emailing and the tool supporting a thorough incident investigation. For investigating serious incidents, we apply industry standard root-cause analysis methodologies (e.g. 'Tripod', or 'Bow Tie', etc.). Lessons learned are shared throughout the company in comprehensive summaries and photos as part of the HSE Alert system to increase the level of knowledge and awareness of all employees. We encourage all employees and contractors to report all HSE events, even the unsafe conditions and acts potentially leading to those. We are committed to share all information in a personalized way as much as possible.
- On the highest level in HSE MS, Element 3: Competence, Training & Behavior 7.c) we declare that „everyone understands their responsibility to "Stop and Intervene" and is motivated to apply Stop Work Authority during any activity in which risk is not adequately controlled or refuses to work in circumstances that may cause HSE harm. Additionally, according to the HSE MS appendix 6. B II. 2.2 Rights and responsibilities, 1.c) „Every employee has the right to have and use "Stop Work Authority" whenever real or potentially unsafe conditions or unsafe actions are identified". Additionally, the messages about our Life Saving Rules clearly state, that „All MOL Group employees and contractors should adhere to the safety rules, intervene and stop work if there is a doubt about safety, so everybody can return home safely after our working day!" as well as the aim „…to ensure you a license to say 'NO'…" Although these messages are explicitly stated in connection with Life Saving Rules, they are valid at each and every safety relevant aspect.

- Maximum 2 working days after an incident occurred or in other, duly justified cases the initial consequence classification must be reviewed and modified via Enablon so that electronic notifications can be sent out, if necessary. An Investigation Team must be nominated within 2 working days following the occurrence of an incident by the responsible person. Depth of investigation, selection of investigation method or involvement of specialists/experts (e.g., authorized fire safety experts) must be determined based on severity or nature of the incident. Incident investigations need to be able to satisfy relevant statutory legal requirements and to be usable in relation to potential insurance claims or litigation. Investigation Reports must be finalized as soon as possible, but within a maximum of 60 calendar days (including validation(s) in Enablon) from the time of incident occurred.

Protection of employees from occupational health hazards

The protection of employees from occupational health hazards is assured by compliance with national laws and internal MOL Group regulations and practices (e.g. the abovementioned Group HSE MS process description), combined with continuous activity of high quality professional operating staff. MOL applies best practices in its local operations which are continuously improved. Extending the general occupational safety activity of safety professionals, occupational health and medical service providers:

- carry out the fit for duty medical examinations specified in legislation and initiates the additional necessary special examinations,
- cooperate in the investigation of occupational diseases, suspicions and increased exposure cases in accordance with the specific legislation, organize special investigations, and conduct statutory procedures,
- examine the health effects of work,
- provide personal protective equipment advice,
- provide information on the working conditions of employees,
- carry out periodic medical examinations for each occupational group,
- track the occupational health records of employees properly,
- take part in relevant workplace hygiene inspections,
- conduct examination of the conditions of employment of workers with disabilities,
- comply with all reporting obligations for occupational health,
- cooperate in defining and managing pandemic prevention and protection measures (in cooperation with further specific professional service providers),
- cooperate in workplace health promotion programs.

The obligation and details of management of the regular and ad-hoc medical check-up process is defined on the highest level in HSE MS, Appendix 6 B. I. 2.2. Fitness for duty.
The access of this health services even above the MOL Group requirements in vast majority of the countries is a strong legal obligation as well. The high quality of the services is ensured by very strong tendering in case of new contracts and continuous control and close professional cooperation (group and local levels) with all service providers for continuous improvement based on best industrial practices. Among the services providers there are subsidiaries of big and recognized international companies, big national and local service providers, specialized health services (e.g. Affidea, Medicover, Buda Health Center, ProCare etc.)

Worker training on occupational health and safety

MOL Group provides regular occupational health and safety trainings for employees and for workers who are not employees but whose work and/or workplace is controlled by the organization (contractors). This includes generic training as well as site-specific trainings or trainings on specific roles, work-related hazards, hazardous activities, or hazardous situations.

Recruitment, selection and placement processes are locally in place to ensure that personnel are qualified, competent and physically and mentally able to meet job requirements. Legally required HSE qualifications must be met for specific jobs. Employee and contractor/ supplier HSE and process safety competencies and training needs must be identified, documented and periodically reviewed. Training plans and calendars must be synchronized with HR for the best resource management. Written procedures must exist to govern HSE Competency Assessments and Training procedures at company level. It must contain the following:

- Content; length of the induction HSE Training and the way of examination,
- Requirements regarding the training of visitors, students and part time employees,
- Practical training requirements if applicable,
- Refreshing training requirements including frequency (yearly frequency is recommended) and topics: induction and practical training topics, new HSE requirements becoming effective since the last training, and lessons learned from incidents.

MOL Group companies continuously seek for real 21st century training method possibilities with the aim of higher training efficiency – please see recent developments in section 'Actions and resources related to occupational health & safety'.

Promotion of workers' health

Health risks are assessed and managed by prevention and protection, providing employees with information and educational initiatives. MOL Group's workplace health promotion programs serve as additional tools to increase the personal health awareness of our workforce not only at the workplace, but also in their private lives.

MOL Group conducted health management gap analysis at main operating companies in order to identify the critical gaps to our standards and required level of compliance and set appropriate actions to eliminate them in an acceptable period of time. We believe that by implementing the identified and approved development actions MOL Group definitely takes a step ahead towards providing healthy workplaces and appropriate health management, including emergency response for all employees. According to MOL Group health management principles we order in general annually or biannually health screenings, but at least once per 3 years to all of our employees based on a detailed screening protocol, depending on the nature of their work (in case of stricter local legal requirement we always comply with local rules as well).

Besides this, we conduct screenings for known health risks (such as diabetes, cholesterol, calculation of Body Mass Index (BMI), etc.) and we draw up an individual basic health plan for all of our employees. Individual health plans are a professional starting point, but we also offer special workplace health promotion programs to our employees, that include a variety of medical screenings in different countries/ areas, with different timing (e.g. cardiovascular package, cancer prevention package, musculo-skeletal package, vaccination programs), healthy lifestyle advice, dietary advice, stop smoking programs and a wide range of physical activity programs.

At the Family Days that are organized by the companies, the family members of our employees have the opportunity to participate in health screening for different health risks (diabetes, cholesterol, BMI, etc.) as well. Health promotion programs are organized locally in order to contribute to both the health and well-being of employees. Different regular individual or group sport activities are supported inside or outside of company facilities (e.g., own sport events, participation in national and/or regional sport events, hiking and health walk activities in groups by purchasing equipment, renting room, providing sport passes, paying participation fee, providing team T-shirts and/or refreshments, setting up a team tent, etc). For our colleagues travelling to and working in countries with a high risk or incidence of communicable diseases we conduct medical screening before travelling and after, and we supply the required vaccinations as well. MOL Group is providing 24/7 services for any potential medical evacuation (MEdEvac) needed around the globe for its expatriates and travellers, and in special situations the local employees of MOL operations if medically necessary, by contracting one of the leader service providers of the industry. Contractors of MOL Group are not covered by these initiatives.

Prevention and mitigation of occupational health and safety impacts directly linked by business relationships

Product stewardship within MOL Group and relevant member companies are assigned and responsibilities for individual Product stewardship process steps are defined. Product stewardship processes identify risks related to dangerous substances/products at an early stage and manage those risks along the value chain (i.e. development, authorization, registration and restriction on their manufacture, market distribution, use, disposal or recycle), thereby enabling adequate protection of human health and the environment, in line with the REACH legislation. New product assessments are conducted prior introduction to market in order to identify and address health, safety and environmental hazards and risk associated with their normal use and potential misuse. Periodic re-assessments must be conducted if product specification changes, including collection and review of adverse effects reported or experienced. Records of assessment and re-assessment are kept up to date. A product dossier must be established for all dangerous products bringing together all the information that the company holds on a product throughout the lifecycle. The OHS aspects are described in the element 6 of HSE MS, its details are available in the appendix 6B I. 2.1 Risk based approach and appendix 6B II. Safe operations and work practices.

Process Safety & Management

MOL Group operates a set complex of industrial assets were rigorous maintenance, timely asset replacement, and adherence to strict safety protocols must be in place to avoid the loss of mechanical integrity, technical, technological or operational issues, natural disasters or human errors. Such events can potentially lead to severe environmental damage (products spills or leakage of hazardous substances – IM-04), personal injuries (see IM-13, RK-04) – besides cost to replace damage assets and remediate environmental damage. Group-level Process Safety & Management principles are outlined in the PSM Process Description (currently only internally available):

- **Process Safety Management (PSM)** is disciplined framework for managing the integrity of hazardous operating systems and processes. It deals with the prevention and control of major events with the potential to release hazardous materials or energy. The PSM elements that group processes and practices designed to prevent LOPC and other types of asset integrity or process safety events via methodologically identify, understand and reduce risks associated with and mitigate any potential consequences of such events. PSM system elements support hardware and human barriers.

- PSM system, due to its cross-functional character is very complex, including research/development (R&D), engineering, construction, operation, maintenance, training and sourcing. The structure of this regulation is based on key elements defined by the so called "PSM Wheel".

- The scope of this process description is valid for those consolidated MOL Group companies which operate hazardous chemical or non-chemical operating systems and technological processes assessed based on risk assessment according to HSE MS.

- Business Unit leaders are accountable to implement the PSM system within their scope with the coordination of the local PSM leader and in cooperation with Group Process and Fire safety leader and Group PSM coordinator.

- Process safety indicators follow the API 754 standards or IOGP recommendations.

Process-based regulations on avoiding, controlling and limiting and environmental and health & safety related impact of incidents and emergency situations are outlined in the Element 6/A Operational safety; Element 10: Incident Management an in Element 11: Emergency Preparedness & Response sections of the HSE MS. These Group-level guidelines ensure the effective management and minimization of environmental and health and safety impacts from incidents and emergencies at all critical assets. Operational safety measures focus on maintaining asset integrity, implementing robust maintenance and inspection programs, and ensuring the proper functioning of safety-critical equipment, supported by trained and competent personnel. Incident management systems ensure all health, safety, and environmental incidents are thoroughly reported, investigated, and analysed to prevent recurrence, with lessons learned shared across the organization. Emergency preparedness and response plans are designed to protect people, the environment, and assets through comprehensive scenario planning, resource readiness, regular training, and drills, ensuring a rapid and effective response to any emergencies.

Worker security (IM-19; RK-09)

The **Security Area Book** is the highest level, process-based policy related to the Security services at MOL Group. It contains a comprehensive set of principles for security governance, security operations, technical security services, crisis & continuity management, travel security and anti-fraud & investigation related activities, thereby covering impacts and risks related to both physical security of workers (IM-20, RK-13) and to unfair business conduct and fraud (IM-10, RK-11). Group Security Director as process owner is responsible for the implementation, for identification of regulatory need and regulation issuance in cooperation with local responsibles. The provisions of this policy must be implemented at all MOL Group companies (i.e. MOL Plc. and controlled operative subsidiaries involved into matrix operation) and are obligatory and binding for affected employees. To ensure awareness, MOL Group has mandatory trainings covering all key areas, whilst relevant policies are available to all employees on MOL Group's E-REG system.

Through the comprehensive measures outlined in the Security Area Book, MOL Group effectively manages the potential threats posed by low-security and high-risk environments (IM-20, RK-13). Security considerations based on a risk-based management system that identifies and analyses security threats and vulnerabilities are integrated into all business and functional processes, ensuring proactive risk management from the planning phase through to operation and discontinuation. This approach is critical for mitigating physical security threats as it ensures operations in low-security areas are supported by site-specific security measures:

- **Security Operations Centre:** Security Operations Centre based security operational model across the group which allows centralised evaluation of relevant information and centrally directed/ supervised responses to incidents.
- **Localized Security Responses**: Acknowledging the varying security risk environments in the countries where MOL operates, the Security Area Book mandates localised, tailored responses to protect people, assets, operations, and reputation, by addressing threats such as criminality, terrorism, and social unrest by deploying context-appropriate countermeasures.
- High risk countries have a VUCA (Volatility, Uncertainty, Complexity, and Ambiguity) environment. Therefore, in these countries the applied security measures, including physical, technical and personal protection and security must be robust, modular, quickly reactive and at all times responsive and adequate to the actual security threat level and types. The MOL Group's Physical Security Risk Management framework defines standardized solutions to deliberate security threats:
- Before entering new countries or starting new projects, MOL Group conducts security planning to address potential threats.
- Compliance with international security standards including SOLAS Convention (standards for the construction, equipment and operation of ships),and ISPS Code (comprehensive set of measures to enhance the security of ships and port facilities, developed in response to the perceived threats) for offshore operations
- Collaboration with government agencies, law enforcement, commercial security providers, and industry peers to stay informed on evolving threats and best practices.
- Protecting expatriates and their families is a top priority in high-risk areas. Security shall provide professional deployment and security brief for expats and provide professional hostile environment awareness training. Local security department must have local regulations covering at least the following standard operating procedures:
    - Implementation of B6 vehicles
    - Convoy movement
    - Close/ personal protection
    - Body guard(s) for expat managers
    - Guarding of expat's residences
    - Security House Rules for offices, facilities, sites
- When third-party security services are used, MOL Group ensures rigorous oversight through regular audits and performance evaluations, site-specific instructions for security guards and legal compliance in search procedures and contraband management.

ENGAGEMENT RELATED TO HEALTH, SAFETY AND SECURITY OF WORKERS

/S1-2/

MOL Group's internal communication with the workers is assured by compliance with national laws and internal MOL Group regulations and practices. "Works councils" are present across MOL Group operations and provide a constant professional communication and interest protection channel within MOL Group between management and – independently elected – MOL employees. Establishing "Works councils" is a legal requirement in many countries of MOL Group operations. The right and at the same time task of the works councils is to participate in and even challenge – besides other aspects – the health and safety relevant decisions of the employer, and the basis of its operation is the cooperation of employers and employees.

The local "Works councils" are operating and having regular joint management-worker meetings, joint meeting with occupational safety committees and forums at different Business/Company levels within the organization (usually on a quarterly basis) based on the local law and operational descriptions that describe the dispute resolution mechanism, the chairing responsibilities, and how the committee members are protected against reprisals.

The policy ensures that employees and their representatives may not be subject to adverse consequences for acting in order to implement the requirements of safe work, or for reporting in good faith due to the employer's perceived negligence. The law allows employees to exercise their right to participate in several ways, depending on the number of employees and the structure of the employer organization.

Special, OHS dedicated local (local business and/ or Company level) occupational safety committees also are operated, based on legal requirements and agreements between employer and employees, with independently elected membership from the companies' employees.
For example, an election of safety representative must be held at all employers where the number of employees reaches 20 (in MOL and INA) or 10 (in Slovnaft) people. It is the employer's responsibility to conduct the election and ensure the conditions. The safety representative is entitled to make sure that the requirements for safe work are enforced in the workplace, so in particular:

- about the safe condition of workplaces, work tools and personal protective equipment,
- on the implementation of measures to protect health and prevent work accidents and occupational diseases,
- on the preparation and preparedness of employees for safe work.

For exercising their rights, safety representatives are allowed to:

- enter workplaces in their operational area during working hours and get information from the employees working there
- participate in the preparation of the employer's decisions that may affect the health and safety of employees,
- request information from the employer on all issues affecting safe work,
- express an opinion or initiate the necessary measures to be taken by the employer,
- participate in the investigation of work accidents,
- turn to the occupational health and safety authority with jurisdiction (in justified cases),
- communicate their comments during official inspections to the person performing the inspection.

According to local legal background – e.g. in Hungary if the number of safety representatives reaches three –, a workplace occupational safety committee can be established. If a committee is established, the rights of the safety representatives will be exercised by the committee. Where safety representatives operate, the employer establishes a parity safety board, in which equal numbers of employees and employer representatives participate. The employer is obliged to appoint a senior employee entitled to make a decision to the board, as well as a person who partially or fully performs the employer's occupational health and safety duties. The duties of the chairman of the board are exercised alternately by the representatives of the employees and the employers.

Furthermore, besides the above-mentioned health and safety relevant professional employee involvement-communication-information channels(s) various other employee interest-protection, information and consultation committees, councils, bodies exist, on local or country levels within our operations, according to relevant legal background, which within their overall employee representation also could manage the health and safety relevant topics in cooperation with the above-mentioned ones. MOL Group's local councils have delegation in the various trade unions, local works councils; whilst on the Group-level the European Works Council consist of the leaders of local councils, having a MOL Group European level series of meetings half-yearly, with presence and active participation of MOL Group top executive management. At these meetings all relevant business and HSE aspects are discussed at the highest level, consisting of last half year actualities, present status and the roadmap of the next period.

The councils, safety committees then cascade down all the relevant information on all their local levels. All these bodies – trade unions (where people in the workforce are unionised), works councils, safety committees etc., on their relevant level – operate various channels for raising concerns or needs include grievance mechanisms, hotlines, dialogue processes or other means through which the undertaking's own workforce or workers' representatives can raise concerns about impacts or explain needs that they would like the undertaking to address (both channels provided by the undertaking directly and channels provided by the entities where their own workforce is working). The operation (general operational rules, election structure, cooperation, frames of financial and human resources, etc.) of all these bodies is supported by the relevant HR departments.

Besides the abovementioned system of works councils and occupational safety committees, all workers are entitled to express their opinions, raise concerns or report any issues (including health and safety) via the Group-level whistle-blower mechanism, SpeakUp!. For more information, please refer to section 'S1-3-C: Policies related to grievances and remediation'.

ACTIONS AND RESOURCES RELATED TO OCCUPATIONAL HEALTH & SAFETY

/S1-4/

ESRS	Disclosure Requirement S1-4
GRI	GRI 3, 3-3 GRI 403, 403-9

	GRI 403, 403-10

Actions on occupation health & safety (IM-13)

The most common root for most of all cases were determined to be lack of attention/care, sometimes improper technical conditions were identified too, and rule violations were still found in some cases as well. After a multi-year smooth implementation of the six Group-level Life Saving Rules introduced on 1 January 2020, we improved and unified the consequence management of any rule breaches at the end of the year – not concentrating only but highly focusing on these incompliances. However, the continuous enforcement of these LSRs is still needed, especially at the periodically fluctuating contractor teams with the unchanged aim of increasing individual awareness and promoting ownership of critical safeguarding measures to prevent injuries and fatalities.

MOL Group continued to provide Occupational Health & Safety (OHS) trainings for own staff and contractors in compliance with external rules and internal regulations. For own staff's continuous HSE education we continued to extend the Axonify, adaptive mobile application-based tool, called LEON, which after its successful introduction in MOL Upstream, also was successfully introduced in MOL Logistics, and it was extended to almost all Business Units in MOL Hungary in 2024. Further goal is to further extend it to other big operations as INA and Slovnaft (SN) where different sized pilots are being conducted. To support this, a Group DS management level pilot continued besides the 6 Life Saving Rules with Firs Aid training, Fire protection, Process Safety sessions, and pilots also continued in INA and SN as well.

In 2024 we approached the management with a new experimental training session, so-called "Consequences training" – making them more demonstrative the possible effects on the staff of their decisions. These half-day trainings or workshops held for 10-15 managers (at any levels, supposed to cover the full management team of a group or local level organization) are organized at the physical training and drill facility of FER Fire Brigade in Duna Refinery, and contain different physical scenes, exercises from the operational and maintenance blue-collar life, which can put the participating managers in heavy, uncomfortable physical situations in a safe environment, making them feeling-touching-understanding the possible consequences for the staff of their possible not HSE-conscious decisions. Already teams of Group Downstream, Logistics, Investment, Industrial & Corporate Services Management and also HR areas participated on these events with really positive feedback.

MOL Group's 'Safety First' approach still targets ensuring safe workplaces and activities, following all internal and external H&S rules, whilst maintaining continuous OHS professional support across all operations. As already reported, in 2021 two major new Group-level OHS initiatives were the launch of Personal Protective Clothing (PPC) and Personal Protective Equipment (PPE) harmonization tenders: after closing successfully the PPE tender in 2022 with conclusion of new contracts, finally at the end of 2023 we closed successfully the PPC tender as well, in order to ensure world-class, high quality protective garments for our whole staff. First deliveries started in Q2 2024 and are being continuous with the agreed quarterly scheduling for our operations in Slovakia and Hungary. Since the overall satisfaction with the new protective garments is high, the smaller subsidiaries e.g., in Romania, Serbia, Austria, etc. are being negotiating the joining to the service through accession contracts as well. In Croatia a separate contract was also concluded with the same technical content negotiated and finalized in the Group tender.

Besides the above-mentioned, mainly fully Group-level safety initiatives and actions, many Group Business- or Local Business level further programs were initiated and managed to increase the safety awareness and safety performance of the given area, considering the covered areas' specialities and most relevant risks. Let's have some examples without claim to be exhaustive:

Deep discussion and understanding of incidents, their background and improvement possibilities on managerial level through dedicated Incident Review Committees in Group Upstream and Group Logistics and Group Production in Downstream, similar event-management in Retail and Lubricant companies as well; Besides quarterly Group level HSE Committees, similar ones organized on lover levels in Group Upstream, Group, MOL and INA Logistics level and Lubricants; Unsafe/ unconscious behaviour concept emphasized in MOL Upstream, Group Production, Logistics and Lubricants; Different local bonus-malus systems launched on almost all areas for own and contractor employees, evaluating their everyday approach to safety aspects and rules; Group Retail level Retail HSE Competition for recognizing the HSE-conscious SeS network operation; Further local special, occasional trainings, action and/ or communication campaigns involving all levels from shop-floor to managers; and many others.

To improve the in-person contractor HSE trainings as well, INA Production continuously operates its demonstrational Training Center in Rijeka Refinery from the end of 2022, and Slovnaft Refinery also was using the already existing Training Center – used earlier only for own staff – for contractors' work supervisors, before every bigger maintenance activities, Turnarounds. In Duna Refinery, Hungary the FER Fire Brigade's Training Center was also used for practical training for contractors' work leaders, based on a previously developed training concept, covering safety aspects of work-permit system, working at heights, fire extinguishing, emergency response, and flange dismantling.

MOL Group continued to strengthen its overall Contractor-HSE program in order to improve the performance. The contractor HSE qualification and audit process, which was released in 2023 is being further improved, with the aim of covering similarly to our direct contractors the sub-contractor layer as well, keeping the focus on registration, screening, qualification and procurement procedures of suppliers in a more systematic, transparent and comprehensive manner. The OHS's focus on the Contractor Safety program in 2024 was on

the proper contractor selection, enabling proper preparation according to the existing circumstances, before contractors' mobilization onto their worksites. During the year we decided to further improve our service procurement processes and supporting system (called SAP Ariba) for which we established a project team and assessed the needed improvements. The proposal was accepted by Steering Committee in December 2024, the realization is due in Q2 2025.

Additionally, the Injury Prevention Action Plan elaborated and implemented in 2023 in Group Industrial and Corporate Services (including all our Single Service Companies), covering more typical areas of Contractor Management and contracted onsite works' lifecycle, aiming the reduction of risks and injury occurrence, was considered successful, thus we applied it for 2024 too, and we aim to continue with that as a kind of a rolling action plan for the next years as well.

In line with the increased contractors' worked hours (by more than 11% in 2024) we performed an increased amount of site inspections as well in 2024 (30,012) in comparison we did in 2023 (28,183) In order to cover as many contractor activities as possible. However, we realised that the high inspection numbers do not necessarily deliver better safety performance, so we intend to rather focus on depths and professional quality of these. A new methodology was introduced in the beginning of last year to record inspections in Enablon (Enablon Inspection Module), for better data analysis and improving action definition, which also was slightly restraining the further increase of the number of inspections performed. The quality of these was slightly increasing, shown by the increasing percentage of site inspections with non-compliances from 15% in 2023 to 18% in 2024.

In 2023 we heavily increased the number of pre-qualification audits compared to previous years, which resulted a higher coverage of audited contractors. Since we are facing a continuous change in the contractors' pool, in addition, the validity period of previous audits has expired in 2024, the number of pre-qualification audits in this year significantly increased to 363 (it was 255, in 2023). The quality and depth of these was also reinforced, however the ratio of successful pre-qualification contractor audits did not changed significantly93% in 2023 to 96% in 2024. Reflecting the decreased tolerance against any unsafe conditions, acts or safety rule violations, we continued to apply different penalties in case of different rule violations, but as mentioned above, on a Group-level unified and intentionally more deterrent way as well, like banning workers from the different sites (80 cases in 2024, 63% increase compared to 2023), or initiating written warnings as well (747 cases in 2024, 71% increase compared to 2023). Both are reflecting the more consequent and stricter application of our consequence management initiatives.

In 2024, the company allocated a total of USD 19.9 million to Occupational Health & Safety activities (excluding REACH-related expenses, which are reported separately), representing a 3.5% increase compared to USD 19.2 million in 2023.

Spending on **health protection** included the provision and maintenance of essential health protection equipment and assets (such as first aid kits and medical equipment), the cost of the health care services at all kinds, health-related trainings (e.g. first aid provider courses, health campaigns, etc.). Additional cost incurred on addressing working environment measurements – covering illumination, harmful substances, dust, and noise.

Expenditures related to **work safety**, include costs of personal protective equipment (PPE, any kinds, including their cleaning and maintenance as well). The company also allocated resources to campaigns, safety billboards, and safety-related training programs, including workplace risk assessments and road safety studies, enhancing the Occupational Health and Safety Assessment Series (OHSAS) system, and developing contingency plans, services of safety coordinators, permit-to-work system management, and analytical measurements of workplace conditions.

Actions on process safety (RK-04)

In 2024 constant targeted safety programs aimed both the workplace and process safety. The perpetual "Together in safety" program in Upstream still has run and " Safety Matters" was introduced in the Downstream as a joint campaign for the Logistics and Production. Both of them targets mainly the safety culture and the awareness which is inevitable for understanding the importance of being compliant with our safety rules and in case of DS campaign targeted 4 shared areas reflecting either on existing things like process safety fundamentals, health-check audits on performance, safety tours, but bringing new initiatives as well like the operating discipline and the roll-out of LEON mobile application.

Actions related to worker's security (IM-19, RK-09)

In 2024, two serious security incidents occurred within MOL Group, both at the VA-3 site of MOL Pakistan, where armed miscreants launched attacks from an adjacent mountainous area.

The first incident took place on 10 June 2024**.** At the time, 14 staff members and 17 Frontier Constabulary (FC) soldiers were present at the site. They successfully prevented the attackers from descending from the mountain, and no harm was inflicted on personnel.

The second incident occurred on 6 September 2024**.** Approximately 20-25 attackers, divided into three groups, launched an assault. Two groups remained stationed on the mountain, while a smaller group attempted to approach the facility. No MOL staff members were on-

site at the time. The 26 FC soldiers present repelled the attack after an hour-long exchange of gunfire. While no personnel were harmed, six bullet impacts were observed on the compressor, and the water tank sustained two bullet hits.

TARGETS RELATED TO HEALTH & SAFETY

/S1-5/

ESRS	Disclosure Requirement S1-5
GRI	GRI 3, 3-3

Targets on occupational health & safety

MOL Group's objective continues to be comparable with top Q1-Q2 Oil and Gas companies in terms of safety performance. This objective is tracked using metrics-based targets to support policy execution while addressing impacts and risks.

In alignment with international standards (facilitating comparisons both with industry peers and across other industries), the primary indicator for worker health and safety management at MOL Group is the Total Recordable Incident Rate (TRIR). This metric reflects the total number of recordable injuries (TRIs, consisting of lost time injuries + restricted workday cases + medical treatment cases) considering both MOL Group employees and contractors, per 1,000,000 worked hours by the same group. TRIR is constantly monitored and reported both towards the top management of the company, and to the public as well as part of the quarterly flash reports.

Each year, the Group HSE Committee proposes a tolerable TRIR limit at the Group level, as well as for key business divisions within the Group. This limit is subject to approval by the Chief Executive Committee. For 2024, the Group-level tolerable TRIR limit was set at 1.3, and the final rate shows a far better performance, with the actual TRIR value of 1.04 (see detailed explanations in Section S1-14: Health and Safety Metrics).

For 2025, considering the previous years' TRIR performance trends, also compared to our target-trend of last few years and considering the Global and European Upstream and Downstream players TRIR performances of last few years too, the Group-level TRIR target has been set to 1.25, underscoring our commitment to a smooth, reliable, continuous improvement in worker safety.

Targets on process safety

2030 APC target is to put the overall number of Process Safety Tier1 incidents on downward trendline. Annual breakdown for 2025 pointed a tolerable limit of 7 Tier1 incident MOL Group overall. In details, it consists: 3 for Upstream, 4 for Downstream Production, 0 for Downstream Logistics and 0 for Retail. Target setting also assigns a tolerable limit for over 1 m3 HC spillages into the environment. In this case we have numerical target for Downstream Production with a 4 maximum allowed incident and for Upstream and Downtream Logistics the continuation of surface integrity and corrosion management programs must be in place with a trackable record.

METRICS RELATED TO HEALTH AND SAFETY

/S1-14/

ESRS	Disclosure Requirement S1-14
GRI	GRI 403, 403-8 GRI 403, 403-9 GRI 403, 403-10

	UNIT OF MEASURE	2024	2023	ESRS
Employees covered by a health and safety management system	%	95	N/A	S1-14_02

95% of employees are covered by a Group-level Health and safety management system. It is calculated as the full number of employees (headcount), where a management system is in place. Detailed description about this policy is available in the Policies related to Health, Safety, and Security of Workers section.

	UNIT OF MEASURE	2024	2024 w/o Midstream	2023	ESRS
Fatalities as result of work-related injuries - own workforce (own staff + contractors)	number	0	0	9	S1-14_02
Fatalities as result of work-related ill health - own workforce (own staff + contractors)	number	0	0	0	S1-14_02
Recordable work-related accidents (TRI) - own workforce (own staff + contractors)	number	96	95	117	S1-14_04
Rate of recordable work-related accidents (TRIR) - own workforce (own staff + contractors)	per 1 mn worked hours	N/A	1.04	1.31	S1-14_05

MOL Group provides a comprehensive list of data around worker related injuries, covering both own staff and contractors. No workers have been excluded – this is ensured by the internally audited HSE MS of MOL Group covering own staff and 100% of all our on-site contractors. Besides, Contractors performing high HSE risk activities for MOL Group, are to be covered by a system that has been audited or certified by an external party (SCC/VCA). Absolute numbers of contractors is not published as it is highly variable based on the number and extent of given activities all over the Group. The calculation methodology is described in the HSE Reporting Handbook (full document is only internally available for MOL Group relevant users).

As highlighted above, MOL Group's objective continues to be comparable with top Q1-Q2 Oil and Gas companies in terms of safety performance. Transparency concerning worker related injuries is a high priority. MOL Group provides a comprehensive list of data around worker related injuries, covering all own workforce (own staff and contractors) as described above.

Rates have been calculated based 1 million working hours, as one of the two options being suggested by the GRI Standards.

FGSZ Zrt. (Midstream) recorded one work related incident in its own workforce, resulting in a TRIR of 0.88. Since information for recordable work related accidents of contractors is not available, full consolidation of the above metric is not possible.

Fatalities

In 2024 we could deliver our safety target not only in terms of TRIR but also from viewpoint of fatalities, targeting here zero, as the only acceptable level. All in all, no own employee fatality happened, which is an improvement compared to the previous years' trend (last own staff casualty was in 2022), and also contractor fatality we didn't have, in contradiction with the extremely sad previous year, when nine contractor fatalities occurred.

Although as said, the Group's 'Zero fatality' goal is being met, in addition, just as in the last year (1 in 2023), one third-party fatality in June was also considered work-related, being caused by non-preventable road accident in MOL Romania: around noon, a passenger car that was coming on the other side of the road suddenly has left its lane and collided frontally with our contractor's tank truck delivering fuel to a MOL Romania service station. The driver of the passenger car has passed away on the scene.

Personal safety

MOL Group experienced a 18.8% YoY decrease in Total Recordable Injuries (TRI) among own employees and contractors, reaching a combined 95 in 2024 (117 in 2023), resulting that MOL Group recorded a 20,6% decrease in the Total Recordable Injury Rate (TRIR, measured by number of TRI cases per one million worked hours) for own staff and contractors as well (reaching 1.04 in 2024, compared to 1.31 in 2023), also well below 1.3 tolerable limit set for the year.

The heavy decrease in number of TRIs despite the slightly increased worked hours (from 89,5 mn in 2023 to 91 mn in 2024) caused an even higher proportional decrease in value of TRIR, resulted by various different actions continued from previous years and newly initiated locally tailored ones by our Business Units and sites. These include different efforts to increase safety awareness, various Group-level and local actions initiated and implemented during the year, as well as the further increased attention to health and safety among staff. While the huge turnarounds and other maintenance- and operation-relevant, mainly manual activities still contributed significantly to the number of TRI events and consequently TRI rate as well (not only in case of contractors, but own staff as well).

During 2024 the number of Lost Time Injuries (LTI, including own staff and contractor fatalities) decreased by almost 17%, to 84 from 101 in 2023, which resulted in also a significant decrease (18,5%) in Lost Time Injury Frequency (LTIF, measured by number of LTI cases per one mn worked hours): to 0.92 during 2024 compared to the 1.13 LTIF recorded in 2023.

Overall, the top causes of the TRIs during 2024 were still slips, trips, falls (generally caused by human error and/or lack of attention), making up 39% of all injuries, followed by different finger and hand injuries (24%). However, for 2024 we analysed not only the background of TRI cases, but all our (own and contractor) FACs (first aid cases, less serious than TRIs, thus not recordable) as well: the Slip&trip injuries are the top causes there (25%), the hand injuries are on the second place (23%), while with relatively high number of insect bites are the third highest (13%) ones.

Work-related ill health

MOL Group registered one occupational illness for own staff employees during 2024.

- The number of fatalities as a result of work-related ill health: 0
- The number of cases of recordable work-related ill health: 1
- The cause of work-related ill health: tick bite

After long years without this kind of event, last year only one event was reported in MOL E&P, caused by tick bite in 2023. The case had along investigational and approval procedure according to Hungarian national legislation, and was finally confirmed by Authority as work-related ill health case only in 2024.

According our Group HSE Reporting Handbook, Occupational illnesses (work-related ill health cases) are to be internally recorded in Enablon in the year, when the Authority accepts it.

MOL Group does not record the possible occupational illnesses of contractors (workers who are not employees but provide contracted activities on MOL Group sites), since the management of this is employers' right and task by law.

In order to avoid all work-related ill health cases, irrespectively on their nature, MOL Group companies determine and evaluate all risks and hazards with potential effect on their employees' and contractors' health and safety, eliminating them through dedicated actions (refer to GRI 403-2 a.). Risk/hazard assessments are carried out locally, action planning (incl. using the hierarchy of controls) are also done locally for work-related hazards that pose a risk of ill health. Thanks to the conscious approach only the above mentioned one work-related ill health case occurred in the last over a decade. The overall professional approach is detailed in the element 6B of HSE MS, its details are available in the appendix 6B I. 2.1 Risk based approach and appendix 6B II. Safe operations and work practices. No own staff workers have been excluded.

Methodology for calculation is found in the Mol Group reporting handbook.

MOL Group does not disclose number of fatalities and recordable cases as a result of work-related ill-health, and also not the main types of work-related ill health cases, of other people than employees, since the management of this is employers' right and task by law.

Contractor safety

In 2024, no contractor fatalities occurred. Lost Time Injury Frequency for contractors (measured by the number of LTI cases per one mn worked hours) decreased by 41.3% YoY, from 0.67 in 2023 to 0.40 in 2024 (including not own FS staff; even higher decrease is visible excluding not own FS staff: from 0.97 in 2023 to 0.47 in 2024 however, the frequency is a bit higher in the second case mentioned indicator – this represents 51.6% YoY improvement). In addition, the Total Recordable Injury Rate for contractors (measured by number of TRI cases per one mn worked hours, including not own FS staff) decreased by 34% YoY, from 0.81 in 2023 to 0.54 in 2024.

Due to the increased amount of contracted works in 2024 (without considering the not own FS staff, contractor worked hours increased by approx. 2.9 mn hours, more than +10%), with the lower number of recordable injuries (21 TRIs in 2024 compared to 33 in 2023) resulted in a significantly lower Total Recordable Injury Rate, 0.71 in 2024 compared to 1.23 in 2023.

Process safety

Process Safety Events	UNIT OF MEASURE	2024 w/o Midstream	2023 w/o Midstream
TIER 1 Process Safety Events	cases	9	9
TIER 2 Process Safety Events	cases	21	18
TIER 3 Process Safety Events	cases	1436	1387
TIER 1+2 Process Safety Event Rate	cases/mn working h	0.42	

During 2024, the number of TIER 1 Process Safety Events (PSE) reached 9 across the Group, keeping a constant after 2023, driven by the extensive safety programs with the operational discipline in the focus, continuous progress of preventive maintenance and the technical shutdown, turn around and LTA/LTE regime.

There was no major fire or explosion, which can lead to the permanent outage of unit, in most cases the reason was loss of primary containment, resulted in personal injuries in 3 cases. Each and every Tier1 events happened in the area of MOL Plc. Four out the five Downstream Production cases were related to loss of equipment integrity during non-standard operation or to improper preparation of equipment for maintenance work resulting in material release and multiply personal injury. In each cases the disparity of PSF can be justified. Retail operations registered 1 TIER 1 event in 2024. Of the 9 TIER 1 events, 1 was Severity 3 (high), 4 were classified as Severity 2 (medium), 4 cases as Severity 1 (low). Group-level TIER 1 PSE target for 2024 was set to seven, and a target of zero greater than 100k $ direct loss as a result if fire/explosion and no terminal outage of operation as result of Tier1 has been set by 2025. The number of TIER 2 Process Safety Events slightly increased to 21 during 2024 compared to the 18 events registered in 2023. The result of leakages were material releases, fires and asset damages, mainly related to the breakage of mechanical integrity. In 2023 there was a further decrease in the combined number of TIER 1+2 incidents (27) compared to 2022 (31).

Combined TIER 1+2 Process Safety Event Rate (PSER) for 2024 reached 0.42. The TIER 3 (including Demand on Safety System) was further reported to identify corrective measures to barrier system, the challenges of the safeguards and serves as leading and lagging indicators in the same time. Furthermore, the small and low severity incidents resulting in loss of primary containment were requested to be analysed on casual factors.

SUB-CHAPTER C: ETHICS

IDENTIFIED IMPACT RELATED TO DIVERSITY AND INCLUSION

/S1. SBM-3/

ESRS	Disclosure Requirement related to ESRS 2 SBM-3
GRI	GRI 3, 3-3

Impact related to ethics described in Table IM-11 below:

Table IM-11: Corporate culture

Severity	Moderate positive impact
Scope	CEE
Likelihood	Actual impact
Description	MOL Group recognizes its responsibility to foster well-being, fair treatment, and a safe and inclusive work environment for all employees, promoting diversity, gender equality & equal pay, and measures to prevent violence and harassment. As a major employer in the Central and Eastern European region, particularly in Hungary, Croatia, and Slovakia, the company significantly influences the evolution of corporate culture and ethical employment practices within the regional job market, setting a standard for responsible employment that extends beyond its own workforce.
Mitigation actions & remediability	MOL Group has established targets, policies, and actions aimed at securing physically and mentally healthy working conditions and ensuring fair treatment and opportunities for all employees, with special focus on vulnerable groups. To support our commitments, we have implemented a whistle-blower system called *Speak Up!* and an ethics council dedicated to identifying and addressing negative impacts on employees (see DR S1-2). Additionally, we collaborate with trade unions to guarantee representation and equal opportunities for all our workers. For details on policies, processes and key actions see DR S1-1, S1-2, S1-3, S1-4.
Time horizons	We consider the topic material on all time horizons.
Relevance in the value chain	Corporate culture is material impact across all levels of MOL Group's value chain.

POLICIES, ENGAGEMENT AND GRIEVANCES RELATED TO DIVERSITY AND INCLUSION

/S1-1; S1-2; S1-3/

ESRS	Disclosure Requirement S1-1, S1-3
GRI	GRI 2, 2-23 GRI 2, 2-25 GRI 2, 2-26 GRI 2, 2-29 GRI 3, 3-3 GRI 403-1 GRI 403-3 GRI 404-2 GRI 408-1 GRI 409-1

This section outlines MOL Group's policies and processes aimed at ensuring a fair, ethical, inclusive work environment and mechanism in place to ensure grievances related to ethical matters.

Commitments related to ethical operations are laid down in the **Code of Ethics and Business Conduct.** It covers all topics related to the responsible management of the company. Principles related to the civil, political, economic, social and cultural rights of workers in MOL Group's own workforce and people in its value chains are elaborated in this section (based on IV.2 of the Code); whilst Section G1-1 in Chapter Governance explains the company's approach towards *Free and Fair Trade and Competition* (IV.3), *Anti-Corruption and Anti-Fraud* (IV.4), *Corporate Loyalty* (IV.5) and *Trustful Business Relations & Responsible Stakeholder Relations* (IV.6).

All Board members, executive officers and employees of MOL Group member companies must act in compliance with the policy commitments, which are approved on the highest management level. MOL Group makes conscious and continuous efforts to implement the Code and to ensure that ethical norms are adopted. All newcomers receive the Code of Ethics and Business Conduct prior to their first workday and get an onboarding Ethics training (e-learning or personal training), where they must pass a test. Annually all employees must pass the Code of Ethics test via e-learning or classroom training.

MOL Group respects the fundamental human rights as our Group Code of Ethics and Business Conduct stipulates. MOL Group respects the Universal Declaration of Human Rights which summarizes fundamental human rights in 30 articles (United Nations General Assembly 1948) and further guidance documents on human rights such as the UN Global Compact (2000), the UN Guiding Principles ('Ruggie Framework') (2011), the OECD Guidelines for Multinational Enterprises (2011) and voluntary principles about security and human rights – full list of relevant external guidelines are listed in the Appendix of the Code of Ethics and Business Conduct. MOL Group considers these codes of conduct to be compulsory guidelines, therefore the MOL Group Code of Ethics and Business Conduct is harmonized with the declarations of the above-mentioned agreements.

MOL Group's management is committed to high level social dialogue and partners with trade unions and works councils active at members companies employing the majority of the Group's employees. For further details, please refer to section on policies, engagement and grievances related to own workforce in Chapter S1-A.

IV.2 of the Code declares commitments human rights and worker's rights including but not limited to:

- Right to Human Dignity;
- Right to Life;
- Liberty and Security of the Person;
- Right to the Highest Attainable Standard of Health;
- Right to Just and Favourable Conditions of Work;
- Rights to Fair Wages and a Decent Living;
- Right to an Adequate Standard of Living;
- Right to Form and Join a Trade Union and Right to Collective Bargaining;
- Freedom from all forms of Forced or Compulsory Labour;
- Freedom from Child Labour;
- Freedom from Discrimination;
- Freedom of Opinion

These rights are ensured via processes and regulations in 6 key focus areas (with further details available in the documents mentioned above):

Workers' and human rights
We respect and actively promote human rights across our value chain, ensuring compliance with corporate policies, laws, and regulations while engaging stakeholders and contributing to community well-being. We oppose human rights abuses and assess the impact of our actions to safeguard these rights. Our focus includes workers, suppliers, local communities, and vulnerable groups such as women, minorities, children, persons with disabilities, indigenous people, and migrant workers and their families. We protect tribal populations and indigenous peoples, avoiding forced relocations, and prioritize human rights compliance among security service providers acting on our behalf.

Health, safety, environment (HSE) and security
As a major energy company, MOL Group recognizes the high safety risks and their potential impact on the environment. We are committed to managing risks responsibly, respecting human rights, avoiding harm to people and the environment, and reducing HSE risks from our activities. We strive to ensure safe working conditions, improve environmental management, and foster an active HSE culture through reliable equipment, skilled personnel, and sound practices. Additionally, we prioritize the security of individuals on our premises and the protection of MOL Group assets, including employees, technologies, physical resources, information, and reputation against security threats. Please find detailed disclosures related to worker health, safety & security in subchapter S1-B.

Equal treatment and opportunities
We at MOL Group are committed to combatting discrimination in all areas of the workplace, throughout our supply chain and in society as a whole. MOL Group understands the value of diversity. Our employees, customers, business partners, suppliers and other external stakeholders are citizens of many different countries with many different nationalities, faiths, religions, beliefs, culture or social origins. We support cultural diversity, the creation of an international team and business community. MOL Group is committed to prohibiting and preventing discrimination of any kind, such as but not limited to discrimination based on race, colour, gender, age, language, religion, political or other opinion, ethnic or national or social origin, property, birth, sexual orientation or any other status including matrimonial or parental status, and to providing equal opportunities to everyone, based on merit, except when particular professional ability can justify selection. Unlawful discrimination is not tolerated, and our publicly available diversity and inclusion programs reflect this commitment.

Dignity and mutual respect
MOL Group is committed to fostering a work environment built on mutual trust, where everyone is treated with dignity and respect. We maintain a fiduciary relationship with our stakeholders and expect the same in return. Harassment, intimidation, or any behaviour that is degrading, offensive, or hostile is not tolerated. Sexual harassment, defamation, and slander are serious violations of human dignity. Everyone within MOL Group, our supply chain, and our communities deserves courtesy and respect.

Protection of privacy
MOL Group is committed to respecting people's privacy and keeping their personal information confidential. We will only acquire and keep personal information that we need in order to operate our company effectively, which is in compliance with the law. MOL Group undertakes to adopt preventive security measures for storing personal data on databases, in order to avoid any risk of destruction and loss or unauthorised access. Details and policies related to information and cyber security can be found in subchapter G1-C.

Fair labour practices
At MOL Group, employees are our most valuable resource. We prioritize their development, work-life balance, and adherence to lawful and fair employment practices. Forced labour, child labour, and unethical practices such as wage withholding or denying rights like sick leave are strictly prohibited across our operations and supply chains. We uphold a minimum working age of 15 for non-hazardous and 18 for hazardous work unless local laws specify higher limits. MOL Group ensures fair employment, supports employees with special needs, and handles disciplinary actions and redundancies with fairness and transparency. We also respect freedom of association, union membership, and collective bargaining rights. For further details, please refer to 'Policies & engagement related to own workforce' section in subchapter S1-A.

Enforcing these principles are operationalised into MOL Group's internal regulations. Highest level of process-based regulations are the **Human Resources Area Book** and the **Diversity & Inclusion Process Description**. Provisions of this Regulations are obligatory and binding for affected employees and cascaded to all companies across the Group (MOL Plc. and controlled, operative subsidiaries involved in matrix operation) via with local HR departments responsible for local action planning in line with Group pillars. Their key objective is to foster an inclusive workplace that promotes diversity, equality, and respect across the all operations by establishing and regularly updating MOL Group's Diversity & Inclusion Framework. The framework serves as the foundation for all human resource processes, focusing on key areas such as well-being, work-life balance, gender equality, age diversity, and inclusion of employees from diverse parental statuses, physical abilities, and ethnic backgrounds. The framework is endorsed by the Management Committee and the Chief Executive Committee of MOL Group.

MOL Group unequivocally prohibits discrimination of any kind, including but not limited to discrimination based on gender, nationality, race, religion, age, or any other status, in compliance with local and national legislation across all jurisdictions where it operates. MOL Group's recruitment and selection processes are designed to ensure equal opportunities for all candidates, with a focus on competency-based methodologies and cultural fit. All roles are open to qualified individuals without discrimination, and any restrictions are based solely on legal or educational requirements. New employees are introduced to the company's practices, procedures, and values to foster alignment with its inclusive culture. Managers and employees are held accountable for championing D&I principles in their daily operations, and specific attention is given to creating an environment that welcomes diverse perspectives, values employee feedback, and encourages open dialogue.

MOL Group ensures that all employees feel recognized and valued through robust employee recognition programs and inclusive workplace initiatives. Annual evaluations of D&I actions are conducted by the Group Culture & Employee Experience team, with findings reported to the Sustainable Development Committee of the Supervisory Board. Feedback is actively integrated into action planning and framework updates, ensuring continuous improvement.

Besides applying these standards into our own operations, MOL Group actively conveys its core values to partners and expects them to uphold ethical business principles. The **Business Partner Code of Ethics**, a binding appendix to all contracts, applies to all MOL Group business partners, including suppliers, contractors, service providers, and advisors. It is publicly available on the MOL Group website.

As a mid-sized oil and gas company operating primarily in Central Europe, MOL Group faces relatively minor exposure to human rights risks in its value chains, with no identified violations to date. However, MOL Group remains committed to respecting fundamental human rights, as outlined in the **Code of Ethics and Business Conduct**, and ensures these principles extend throughout its supply chain. Particular attention is given to workers, suppliers, local communities, and vulnerable groups, including women, minorities, children, persons with disabilities, and migrant workers:

- **Prevention of Child and Forced Labor:** MOL Group strictly prohibits child, forced, bonded, or unethical labour practices. Business partners are required to adhere to these standards and inform MOL Group of any breaches while implementing corrective actions. MOL Group reserves the right to audit and terminate partnerships for non-compliance, conducting self-assessments, certifications, and on-site audits to verify adherence to ethical standards.
- **Training and Audits for Security Personnel:** MOL Group ensures that where it employs security forces (currently in Russia and Pakistan), are trained in human rights policies and procedures. To monitor compliance, MOL Group performs multi-tiered evaluations ensure transparency and accountability in security operations, reducing the risk of human rights violations. Security service providers are required to conduct daily and monthly self-evaluations for all security guards on duty. Using a standardized Daily-Monthly Evaluation Sheet, they assess the performance of each guard based on predetermined criteria and a three-tier rating system. These evaluations are then submitted to the MOL Group Regional Security Manager for review. Beyond self-evaluations, MOL Group's Regional Security Leaders conduct independent monthly audits to assess the overall performance of security forces. These audits include a Monthly Fluctuation Report that tracks personnel changes and performance trends.

Additionally, Regional Security Leaders prepare a Summarized Evaluation Report for submission to the Country Manager, offering a comprehensive review of security operations and highlighting any concerns or required corrective actions.

- **Rights of Indigenous Peoples:** Neither MOL Group CEE operations, nor its International Upstream operations located adjacent to indigenous peoples' communities. Nevertheless, MOL Group committed to protecting indigenous peoples' rights (based on the UN definition) under its Code of Ethics and Business Conduct. MOL Group's HSE MS requires assessing and mitigating potential social impacts, including protecting the health, safety, and living conditions of local communities; securing prior consent where necessary and avoiding involuntary resettlement; and preserving cultural heritage and traditional landscapes. More details on policies and actions related to local communities can be found in subchapter S3-A – Affected communities.

POLICIES RELATED TO GRIEVANCES AND REMEDIATION

/S1-3/

Whistleblower Mechanism

MOL Group is committed to maintaining the highest ethical standards across its operations. To support the enforcement of its principles and processes, the Group operates the SpeakUp! whistleblower mechanism, a secure and accessible platform for raising concerns, reporting violations, and seeking advice. Reports made through SpeakUp! are treated confidentially and can be submitted anonymously without fear of reprisal.

The SpeakUp! mechanism serves as a critical tool for fostering a culture of integrity, safeguarding the reputation of MOL Group and its business partners, and protecting the well-being of employees and communities. This platform is available to:

- Employees of MOL Group.
- Individuals in contractual relationships with MOL Group companies.
- Any external stakeholder with a reasonable and legitimate interest in reporting or addressing unethical conduct.

Violations of the Code may involve MOL Group member organizations, service stations, suppliers, distributors, contractual partners, sponsored or supported partners, or joint ventures. SpeakUp! is prominently accessible via MOL Group's website and referenced in contracts and codes. By enabling stakeholders to report concerns, SpeakUp! helps detect misconduct, legal violations, and other risks.

Reporting and Investigation Process

MOL Group emphasizes the shared responsibility to uphold its values and considers the failure to report unethical behaviour a potential breach of ethical standards. Misconduct or legal violations can lead to disciplinary action, including termination of contractual relationships. Retaliation against individuals who report concerns in good faith is strictly prohibited, and allegations of retaliation are subject to investigation by the Ethics Council. Annual ethics trainings are the primary means to increase awareness and keep trust in MOL Group's SpeakUp! system.

The investigation process adheres to the Ethics Council Rules of Procedure, an appendix to the Code of Ethics, and follows these steps:

1. **Receiving Reports:** Capture grievances and reports.
2. **Acknowledging Cases:** Confirm receipt and inform stakeholders of the process.
3. **Assessing Issues:** Evaluate the nature and scope of the reported concern.
4. **Assigning Responsibility:** Delegate cases to the appropriate organizational unit.
5. **Investigating Cases:** Conduct thorough inquiries based on established protocols.
6. **Approving Reports:** Finalize investigation findings.
7. **Issuing Resolutions:** Deliver Ethics Council decisions if ethical aspects are identified.
8. **Communicating Outcomes:** Share findings and recommendations with stakeholders.
9. **Monitoring Implementation:** Ensure corrective measures are applied.
10. **Reporting and Sharing Learnings:** Publish anonymized case studies to prevent recurrence.

Role of the Ethics Council

The Ethics Council is responsible for overseeing the SpeakUp! mechanism and ensuring its proper functioning. Its primary objectives include upholding MOL Group's ethical standards, addressing individual complaints, conducting ethics training, and supporting structured ethics improvement initiatives. The Council's functions include:

- Regularly reporting to the MOL Board of Directors, Chairman-CEO, and Supervisory Board on ethics-related issues.
- Reviewing completed investigations and findings.
- Monitoring ethics risks and implementing improvements.
- Overseeing key processes such as mergers and acquisitions (M&A), trading, and procurement through know-your-customer (KYC) and due diligence procedures.

The Council operates under the Ethics Council Rules of Procedure and is supported by:

- **The Preparatory Committee:** Conducts preliminary assessments and decisions.
- **Group and Local Ethics Officers:** Manage operational tasks such as investigations, grievance handling, and consequence management.
- **Country Chairpersons and CEOs:** Submit annual ethics-related reports to strengthen ethical foundations.

The Chairperson of the Ethics Council is an independent party, ensuring impartiality and fairness in all proceedings. Ethics Officers, appointed by CEOs of MOL Group companies with more than 20 employees, provide localized support and ensure the consistent application of ethical standards across the Group.

Legal and Organizational Framework

Established in 2006, the SpeakUp! mechanism operates under Hungary's whistleblower protection legislation. Ethics risks are continuously monitored and integrated into MOL Group's operations through:

- **Internal Regulations:** Updates to policies and procedures based on assessed risks.
- **Compliance Measures:** Ensuring adherence to both legal obligations and MOL Group's ethical norms.
- **Ethics Risk Assessments:** Embedded in M&A, trading, procurement, and other key processes.

By maintaining this framework, MOL Group reaffirms its commitment to integrity, compliance, and the well-being of its stakeholders.

ACTIONS RELATED TO DIVERSITY AND INCLUSION

/S1-4/

ESRS	Disclosure Requirement S1-4
GRI	GRI 3, 3-3 GRI 2, 2-24 GRI 203, 203-2

At MOL Group, multiple internal functions play crucial roles in managing impacts on the workforce, ensuring risks are addressed effectively, and promoting positive outcomes. The HR function takes the lead in managing impacts and risks related to human resources. This includes overseeing the implementation of Diversity & Inclusion policies, ensuring compliance with labour standards, and fostering an inclusive and supportive workplace environment. HR also supports the alignment of employee practices with MOL Group's values and strategic objectives. The Ethics function has a reactive role in addressing grievances and providing remediation. It is responsible for investigating incidents and ensuring fair resolution of complaints.

Actions to promote diversity and inclusion

MOL Group has taken targeted action to promote employee well-being and the development of corporate culture in line with the 4 strategic pillars of MOL Group's Diversity & Inclusion (D&I) framework are Multi-Generational collaboration, Female empowerment, Working Capacity and Wellbeing. (IM-11)

Several D&I events on Group level and in core countries were organized to introduce each focus area and show Group's commitments within each pillar (Multi-Generational collaboration, Female empowerment, Working Capacity and Wellbeing). During these occasions, external speakers, academia representatives as well as mental health professionals gave lectures or individual consultations and workshops raising awareness of enhanced collaboration across generations, supporting parents and female talent, the benefits of employing colleagues with disabilities and nurturing mental health in the organization. Across the Group, 26 actions were registered, with Wellbeing and multi-generational collaboration representing the majority of commitments, followed by women empowerment and disability. More concretely, family friendly programs, knowledge-sharing, mental health activities and creating an inclusive workplace were the most typical focus areas across the Group. Unconscious bias training has been embedded in the First Time Manager leadership development program, and on Group level 100+ leaders participated to create better inclusion in the organization. In INA specifically, White Cane Awareness Day Event, Dads at INA Campaign, to enhance workplace inclusion. At the end of 2023, INA was recognized as one of the first INC.Q Equal Pay certified companies, which is awarded to companies with less than 5% differences in salaries and financial awards between genders. INA continues being recognized by independent auditors (MAMFORCE® / DADFORCE®) whose evaluation of family-friendly and gender-non-biased policies implementation has shown INA being 19% over the market benchmark. INA also became one of the first companies to receive INC.Q best employer awards, winning in three categories: Best large company for women, Best energy company for wellbeing, Best energy company for Diversity, Equity and Inclusion. For the first time ever in INA there was a special event focusing on young women in business, with lecture and talk with Senior leader who is a woman. INA Group also continues its efforts to support students with disabilities with participation in "Experience is worths its weight in gold project" providing internship opportunities for students with disabilities. As of 2024, quarterly DEI trainings have been implemented, providing all employees with

possibility to get familiar with the topic and how important it is within the Group. Slovnaft has also continued its cooperation with Diversity Charter in Slovakia, as an ambassador of the organization. Following the MOL Group D&I Framework, more than 15 different projects and activities were started in 2024 to enhance the awareness of our colleagues about relevant topics, including female colleagues and their career journey, overall wellbeing, mental health, multigenerational collaboration and cooperation of Slovnaft with retired colleagues. MOL Hungary has strengthened its family-friendly initiatives by introducing a DayCare program for school holidays and School Starting Packages for parents of elementary school children. These efforts have earned recognition, including the Family-Friendly Company title, the BeneFit Prize, and Employer Branding Awards.

The Diversity & Inclusion Ambition Gender Chapter commitments continued with voluntary recruitment targets and principles in terms of gender diversity to ensure MOL Group is the future choice of female candidates. During 2024, 31.8% of all hires were female, a higher percentage than the female representation at the Group, supporting the direction towards better gender balance. The percentage of women of all management positions increased to 28.2%. To achieve the targets and to regularly measure gender diversity, a semi-annual D&I Gender Dashboard is prepared and shared with senior management. To improve decision making and team management, the online Managerial People Dashboard was launched in Hungary providing data visualizations and reports about the headcount, diversity, fluctuation, aging, loyalty and internal movements in the organization.

Actions on incidents and complaints related to a fair, ethical, inclusive work environment

In 2024, the Ethics Council received 72 whistle-blower reports related to improper workplace behaviour (i.e., an employee behaved improperly while on company premises or at a work-related event with violating company values), and 13 related to unfair labour practices (i.e., an employee acted improperly or did not follow established company processes in the recruiting, hiring, evaluation, promotion, discipline, dismissal or compensation of an employee).

Furthermore, the following actions were taken in relation to promoting a fair, ethical, inclusive work environment:

- Monitoring local legislations regarding the EU Whistleblower Directive taking action if required by law
- Collaborating with relevant business units on understanding and implementing upcoming sustainability and human rights due diligence requirements
- Focus on awareness communication and partnership with peer organisations (Communication, Cultural Office, Security, etc)
- MOL Group's ethics program in 2024 centered on enhancing awareness through regular articles detailing real investigations in an anonymous manner, as well as mandatory ethics training for all employees.
- Efforts to communicate and educate on ethics were expanded to include governance body members, with ethics integrated into the annual training curriculum for both the Board of Directors and the Supervisory Board.

TARGETS RELATED TO DIVERSITY AND INCLUSION

/S1-5/

ESRS	Disclosure Requirement S1-5
GRI	GRI 3, 3-3

MOL Group’s flagship commitments related to fostering a fair, ethical, inclusive work environment is to constantly ensure that all of our employees successfully complete the annual ethics training, and to reach the targeted minimum 30% of woman in management, applicable on HAY 18 and above. These targets are publicly communicated – including in MOL Group’s Shape Tomorrow Strategy.

Women in management	UNIT OF MEASURE	2024	2023	2022	2021	2020
Percentage of female managers	%	28.2	27.9	26.5	25.9	26.1

METRICS RELATED TO CHARACTERISTICS OF EMPLOYEES

/S1-6/

Workforce /S1-6_1/	UNIT OF MEASURE	2024	2023	ESRS
Number of employees (HC)	persons	25 528	24 912	S1-6_01, S1-6_02, S1-6_09
o/w Male	%	73.1	-	S1-6_01
o/w Female	%	26.9	-	S1-6_01
Full time employees	persons	24 957	24 938	
o/w Male	%	73.8	74.1	S1-6_01
o/w Female	%	26.2	25.9	S1-6_01
Part time employees	persons	571	514	
o/w Male	%	45.7	51.9	S1-6_01
o/w Female	%	54.3	48.1	S1-6_01
Permanent employees (Employees with indefinite term contract)	persons	22 347	21 508	S1-6_7
o/w Male	%	74.5	74.7	S1-6_7
o/w Female	%	25.5	25.3	S1-6_7
Temporary employees (Employees with fixed term contract)	persons	1 934	1 602	S1-6_7
o/w Male	%	61.0	59.8	S1-6_7
o/w Female	%	39.0	40.2	S1-6_7
Number of employee who have left undertaking	persons	2 852	3 076	S1-6_11
Turnover rate	%	12.8	14.1	S1-6_12

Workforce breakdown by country /S1-6_04/	UNIT OF MEASURE	2024	2023	ESRS
Number of employees in Croatia	persons	8 453	8 340	S1-6_05
Number of employees in Hungary	persons	10 130	9 758	S1-6_05
Number of employees in Slovakia	persons	3058	2992	S1-6_05
Number of employees in Non-European Union countries	persons	377	365	S1-6_05
Number of employees in Other European Union countries	persons	1 618	1 655	S1-6_05

Employee data is based on annual sustainability data collection. Employee numbers are reported in head count and reflect year-end closing. Most representative number in the financial statement can be found in the Consolidated Financial Statements General information section.

METRICS RELATED TO DIVERSITY AND INCLUSION

/S1-9; S1-12/

ESRS	Disclosure Requirement S1-9, S1-12
GRI	GRI 405, 405-1

Diversity metrics

Gender distribution in top management*	UNIT OF MEASURE	2024	2023	ESRS
Number of male employees	persons	50	43	S1-9_01
Number of female employees	persons	4	4	S1-9_01
Percentage of male employees	%	92.6	91.5	S1-9_02
Percentage of female employees	%	7.4	8.5	S1-9_02

*Top management is defined based on HAY categories, positions graded as HAY24 or above are considered Top Management.

Age distribution of employees	UNIT OF MEASURE	2024	2023	ESRS
o/w below 30 years old	%	14.5	-	S1-9_03
o/w between 30-50 years old	%	54.6	-	S1-9-04
o/w over 50 years old	%	30.8	-	S1-9_05

Top management is defined based on HAY categories, positions graded as HAY24 or above are considered Top Management.

METRICS RELATED TO REMUNERATION (PAY GAP AND TOTAL REMUNERATION)

/S1-16/

Pay gap	UNIT OF MEASURE	2024	2023	ESRS
Rate of average base salary of women to average base salary of men	%	93.3	-	S1-16_01

Pay gap reflects the difference between average total monthly base salary of female and male employees.

Excessive pay	UNIT OF MEASURE	2024	2023	ESRS
Annual total remuneration ratio of the highest paid individual to the median annual total remuneration for all employees	number	96.3	-	S1-16_02

The indicator includes the median annual total remuneration of all employees at MOL Group's Hungary-based companies, INA d.d. and Slovnaft a.s. compared to the highest paid individual in MOL Group. The remuneration of the highest paid individual is based on the Remuneration Report of MOL Group and includes the total amount paid to the executive in the given year.

The ratio is not available for the median annual total remuneration for all MOL Group employees due to limitations in the data collection process.

METRICS RELATED TO INCIDENTS AND COMPLAINTS RELATED A FAIR, ETHICAL, INCLUSIVE WORK ENVIRONMENT

/S1-17/

ESRS	Disclosure Requirement S1-17
GRI	GRI 2, 2-25 GRI 2, 2-27 GRI 406, 406-1

Number of incidents of discrimination [table] /S1-17_01/

	UNIT OF MEASURE	2024	2023	ESRS
Incidents of discrimination	number	1	-	S1-17_02
Complaints filed through channels for people in own workforce to raise concerns	number	104	106	S1-17_03
Complaints filed to National Contact Points for OECD Multinational Enterprises	number	0	-	S1-17_04
Fines, penalties, and compensation for damages as result of incidents of discrimination, including harassment and complaints filed	HUF	0	-	S1-17_05
Severe human rights issues and incidents connected to own workforce	number	0	-	S1-17_08, S1-17_10
Severe human rights issues and incidents connected to own workforce that are cases of non-respect of UN Guiding Principles and OECD Guidelines for Multinational Enterprises	number	0	-	S1-17_09
Fines, penalties, and compensation for severe human rights issues and incidents connected to own workforce	HUF	0	-	S1-17_11

Complaints and incidents are managed through MOL Group's whistleblower system. More detailed description can be found in this chapter's Ethics subchapter. The number of complaints shows no significant difference from previous year's data.

AFFECTED COMMUNITIES

/S3/

INTRODUCTION

In our 2024 double materiality assessment, we have concluded that MOL Group has both positive and potential negative impacts on affected communities, and acknowledged that a lack of consultation or limited engagement can lead not only to adverse impacts on people, but can also materialize as financial risks for the company, such as to disruption to project planning or operations, delays, rising costs, legal challenges and the potential escalation of local issues to the national stage. Description of the methodology and consultations conducted are described in section ESRS 2 IRO-1 of this report.

MOL Group is a major market player and employer with a sizeable operational footprint, working under special attention from stakeholders, especially from community interests in areas where MOL Group conducts its operations. Community engagement plays a crucial role for MOL Group, particularly in Downstream Production sites across the CEE and in Upstream operations in Pakistan, Hungary and Croatia. MOL Group currently operates four major Downstream Production sites: Danube Refinery located in Százhalombatta (Hungary), Rijeka Refinery located in Rijeka (Croatia), one integrated refinery-petrochemical facility located in Bratislava (Slovakia) and one petrochemical facility in Tiszaújváros (Hungary). All three of the Group's refineries are located in or near areas of dense population (measured as within 49 km of an urbanized area with a population greater than 50,000). A fourth fuel refinery located in Sisak (Croatia) was permanently closed in 2020 and is currently undergoing conversion to an alternative use. A smaller rubber bitumen manufacturing plant (aka. Zala Refinery) is located near Zalaegerszeg (Hungary).

MOL Group's refineries and petrochemicals sites play an important role in contributing to the local and state economy by providing employment opportunities, supporting suppliers, serving industrial customers as well as manufacturing products that are essential to everyday life. However, negative effects associated with petroleum refining are a cause of concern for nearby communities. Most concerns relate to air quality, as refineries and petrochemical plants create nuisance odors and air emissions from refining crude oil, directly affecting the quality of life of nearby residents. MOL Group works to balance local concerns with the desire for economic development, seeking to identify, avoid and mitigate potential negative impacts while developing long-term, positive relationships with the neighbouring communities.

The list of identified impacts and risks can be divided into two groups:

The first group relates to local communities living adjacent to the undertaking's operations:

- Disturbance from operations (IM-17)
- Operational hinderances and / or increased expenses due to community issues (RK-10)

Whilst, the second group relates to the macro-level economic impacts on the welfare of citizens:

- Corporate giving, donations, volunteering (IM-16)
- MOL Group as a taxpayer (IM-18)
- Secure employment on fair terms (IM-12) (see details in S1 - Sub-chapter A: Human Resource Management)
- Trainings and skills development (IM-14) (see in S1 - Sub-chapter A: Human Resource Management)
- Supply of critical products (fuel, electricity, convenience products) (IM-20) (see in chapter S4 - Consumers and end-users)

Since managing impacts and risk related to these two groups require different approaches, this chapter is divided into two sub-chapters to allow a more distinct understanding of MOL Group's policies, actions, targets and metrics associated with each group:

- **Sub-chapter A** focuses on how MOL Group manages impact on, and risks associated with local communities, primarily ones living adjacent to the company's operations. (IM-17, RK-10)
- **Sub-chapter B** focuses MOL Group's policies and actions relate to its macro-level impacts, such as shared wealth and MOL Group's economic impact. (IM-16, IM-18, IM-12, IM-14, IM-20)

SUB-CHAPTER A: MANAGING IMPACTS AND RISKS RELATED TO LOCAL COMMUNITIES

IMPACTS AND RISKS RELATED TO AFFECTED LOCAL COMMUNITIES

/S3. SBM-3/

ESRS	Disclosure Requirement S3.SBM-3
GRI	GRI 3-3-a GRI 413-2-a

The tables below details the identified impacts and risks related to local communities based on our 2024 double materiality assessment:

Table IM-17: Disturbance from operations

Severity	Moderate

Scope	Local level, relevant at all locations mentioned in the introduction section of this chapter
Likelihood	High
Description	MOL Group has 3 refineries, a petrochemical site around 2400 service stations and multiple drilling sites in the proximity of residential areas. Even with all possible pre-emptive actions, this can cause the disturbance of local communities via noise, light pollution and odours.
Actions	See in section 'Actions to manage impacts and risks related to affected local communities'
Time horizons	We consider the issue material on all time horizons, with the aim of reducing the disturbance to the lowest possible level.
Relevance in the value chain	Relevant related to all of MOL Group's operations where local communities are impacted, particularly in Downstream Production sites across the CEE and in Upstream operations in Pakistan, Hungary and Croatia

Table RK-10: Operational hinderances and / or increased expenses due to community issues

Type	Operational risk
Likelihood	Medium
Magnitude of financial effect	Low
Description	Industrial and retail activities of MOL Group are often conducted in the proximity of residential areas. MOL Group sustains a well-established system to communicate high-impact operations (via noise, light pollution and odors) and to receive and handle community grievances and invests in preemptive infrastructure to minimize disturbance. However, incidents, extreme weather events, turnovers, asset replacements and major maintenance can lead to increased noise, odors or light, entailed by reputation risks and/or increased cost in mitigation measures, or in extreme cases, hinderances in operations.
Related impact & dependencies	For information on related impacts on affected communities, refer to *IM-17 - Disturbance from operations*.
Mitigation actions	MOL Group mitigates the risk of hinderances with infrastructure development (e.g., noise walls, odor-reducing actions), informing the public on planned operations, grievance mechanism, public consultations and grants for housing improvements to help minimalize the disturbance.
Financial effect & time horizons	The financial effect of actions is calculated as expenses on corporate giving and donations for local communities and OPEX in relation to preemptive actions and measurements (financial effect of pollution prevention and remediation actions is covered in RK-05). Currently, these expenses do not reach the threshold financial materiality, but related figures are published in DR S3-4 for transparency.
Relevance in the value chain	Relevant related to all of MOL Group's operations where local communities are impacted, particularly in Downstream Production sites across the CEE and in Upstream operations in Pakistan, Hungary and Croatia

IM-16: Corporate giving, donations, volunteering – For further details, please refer to sub-chapter B: Shared wealth & economic impact

POLICIES RELATED TO AFFECTED LOCAL COMMUNITIES

/S3-1; S3-2; S3-3/

ESRS	Disclosure Requirement S3-1, S3-2 & S3-3
GRI	GRI 2-12 GRI 2-23 GRI 2-25 GRI 2-26 GRI 2-29 GRI 3-3 GRI 411-1

This section outlines the company's policies for managing significant impacts and risks concerning affected communities, including the processes for identifying, assessing, managing, and remediating these impacts. It details how MOL Group engages with these communities, incorporates their perspectives into its decision-making, and addresses potential and actual impacts through accessible channels for raising concerns.

General approach of managing impacts and risks related to affected communities

MOL Group's principles related to the economic, environmental, and social development of local communities and respect of human rights is outlined in section IV.6.2. of our Code of Ethics and Business Conduct, and in the HSE Social Impact Policy – both available on our website. In summary, these documents highlight Mol Group's commitment to:

- Make a positive impact while eliminating negative impacts on the communities in which we operate, and on society in general
- Continuously measure, evaluate and improve our HSE and social performance and communicate it openly to stakeholders, including local communities and civil society representatives who are affected by or have legitimate interests in our operations
- Promote a culture in which all MOL Group employees share these commitments and actively participate in initiatives that support local development

(For further details, please refer to full text of these documents via this link provided above.)

To monitor performance and inform management about progress, local communication teams forward half-yearly reports to Group Communications; whilst Group Communication reports at least annually to the Sustainable Development Committee and prepared an Annual Report on Community Engagement, and provides information for external reporting requirements.

Community Engagement

MOL Group has an integrated approach to community engagement and grievance management. The aim of this framework is to identify, assess and remediate potential negative impacts and manage risks (i.e. IM-17, RK-10) – as explained by the **Community Engagement Methodology** (internal document). This regulation provides the principles and practices of community engagement and the process of identifying and involving stakeholders and the high-level process for handling incoming grievances from the public, communities and local authorities. The processes are aligned with all regulations and instruments, including: ISO 9001:2015 and ISO 14001:2015 standards regarding requirements for stakeholder management, the AA1000 Stakeholder Engagement Standard (2015), and IPIECA's „Community grievance mechanisms in the oil and gas industry" standard. The key elements are also publicly available on our website in the Community Engagement Methodology Guide.

MOL Group's engagement with communities is based on principles of inclusivity, transparency, responsiveness, and accountability. The guide outlines a structured process for community engagement, which includes:

1. **Identify & analyse**: Identifying relevant stakeholders
2. **Design & plan**: Developing engagement plans that are tailored to the specific context and needs of the community.
3. **Implementation**: Conducting engagement activities
4. **Evaluate, report & update**: Assessing the effectiveness of engagement activities and making necessary adjustments to improve outcomes.

Engagement processes are structured to identify and analyse stakeholders, develop tailored engagement plans, implement various interaction methods, and evaluate outcomes. The company emphasizes building high-quality partnerships with communities to support business success and strategic objectives while mitigating and addressing potential impacts on local stakeholders.

MOL Group engages directly with affected communities, their legitimate representatives, or credible proxies, such as local non-profits, municipalities, and associations. Community Relationship Officers play a key role in maintaining continuous communication with stakeholders and addressing their concerns effectively. Obtained perspectives and concerns are actively sought to inform decision-making and manage potential and actual impacts. The insights gained shape consensus-based decisions and collaborative solutions to community-related issues. Special attention is given to identifying and addressing the perspectives of marginalized and vulnerable groups within affected communities. The company considers factors such as physical safety, environmental and health conditions, quality of life, and cultural or social cohesion. Proactive measures are taken when resistance or significant risks are identified, ensuring inclusive engagement and equitable outcomes. In case of ongoing operations, such as nearby major industrial site such as refineries and drilling sites, engagement happens on a regular basis. In case of other operations, such as site openings or closure, engagement must occur as early as possible in the lifecycle of the project. Engagement activities include public hearings, joint activities, and ongoing communication with authorities and stakeholders. The frequency and method of engagement are tailored to the specific context, ensuring alignment with community needs and the significance of operational impacts. Effectiveness is assessed through monitoring and evaluation mechanisms that ensure alignment with stakeholder expectations and the resolution of grievances. Feedback from communities and the outcomes of engagement activities inform continuous improvement. Documentation is localized based on the standardized Methodology Guide to address the unique socio-economic and environmental contexts of each site.

(For further details, please refer to full text of these documents via this link provided above.)

Grievances & remediation

Citizens, communities and local authorities have the right to raise a grievance claim if they have a concern, the source of which is potentially connected to the activities of MOL Group – including but not limited to issues related to disturbances, safety, environmental concerns, and potentially human rights concerns. **Community Engagement Methodology** and the **Guide** also sets the Group-level framework for grievance management. The system is established based on the foundations of Guiding Principle 31 in the United Nations (UN) 'Guiding Principles on Business and Human Rights', which is listing 8 effectiveness criteria: legitimate, accessible, predictable, equitable, transparent, rights-compatible, a source of continuous learning and based on engagement and dialogue enabling effective remedy.
A key requirement of the policy is operating grievance channels accessible at all operational levels (on company / organization / site level, depending on frequency of concerns raised and cost-benefit analysis), ensuring that affected communities can raise concerns directly with

the sites impacting them, in the most convenient way possible. To ensure consistency and meeting Group-level requirements, all channels are also overseen by the Group Communication department. In 2024, the following channels were in operation:

- Each local communication team operates an official email channel
- Dispatcher Services: Sites with the highest operational impact (currently Danube Refinery, Slovnaft Refinery) operates 24/7 dispatcher services
- Online platforms: Danube Refinery and Slovnaft Refinery also operates mobile applications and is available on social media platforms that allow residents to submit concerns, receive updates, and access real-time information
- Furthermore, members of affected communities might also use the Group-level whistleblower system (SpeakUp!), as described in Section *S1-3-C: Policies related to grievances and remediation.*

The Group-level regulation on the handling of grievances require:

- All claims have a first response within 24 hours from the time it's received, except for non-automatic answers on weekends and public holidays (the first response can be an automatic or a template answer), that the company/site has received the request and will investigate the grievance.
- All grievances are registered in a dedicated system with a predefined structure on the local level. The lead time for responses is tracked, and performance is monitored through regular reports at both local and group levels. These reports inform annual evaluations to refine grievance handling processes and improve effectiveness.
- Every incoming claim must be evaluated locally, investigated and answered. If necessary, relevant mitigation actions and remedies must be defined and implemented in collaboration with relevant business units and functional areas (such as HSE). The Group-level regulation does not cover the actual business solutions to grievances, as these have to be developed and implemented by relevant business areas. Those details of the process, which is not covered by this regulation - specifications will be regulated on the appropriate local level.
- Every incoming claim and its details is reported as requested by Group Communications.

MOL Group has strict procedures in place to protect individuals who raise concerns via its channels:

- Grievances can be sent anonymously through the established channels, ensuring accessibility without fear of exposure.
- Grievance handling complies with data protection laws, ensuring confidentiality and respect for privacy. MOL Group adheres to stringent data protection rules, ensuring that grievances are treated confidentially. All personal data is processed in compliance with applicable laws.
- As stated in the Code of Ethics and Business Conduct, MOL Group will not tolerate any retaliation against people reporting compliance issues or raising concerns in good faith. Allegations of retaliation are handled by local Ethics Officer or the Group-level SpeakUp!, and appropriate actions will be taken (see section *S1-3-C: Policies related to grievances and remediation)*.

ACTIONS TO MANAGE IMPACTS AND RISKS RELATED TO AFFECTED LOCAL COMMUNITIES

/S3-4/

ESRS	Disclosure Requirement S3-4
GRI	GRI 2-24 GRI 2-25 GRI 3-3 GRI 203-2 GRI 411-1 GRI 413-1

MOL Group is a significant market player and employer with a substantial operational footprint. As such, it operates under close scrutiny from stakeholders, particularly regarding community interests in the areas where it conducts its operations. Members of the public and representatives of impacted groups expect to be informed, consulted, and involved in MOL Group's decision-making processes. A lack of consultation or limited engagement can lead to adverse impacts on people, disrupt project planning and operations, cause delays, increase costs, invite legal challenges, and escalate local issues to the national level.

Community engagement is a critical priority for MOL Group, particularly at its Downstream production sites in Central-Eastern Europe and its Upstream operations in Pakistan. Therefore, MOL Group pursues a strong collaboration with the communities, its partners in the supply chain as well as the regulators, ensuring the involvement of practically every layer of the society in the transition process not only as moral imperative but a strategic necessity for their continued success. The main aim of our actions in 2024 continued to be ensuring that community engagement practice including grievance mechanism and trainings is implemented in 100% of major operations, and that complaints – especially related to environment protection topics such as noise, odour, water and air quality being the most common ones – are minimised and operational hindrances are avoided. (IM-17, RK-10) Below are updates on community engagement efforts and grievance management across key locations.

Danube Refinery

- In 2023, MOL Group developed a mobile application, Hello Dufi, to provide real-time information to the local community surrounding the Danube Refinery. Launched in early 2024, this platform allows residents to submit comments, and MOL Group regularly shares news and updates about refinery operations. This initiative builds on the success of the Slovnaft refinery's Sused Slovnaft app, which significantly improved communication with the local community.
- By October 2024, the Hello Dufi app recorded 750 downloads and facilitated 524 grievances, mainly regarding noise, odour, flaring, and smoke. This increase in reported grievances reflects the app's effectiveness in enabling community feedback.
- MOL Group has enhanced continuous communication with local municipalities around Százhalombatta, fostering partnerships with residents and treating them as key stakeholders.
- In parallel, significant investments were made in 2024 to reduce odour sources and their impacts, addressing one of the most reported issues from the local community.

Bratislava Refinery

- By October 2024, 60 grievances were recorded compared to 69 for the entire previous year. The elevated number of complaints is linked to two major turnarounds in 2024, particularly affecting operations at the Ethylene unit.
- Noise-related grievances are primarily linked to flaring, which, though infrequent, is perceived as highly disruptive.
- MOL Group continues to strengthen communication with local communities, maintaining 24/7 availability and transparency. This approach has resulted in fewer grievances being escalated through local mayors.
- Communication efforts in 2024 included videos, PR articles, and updates to the Sused Slovnaft app. From January 2025, dispatching services will also play a role in promptly addressing community concerns.
- Noise reduction projects are underway, with technological upgrades currently in the testing phase. MOL Group is preparing for potential implementation based on these results.

Rijeka Refinery

- In 2024, six grievances were recorded (three related to the sea and three to air quality), compared to seven in 2023. The decline in sea-related grievances is attributed to remediation activities, including drilling new wells and extracting hydrocarbons to reduce their accumulation in the sea.
- Air-related grievances were primarily linked to the start-up of the refinery, which temporarily increased noise, smoke, and odour levels. Notifications were sent to local authorities and relevant agencies.
- To address noise-related grievances, MOL Group prepared an FEL-1 document outlining two key actions for 2025:
    1. Covering critical equipment on the 379 Claus 2 and 323 Vacuum Distillation units.
    2. Conducting noise-level measurements at locations where equipment was replaced during the 2024 turnaround.
- During the 2024 turnaround, four turbines were replaced with electric motors, and air coolers on FCC/HCU units were upgraded to reduce noise levels.

Upstream Croatia

- By October 2024, three grievances were recorded (two HSE-related and one non-HSE-related), marking a significant decrease from 2023 (10 HSE-related and three non-HSE-related grievances). The reduction is due to fewer workover activities near populated areas in 2024, which previously caused complaints about noise, odour, and smoke.
- MOL Group implemented the **Manage Community Engagement and Grievances** document, requiring quarterly grievance reporting by managers. This improved the grievance resolution process and encouraged the use of established mechanisms.

Sisak Site

At Site Sisak, two grievances were recorded in 2024. Following investigations, it was confirmed that neither was related to the site's operations. One grievance concerned air pollution, which was verified by environmental inspectors as unrelated to activities at Site Sisak. The second grievance involved pollution in the River Kupa, which was similarly found to be unconnected to the site's water management operations.

Upstream Pakistan

- In 2024, 52 grievances were recorded: 14 related to HSE and 38 to community matters.
- To mitigate grievances and enhance resolution, several actions were taken. Awareness-raising discussions were held with local communities before technical work began, informing them about potential impacts and fostering cooperation. The grievance

resolution process was strengthened through a collaborative approach with government support and active participation from relevant departments, leading to more efficient case closures.
A notable best practice at the Makori Deep-3 drilling location involved averting a potential armed conflict among local groups by forming a local committee, as directed by the Commissioner of Kohat Division. This initiative ensured smooth civil works and timely mobilization of the drilling rig, demonstrating the effectiveness of proactive community engagement.

Waste management services

In 2023 with MOHU starting its operation in Hungary the implementation of their integration to the Group level community engagement process has started.

TARGETS RELATED TO AFFECTED LOCAL COMMUNITIES

/S3-5/

ESRS	Disclosure Requirement S3-5
GRI	GRI 3-3

The most important key performance indicators to measure the effectiveness of our actions related to community engagement are the *Number of Relevant Operations with implemented Community Engagement Plan / Number of Relevant Operations* (%) and the *Number of Closed grievances /Number of Registered Grievances by stakeholders* (%). Since they are measured site by site, MOL Group has not implemented a formal Group-level target. Relevant information is disclosed in section 'Actions to manage impacts and risks related to affected local communities' above.

SUB-CHAPTER B: SHARED WEALTH & ECONOMIC IMPACT

IMPACTS RELATED TO SHARED WEALTH & ECONOMIC IMPACT

/S3. SBM-3/

Sub-chapter B focuses MOL Group's policies and actions relate to its macro-level impacts, such as the welfare of citizens, shared wealth and MOL Group's economic impact.

Impacts related to shared wealth & economic impact are the following:

Table IM-16: Corporate giving, donations, volunteering

Severity	Moderate
Scope	Local level, relevant at all locations mentioned in the introduction section of this chapter
Likelihood	Actual impact
Description	MOL Group contributes to the socio-economic progress in local communities in which it operates through several different channels, including volunteering, sponsorships, donations, and other forms of economic support. In 2024, MOL Group supported social investments in the amount of over USD 3.48 million in absolute terms (excluding leveraged donations derived from tax-base decreasing donation instruments).
Actions	See in section 'Actions related to shared wealth and economic impact'
Time horizons	We consider the matter material on all time horizons.
Relevance in the value chain	Relevant related to all of MOL Group's operations where local communities are impacted.

Table IM-18: MOL Group as a taxpayer

Severity	Significant
Scope	CEE
Likelihood	Actual
Description	MOL Group is a major company in the CEE region, therefore a key contributor to the budget of countries where it operates, especially in Hungary, Croatia and Slovakia. MOL Group contributes to the creation of public wealth to a significant degree.
Actions	'Actions related to shared wealth and economic impact'
Time horizons	We consider the issue material on all time horizons.
Relevance in the value chain	MOL Group as a taxpayer is material impact across all levels of MOL Group's value chain.

- IM-12: Secure employment on fair terms – see details in S1 - Sub-chapter A: Human Resource Management
- IM-14: Trainings and skills development - see in S1 - Sub-chapter A: Human Resource Management
- IM-20: Supply of critical products (fuel, electricity, convenience products) – see in chapter S4 - Consumers and end-users

POLICIES RELATED TO SHARED WEALTH & ECONOMIC IMPACT

/S3-1; S3-2; S3-3/

MOL Group's operations are guided by a strong commitment to ethical conduct, transparency, and social responsibility, as outlined in its **Code of Ethics and Business Conduct**. These principles are embedded in the company's approach to social investment, sponsorship, and donations, ensuring that MOL contributes meaningfully to the economic, environmental, and social development of the regions where it operates.

MOL Group actively invests in raising living standards and fostering social development in its operational regions. Beyond creating jobs, the company gives back to the communities by paying taxes and engaging in activities that enhance public health, culture, and education. These initiatives aim to create a more habitable environment and economically resilient communities, reinforcing MOL's role as a key contributor to societal progress.

Transparency is a cornerstone of MOL Group's financial and operational practices. The company pays taxes responsibly and in full compliance with all applicable laws and international regulations, including those related to transfer pricing. Responsible taxpaying is viewed as an integral part of MOL's social responsibility, and the same high standard is expected from all business partners across the value chain. This commitment underscores MOL's dedication to fostering trust and integrity in all its dealings.

MOL Group's engagement extends beyond financial contributions, as it actively participates in trade organizations, industry associations, and multi-stakeholder partnerships that promote the values of sustainable development (please see relevant disclosures in Sub-chapter G1-A). By identifying social and societal needs, MOL supports social enterprises and innovation as tools for addressing challenges. The company also encourages and facilitates volunteer activities among its employees, fostering a culture of social engagement that aligns with MOL's core values.

To enhance positive impacts (i.e. IM-16), **Managing Corporate Giving Activities Process Description** defines the Group-level processes related to sponsorship, donation and social investment activities in order to provide a comprehensive framework for the management of successful, efficient and transparent corporate giving activities within the company. Its key principles are available on our website under MOL Sponsorship and Donation, underpinning our corporate giving strategy, ensuring impactful, ethical, and sustainable contributions to society:

1. **Focus on Positive Social Impact:** We prioritize structured, goal-oriented programs that deliver significant social impact, focusing on children, talent development, disadvantaged groups, local communities, health, culture, sports, and environmental protection.
2. **Professionalism and Ethical Standards:** All decisions are guided by strict ethical norms (based on MOL Group's Code of Ethics and Business Conduct) and predefined strategic and professional criteria, supported by independent advisory committees. Supported partners are also expected to respect our core values, including human rights and the rejection of corruption and discrimination.
3. **Transparency and Accountability:** We maintain clear and regulated processes, expect adherence to transparency, and provide regular reports on our activities. Only programs with a transparent background are supported.
4. **Sustainability and Long-Term Value Creation:** Our support emphasizes sustainability, integrating economic, social, and environmental considerations to maximize long-term benefits.
5. **Cross-Border Engagement:** As an international company, our support extends to all countries of operation, tailored to local opportunities, needs, and resources.
6. **Community Involvement:** We encourage initiatives requiring active community participation and ensure that community interests are represented in decision-making.
7. **Promotion of Talent and Achievement:** We recognize and support young talents, ensuring funding reaches those most deserving and in need, as determined by professional evaluations.
8. **Focus on Practical Outcomes:** Preference is given to action-oriented programs over events or conferences, limiting the latter to 20% of total sponsorship activities.
9. **Support for Local Communities:** Emphasis is placed on initiatives benefiting communities within the MOL Group's operational areas.
10. **Non-Discrimination and Ethical Standards:** We refrain from supporting religious organizations, political activities, or any initiative conflicting with human rights, public morals, or ethical standards.
11. **Maximizing Efficiency and Synergies:** Resources are concentrated on fewer, impactful projects to ensure efficient use and greater overall effectiveness.
12. **Tax Efficiency:** Priority is given to support programs providing tax advantages, aligning with our financial strategy.
13. **Preparedness and Planning:** Only requests submitted at least three months in advance are considered, ensuring thorough evaluation and synergy exploration.
14. **Conflict of Interest Prevention:** MOL Group does not provide direct financial support to shareholders or employees to avoid conflicts of interest.
15. **Recognition of Quality and Excellence:** We support initiatives symbolizing quality and persistence, aligning with our ethos of achieving exceptional results through dedication.
16. **Incubator Effect:** We prioritize projects requiring initial support to ensure long-term sustainability once established.

17. **Corporate Responsibility and Profitability:** Our giving activities are linked to corporate profitability, with a commitment to allocate 1% of the MOL Group's average net business result over the past three years to such initiatives.
18. **Ethical Use of Resources:** Our preference is for in-kind support, such as fuel or gift cards, which aligns with our operational strengths.
19. **Merit-Based Selection:** Programs are primarily selected through open competitions and reviewed by professional panels to ensure fairness and alignment with societal needs.

In case of major projects affecting a wider society in the place of operation a Social Investment programme design should be carried out. Programme planning occurs simultaneously with the business project design itself. Based on the methodology defined in The Social Engagement Group Practice, before decision on an investment or abandonment project proposal sites/operations shall carry out a Social Impact Assessment to identify basic information and ideas about wider societal issues. A context study should also include an analysis of existing local opportunities to improve the Company's effectiveness or strategy execution. These could include: available human resources, government capacity, physical infrastructure (e.g. waste management, town planning, etc.) and local supplier/contractor capabilities.

ACTIONS RELATED TO SHARED WEALTH & ECONOMIC IMPACT

/S3-4/

MOL Group, as a leading company and major taxpayer and in the Central and Eastern European region, plays a pivotal role in fostering shared wealth and economic stability in the countries where it operates. Particularly in Hungary, Croatia, and Slovakia, MOL Group's substantial contributions to national budgets through taxes, royalties, fees, and other financial streams directly support public services, infrastructure, and social programs. By generating significant economic value, the Group enhances public wealth, benefiting governments, communities, and stakeholders alike.

Financial contributions are extensive and include taxes, mining royalties, rental expenses, wages, salaries, social security payments, and employee benefits. These contributions form a cornerstone of economic development in the regions where MOL operates, ensuring the funding of essential public services such as healthcare, education, and infrastructure. The scale and impact of these payments are detailed in MOL Group's Financial Consolidated Statements, specifically in sections on Total Operating Expenses and Income Taxes. Additionally, the company's annual "Payments to Governments" report (in line with Chapter 10 of EU Directive 2013/34/EU and Chapter VI/A of Hungarian Accounting Act C of 2000) provides a transparent breakdown of its fiscal contributions, underscoring its role as a responsible corporate entity committed to supporting national and regional economies.

As one of the largest employers in the regions where it operates, MOL Group's economic impact extends beyond taxation. The company's provision of secure, long-term employment is a critical component of its socio-economic influence (IM-12). MOL ensures its employees are treated with respect, fairly compensated, and supported through comprehensive benefits that promote well-being and stability. This approach not only provides financial security to employees and their families but also drives local economic activity, as wages and salaries are reinvested into surrounding communities. In regions facing economic challenges, MOL's presence helps to reduce unemployment and create a stable foundation for economic development. See more details in S1 - Sub-chapter A: Human Resource Management.

In alignment with its broader ESG strategy, MOL Group integrates sustainability into its operations, further amplifying its positive impact. This includes sustainable procurement practices that prioritize local suppliers, reducing environmental impacts and fostering stronger community relationships. By considering logistics-related costs and emphasizing local partnerships, procurement framework supports regional development while achieving operational efficiency. Furthermore, MOL Group ensures the continuous supply of critical products, such as fuel, electricity, and convenience products, which are essential for maintaining societal and economic stability (IM-20).

Social investments are another vital aspect of the company's contribution to shared wealth and economic development. The company is committed to enhance its positive effect on the socio-economic progress in local communities in which it operates via effective actions, including volunteering, sponsorships, donations, and other forms of economic support (IM-16). As a key example, MOL Group collaborates with the Hungarian Food Bank Association. In 2024, this partnership saved more than 14 tonnes of surplus food from service stations, effectively preventing over 35 tonnes of CO2 emissions, as estimated by the FAO Food Wastage Report. This initiative reflects MOL's dedication to reducing waste and mitigating environmental impact while supporting those in need.

In 2024, one of our most important Group level corporate social responsibility initiatives was the Green Belt Program, which exists in 6 countries in order to support local communities to create public green spaces. Since 2005 nearly 1800 initiatives were supported, 3,2 million square meters green areas were renewed, 389,540 trees, flowers and shrubs were planted in worth of more than USD 5.9 million. Another important initiative is the Talent Support and Child Healing Program, which exists in 3 countries. Since 2006 we helped more than 10,434 young people in the fields of sports, classical music and sciences for USD 5.8 thousand. Also, MOL's partnerships with hospitals and organizations in Croatia and Romania improve the quality of life for children with chronic illnesses and disabilities, further demonstrating its commitment to social responsibility.

TARGETS RELATED TO SHARED WEALTH & ECONOMIC IMPACT

/S3-5/

Published in its Shape Tomorrow Strategy, MOL Group has a target of ensuring that at least 50% of social investments are spent on local communities by 2030. Social investments are defined as the voluntary contribution of companies to communities located near their operations and to society at large with the aim to support external stakeholders in their fields of interest, typically through transfer of knowledge, skills or resources. Interim progress towards the target is not published. In 2024, MOL Group donated 1,270 million HUF in total in cash, in-kind giving or leverage. The amount does not include sponsorships.

CONSUMERS AND END-USERS

/S4/

INTRODUCTION

As an integrated oil and gas company, MOL Group's primary end-user base is the consumers attending our service stations. Consumer Services segment of MOL Group is a leading fuel retail operation in the CEE region, with a 10 million retail customer base and one million daily transactions. The success and profitability of the current Consumer Services business have been defined by fuel retailing for the past 75 years. Despite healthy growth of fuel consumption in Central Eastern Europe in the past several years, advancements in technology and new consumer habits have fundamentally changed what has so far been considered fuel retailing. MOL Group, realising the need to adjust to this new environment, made a core part of its 2030 strategy to transform its retail operations by tapping into growing areas of consumer demand and take part in the reinvention of transportation in CEE. Therefore, MOL Group considers its core consumers base "people on-the-go", rather than only end-users of our fuel and other oil products.

This chapter focuses on how the impacts on this core consumer base are managed, and opportunities related to the expanding mobility services offered by the company.

IMPACTS AND OPPORTUNITIES RELATED TO CONSUMERS

/S4. SBM-3/

ESRS	Disclosure Requirement related to SBM-3_01, SBM-3_01, S4.SBM-3_01 to S4.SBM-3_08

In our 2024 double materiality assessment, we identified 4 impacts and 2 opportunities which specifically relate to our core consumers base – "people on-the-go" – as defined in the Introduction section of this chapter. We concluded the topic *Consumers and end-users* to be material from both impact and financial perspective. Description of the methodology and consultations conducted are described in section ESRS 2 IRO-1 of this report. This section outlines the impacts and opportunities associated with the Retail and Consumer services segment of MOL Group:

Table IM-20: Supply of critical products (fuel, electricity, convenience products)

Severity	Significant, actual positive impact
Scope	Regional (Central-Eastern Europe)
Likelihood	Actual
Description	MOL Group is a key supplier of fuel & energy (both for wholesale and retail customers) in the CEE region (leading regional network: among top 3 players on 100% of its retail network) and operates ~2400 services stations providing fuel (including close to 300 electric charging points) and convenience products and services not only in urban areas and alongside highways, but often in remote areas where access to fuel for rural communities would not be available otherwise.
Actions	MOL Group is dedicated towards continuing to fulfil consumer demands during regulatory changes, market turbulences and potential crises.
Time horizons	We consider the matter material on all time horizons.
Relevance in the value chain	The impact is material for the Consumer services segment, in all 10 countries where MOL Group operates service stations.

Table IM-21: Consumer health & safety

Severity	Moderate
Scope	Local
Likelihood	Medium
Description	MOL Group operates over 2400 service stations mainly via partners or contractors. The offered products at fuel stations, such as fuels and chemicals can be hazardous to health and safety, posing potential risks on consumers, workers and on nearby communities even with strict safety regulations. This is managed with proper staff trainings, shared important information for customers and always compliant assets, operations and goods. On the other hand, service stations have properly trained personnel, who therefore are capable of providing assistance and first aid (including more than 130 defibrillators) - which can be especially crucial in remote areas, such as next to roads and highway, where help would not be available in close proximity otherwise. Additionally, many stations are equipped with life saving devices like automatic defibrillators as well, ensuring the intervention in special cardiovascular catastrophic situations on these remote areas too.
Time horizons	We consider the matter material on all time horizons.
Relevance in the value chain	The impact is material for the Consumer services segment, in all 10 countries where MOL Group operates service stations.

Table IM-22: Providing sustainable mobility services

Severity	Moderate positive impact
Scope	Country level (Hungary, Slovakia) / potentially regional (Central-Eastern Europe) in the future
Likelihood	Actual
Description	Beyond traditional retail, MOL Group is embracing changes in transportation by tapping into growing areas of consumer demand. MOL Group's mobility services include car sharing (MOL Limo's fleet of ~450 cars of which over a third is fully electric); bike sharing (in Budapest & Bratislava); fleet management (MOL Fleet Solution manages vehicles used by MOL Group and external clients) & public transport (operating over 300 buses in Hungary through a joint-venture).
Time horizons	We consider the matter material across all time horizons, to an increasing extent.
Relevance in the value chain	The impact is material for the Consumer services segment, in all 10 countries where MOL Group operates service stations.

Table OP-06: Shared economy services

Maturity	Implemented at scale
Likelihood	Low
Description	MOL Group supports sustainable transportation options by investing in car-sharing (MOL Limo) and sponsoring bike-sharing services (Bubi, Bajk), promoting energy-efficient modes of travel and reducing the carbon footprint associated with personal vehicle ownership.
Related impacts, risks and dependencies:	Impacts of MOL Group's early entrance to this emerging sustainable market are providing sustainable mobility services (IM-22) fostering the transition to a low carbon economy (IM-01). It also contributes to reducing climate change related risks (RK-01, RK-02).
Financial effect & time horizons:	Investments and EBIDTA from sharing economy services makes the financial effect of this opportunity „medium". It is considered financially material in all time horizons, but mainly on the long term due to its increasing significance.
Relevance in the value chain	The opportunity is material for the Consumer services segment. Currently car sharing (MOL Limo) and fleet management services (MOL Fleet) are provided in Hungary, while Mol Group supports bike sharing in Budapest, Hungary (MOL Bubi) and in Bratislava, Slovakia (Bajk). In the future, MOL Group's aim is to expand these services to other municipalities and countries, with the goal of becoming one of the primary sources of mobility solutions and innovations in the region.

Table OP-07: E-charging network

Maturity	Implemented at scale
Likelihood	Low
Description	By investing in e-charging infrastructure, MOL Group supports the growth of electric vehicles, contributing to the reduction of greenhouse gas emissions in the transportation sector, and also enters into a growing market. Besides increasing the current number of MOL Plugee-branded electric chargers at service stations, together with other partners of the NEXT-E consortium, MOL Group have installed over 300 EV chargers along main highways in the Czech Republic, Slovakia, Hungary, Slovenia, Croatia and Romania.
Related impacts, risks and dependencies:	Impacts of MOL Group's investment in the development of the regional e-charging network are providing sustainable mobility services (IM-22) fostering the transition to a low carbon economy (IM-01). It also contributes to reducing climate change related risks (RK-01, RK-02).
Financial effect & time horizons:	Investments and EBIDTA from e-charging network makes the financial effect of this opportunity „medium". It is considered financially material in all time horizons, but mainly on the long term due to its increasing significance.
Relevance in the value chain	The opportunity is material for the Consumer services segment. MOL Group currently operates close to 300 electric chargers across 6 countries Central-Eastern-Europe.

POLICIES RELATED TO CONSUMERS AND END-USERS

/S4-1; S4-2; S4-3/

In line with the business and sustainability strategy of MOL Group, the main objectives of the internal policies in the field of Retail and Mobility (together referred to as Consumer Services) are to meet the changing consumer needs whilst minimising the negative environmental effect, support the transition towards sustainable mobility and transport, whilst ensuring profitability and business continuity on the long term. MOL Group's policies ensure a structured approach to managing impacts and opportunities related to consumers through a focus on sustainability, operational reliability, and innovation.

The highest-level process-based policies of the Consumer Services segment -supervised by the Group Consumer Services Vice President - are the **Retail Area Book** and the **Mobility Area Book.** Processes described in these documents must be applied at all MOL Group companies providing Retail and/or services by channelling them into local and operation specific Process Descriptions.

In the Retail segment, a key priority is ensuring the availability of critical products and services, including fuel and convenience goods at all times and all locations (IM-20). This must be implemented with processes related to local supply chain management - responsible for product availability – and efficient inventory optimization. This commitment reflects the company's critical role in the CEE region.

In the Mobility segment, policies must focus on not just following but driving the trend towards innovative and sustainable mobility solutions in line with the Shape Tomorrow strategy's objectives. The Mobility Area Book declares that new trends in the market for mobility services shall be continuously researched even beyond the scope of existing mobility businesses to monitor potential market entry strategies. New mobility-related business opportunities and possible innovative approaches to customers shall be identified, innovative solutions and new business lines shall be explored. Clear, regularly monitored targets and KPIs must be set to ensure continuous investments in electric vehicle charging infrastructure and support for providing alternative fuels and shared transportation options. These are crucial to promoting the transition to a low-carbon economy (IM-01; IM-22; OP-06; OP-07) whilst meeting changing consumer demands.

HSE compliance is also central to these efforts, with strict operational standards, regular staff training, and the provision of life-saving equipment such as defibrillators to ensure safety at all service stations (IM-21). Sustainability is a cornerstone of MOL Group's operations. The Group Retail organization has committed to conscious waste management, recycling and increased energy efficiency to support reaching MOL Group's carbon reduction goals.

MOL Group integrates consumer perspectives into its strategic and operational decisions through comprehensive policies designed to prioritize consumer insights. Regular consumer engagement combined with business data provides a holistic understanding for stakeholders, supporting the actionable insights that address specific consumer needs and ensure adaptability to changing consumer expectations. Retail customer's insights are systematically collected to overall customer satisfaction through a number of channels. On Group level, the most important channels are as follows:

- A comprehensive customer insight system known as Brand Tracking is used for the ongoing monitoring of our customers' behaviours on a monthly basis through. This system is operational across seven countries, encompassing a total of 3,000 customers per country, resulting in a cumulative 21,000 participants within MOL Group. Monthly data collection, amounting to

250 customers per month per country, is a fundamental aspect of this process. Brand Tracking provides invaluable data pertaining to brand awareness, usage patterns, overall brand performance, and 25 distinct key performance indicators (KPIs) related to fuel, gastronomy, store hygiene, loyalty programs, and staff behaviour. These insights inform the development of country-specific action plans while an important part of this tracking evaluates the effectiveness of our primary campaigns enabling continuous enhancement of their efficiency.

- Emphasizing our commitment to quality, we put significant emphasis on ongoing product quality enhancement initiatives, facilitated by a series of rigorous product tests. For instance, our fuel quality assessments involve collaboration with DTC Austria, while blind taste tests conducted by third-party agencies evaluate key gastronomy offerings.
- To gain deeper insights into the evolving needs of our loyal customers and respond promptly to their changing habits, we have implemented an internal research system (e.g. Rate My Shopping initiative) to obtain rapid feedback from members of our loyalty programs. The continuous refinement of our offerings and loyalty functionalities are informed by these insights. The customer loyalty program constitutes a key element in the digital transformation of Consumer Services. MOL MOVE, the digital, gamified, tier-based rewards program has been introduced in 8 markets already (Croatia, Slovenia, Hungary, Czech Republic, Slovakia, Romania, Serbia and Poland). The platform enables MOL Group to provide personalized and highly automated communication with an omnichannel approach, currently with 4,5 million active users across our CEE network.
- Regarding the handling of general consumer complaints, MOL Group does not have unified policy. All retail stations are expected to operate their own system of handling consumer complaints following local legal requirements. In case a consumers concerns are not addressed on local level, consumers are encouraged to use the Group-level **SpeakUp!** mechanism accessible for all internal and external stakeholders for advice or to raise concerns ("whistleblowing"). Reports can be made anonymously and will be treated as confidential, without risk of reprisal. For further details, please refer to Section S1-C: Policies of this report.

ACTIONS RELATED TO CONSUMERS AND END-USERS

/S4-4/

In 2024, MOL Group continued to implement targeted actions to achieve business goals in line with the strategy and policy objective, including measure to addressing the identified impacts and opportunities.

- **The retail segment** invested USD 113.4 million in 2024, prioritising the delivery of critical products with superior quality (IM-20) and maintaining our service station network of nearly 2,400 locations across ten Central Eastern European countries, ensuring accessibility and reliability for millions of consumers daily. In 2024 we continued offering enhanced EVO Plus fuels featuring the EVO Plus Triple Effect, which ensures better engine performance, lower emissions, and longer engine life; and further developed our e-charging network. Energy consumption for all EV chargers in 2023 reached 2,4 GWh, saving a total of 1.800 tonnes of CO2-eq in 2024 Jan-Nov period the CO2eq total saving is 1.600 tonnes.
- **The mobility segment** invested USD 60.2 million in 2024, advancing toward a cleaner and more efficient mobility ecosystem:
  - **Electric charging network:** In 2018, MOL Group launched MOL Plugee, a new EV charging brand under the Consumer Services division. By year end 2024, 278 MOL Plugee EV chargers were installed throughout the Group's service station network across the CEE region. In 2024 MOL Group installed 5 ultra-fast and 5 DC charger solutions on 6 existing and on 2 new locations in Hungary. MOL Group launched its application-based service in Hungary in 2020 and in Slovenia, Slovakia, Czech Republic, Croatia and Romania in 2021. At the end of 2024 it enabled our more than 55,000 registered Plugee users and other customers to have a seamless charging experience in 6 countries thanks to the late summer introduced European roaming activity. Next to the European roaming, this year MOL Plugee launch the virtual fuel card for B2B partners which highly supports the electrification of the business sector. Energy consumption for all EV chargers in 2024 reached 2,200 MWh, saving a total of above 660 tonnes of CO2-eq.
  - **Car sharing:** MOL Limo is the largest car-sharing service in Budapest with a fleet of 450, of which one third is electric. Every shared car expected to replace 5-10 private cars thereby MOL Limo is supporting the UN's SDG 12 on Responsible Consumption. To motivate users for sustainable transportation solution, every MOL Limo monthly subscription is automatically accompanied by MOL Bubi monthly subscription.
  - **Bike-sharing:** MOL Bubi (in Budapest) and Slovnaft Bajk (in Bratislava) bike-sharing services are also supported by MOL Group to promote emission-free and healthy mobility.
  - **Fleet Management:** The average age of our managed fleet remained under three years, significantly reducing CO2 emissions compared to the Hungarian national average vehicle age of 16 years. It is available for Plugee users to charge fleet vehicles with fleet cards, so our fleet solutions are ready to serve both electric, hybrid and ICE vehicles as well. In 2024, the electric fleet's energy consumption reached 70.000 kWh, saving a total of 50 tonnes of CO2-eq.

In 2025 and beyond, MOL Group remains committed to expanding its sustainable mobility initiatives, focusing on electrification, hydrogen-based solutions, and fleet management innovations.

- As part of these efforts, MOL Group will introduce additional electric and hybrid vehicles to its MOL Limo fleet, further enhancing urban mobility with lower-emission transport options.
- In January 2024, MOL Group signed strategic agreements with Hungary's three largest public transport and freight companies—Volánbusz, MÁV, and Waberer's—to foster the development of hydrogen-based mobility solutions. This collaboration aims to stimulate the domestic green hydrogen market and lay the groundwork for broader adoption in public and commercial transportation.
- In November 2024, MOL Group reached an agreement with Mercarius Flottakezelő, one of Hungary's largest and fastest-growing vehicle fleet management companies. Under this agreement, MOL Fleet Solution and Mercarius have established a joint holding company, MOL Mercarius, which will become the second-largest player in the Hungarian fleet management market, managing more than 20,000 vehicles. This collaboration aligns with MOL Group's long-term strategy to strengthen its fleet management capabilities while promoting sustainable and efficient mobility solutions.

We did not identify any significant, systematic negative impact on our consumers. In line with our policies, customer satisfaction is continuously monitored. In 2024, we continued to enhance the "Rate My Shopping" initiative, a key consumer engagement programme with the aim of maintain high-quality service standards across the network our service stations. Through real-time feedback collection, customers provide immediate evaluations of their experiences, allowing MOL Group to monitor satisfaction levels and identify areas for improvement. Feedback is analysed continuously, enabling the identification of service stations with recurring low scores or complaints. These stations undergo a thorough review, with collaborative discussions involving partners and station hosts to address weak points, share good practices, and develop targeted action plans. Written feedback is reviewed regularly to ensure swift responses to suggestions and resolution of identified issues. The initiative is closely integrated with MOL Move, the company's customer service platform, to manage complaints effectively. Critical complaints, such as financial discrepancies, ethical violations, cleanliness concerns, HACCP issues, and product or service unavailability, are flagged for immediate attention. Area Sales Managers are notified to align field actions, and customers receive official responses to ensure accountability and transparency.

The *eSMILE* - launched in 2020 - is a flagship training and development programme for over 19,000 service station employees. This digital microlearning platform covers product knowledge, consumer care, compliance and safety aspects. It ensures improved customer interactions through skilled and confident staff, timely updates during events (pandemic situations) ensuring safety, and the proactive service approach introduced with the *Customer Service Protocol*. The platform also accelerates onboarding for new hires, enhancing their readiness. By fostering employee engagement and upskilling, *eSMILE* improves customer satisfaction and supports the transformation of MOL's service stations into modern FMCG hubs.

Protection of the health and safety of our customers visiting our service stations in an outmost priority. (IM-21) This is ensured by sustaining capabilities to provide assistance and first aid for those on their way. In 2024, and over 133 service stations are equipped with defibrillators and personnel trained in providing first aid at most service stations (over 90% in Hungary, Slovakia, Czech Republic, Croatia and Slovenia).

EXCLUDED DISCLOSURE REQUIREMENTS FROM SOCIAL STANDARDS

Topic	Relevant IDs	Explanation
Human rights abuse, Forced labour, child labour, modern slavery and human trafficking	S1.SBM-3_07 – 10 S1-1_06 S1-1_08 S1-2_05 S1-17_14 S2 – all disclosures S3-1_03 S3-1_05 S3-1_07 S3-4_11	MOL Group exposure to the risk of incidents of human rights abuse, forced labour, child labour, modern slavery and human trafficking is relatively minor given that most of the Group's activities are performed in European countries. Nevertheless, MOL Group is committed to lawful and fair employment and to respecting labour principles. MOL Group also expects the same from business partners and external stakeholders. MOL Group will not tolerate any form of forced, compulsory, bonded or child labour or any other kind of unethical employment practice such as withholding wages, denying sick leave or daily rest, abuse of alternative employment forms or evasion of health care contributions. We ensure that these forms of labour and slavery, servitude, and human trafficking do not take place within our business and supply chains. To further improve social risk management in the supply chain, MOL Group's Procurement organization will implement conduct an in-depth supply chain screening in line with the Hungarian *Act CVIII of 2023 on the rules of corporate social responsibility considering environmental, social, and societal aspects to promote sustainable financing and unified corporate responsibility, and on the amendment of related laws* until June 2025.
Impacts on indigenous peoples	S3-1_01 S3-2_07	Disclosures related to impacts on indigenous peoples are excluded, as the topic is not material. Neither MOL Group CEE operations, nor its International Upstream operations located adjacent to indigenous peoples' communities. Nevertheless, MOL Group committed to protecting indigenous peoples' rights (based on the UN definition) under its Code of Ethics and Business Conduct.
Opportunities related to social standards	S1-4_07 S2-4_09 S3-4_09	Although we acknowledge that to realise any business opportunities, human resources and the support of local communities are key enablers, we did not categorise any of the identified opportunities directly into these topics.
Target setting - Workforce' representatives	S1-5_01 S1-5_02 S1-5_03	Workforce' representatives are informed about the results of tracking performance against targets (i.e., employee engagement rate, TRIR guidance, completion of annual ethics training,) but no documentation is available on consultations with workforce' representatives.
Awareness & trust in channels to raise concerns	S3-3_14	Currently there is no Group-level information available on the a assessment of awareness and trust in processes related to affected communities
Vulnerable / marginalised consumers and end-users	S4-2_06	Impacts we have identified for Consumers and end-users are positive impacts, and MOL Group has not identified consumers and end-users that may be particularly vulnerable to impacts or marginalised. Therefore disclosure requirement is omitted.
Targets related to consumers & end-users	S4-5_01 S4-5_02 S4-5_03	Due to the nature of the target, no direct engagement with consumers and end-users was conducted.
Resources allocated to management of material impacts	S1-4_09 S2-4_12 S3-4_12 S4-4_12	In case of social impacts, resources allocated to managements cannot be reliably estimated. Development of methodology is under consideration.

DISCLOSURES ON GOVERNANCE STANDARDS

INTRODUCTION

In our 2024 double materiality assessment, we identified the following impacts and risks related to governance[36]:

- Key regional business partnerships (IM-09)
- Risk of unfair business conduct (IM-10)
- Risk of fraud (RK-11)
- Risk of Information & cyber security incidents (RK-12)

As a result, we concluded the topic Governance to be material from both impact and financial perspective. Description of the methodology and consultations conducted are described in section ESRS 2 IRO-1 of this report.

These impacts and risks can be categorised into 3 groups, each requiring specific expertise, policies, actions and approaches to be managed. Therefore this chapter is divided into the following 3 sub-chapters outlining specificities of each group:

- **Sub-chapter A** outlines MOL Group's approach to ethical business conduct, describing policies and metrics related to fraud prevention and lobbying (IM-10, RK-11).
- **Sub-chapter B** describes how MOL Group ensures fair treatment of suppliers focusing on payment practices (IM-09).
- **Sub-chapter C** provides a general overview on MOL Group's cyber & information security approach (RK-12).

Each sub-chapter starts by providing a detailed description of IROs relevant for the topic, then details of the policies, actions, targets and metrics to outline how these IROs are managed by MOL Group.

SUB-CHAPTER A: BUSINESS CONDUCT

IMPACTS, RISKS & OPPORTUNITIES RELATED TO BUSINESS CONDUCT

/G1. IRO-1/

As an operator in a high-risk industry, MOL Group is committed to monitor, manage and maintain its risks related to business conduct within acceptable limits, with continuous risk monitoring. Fraud incidents, including corruption, bribery, and lack of transparency in business conduct, can have adverse consequences for our stakeholders and also embodies financial risks for the company. Through our double materiality assessment, we have identified both of these aspects: the stakeholder impact is addressed under the 'IM-10: Risk of Unfair Business Conduct,' while the financial risk implications are captured by 'RK-11: Risk of Fraud.' - as described in the tables below:

Table IM-10: Risk of unfair business conduct

Severity	Moderate, potential negative impact
Scope	Regional (Central-Eastern Europe)
Likelihood	Low
Description	Being one of the biggest companies in the CEE region, MOL Group is in possession of significant corporate power. Misconducts of individuals or organisations exercising corporate power is documented as a potential source of adverse impact on society, democratic processes, business partners, workers, local communities, stockholders, consumers and on the environment. Therefore, MOL Group prioritises the establishment and reinforcement of its ethics management system to ensure integrity and transparency.
Mitigation actions & remediability	MOL Group implements several mitigation actions to ensure ethical practices. These include adherence to a Code of Ethics and Business Conduct, internal protocols and mandatory trainings, ongoing monitoring and investigation of ethical breaches, and a publicly available whistleblower reporting system (Speak Up!). Additionally, MOL Group enforces stringent internal and external ethical expectations throughout its supply chain. In case of detecting a misconduct, MOL Group takes responsibility and ensures the remediation of affected parties to the fullest possible extent.
Time horizons	We consider potential impact material on all time horizons.
Relevance in the value chain	We consider potential impact material in relation to all of our value chains.

[36] Although we acknowledge that to realise any business opportunities, having solid corporate governance practices is a key enabler, we did not categorise any of the identified opportunities into G1 – Governance.

Table RK-11: Risk of fraud

Type	Other (Fraud)
Likelihood	Low
Magnitude of financial effect	Medium
Description	Fraudulent activities (external & internal fraud) may cause significant financial and reputational damages.
Related impact & dependencies	For information on related impacts, refer to *IM-10 - Risk of unfair business conduct.*
Mitigation actions	MOL Group mitigates the risk of incidents by dedicated teams and control functions on local and group level and increasing awareness by mandatory trainings and regular newsletter.
Financial effect & time horizons	Financial effect of the risk is not quantifiable, but the topic is considered material (medium) due to the severity of potential risks on all time horizons.

POLICIES RELATED TO BUSINESS CONDUCT

/G1-1/

Ethics and governance practices are essential to ensure that the company understands and mitigates the sustainability risks of its operation and is able to manage those risks. It contributes to improving MOL Group's financial position while maintaining its authenticity and validity to investors and operating as "good corporate citizen". This section outlines the company's principles, commitment, procedures on business conduct, detailing how it prevents, identifies, assesses, manages, and addresses related impacts (IM-10) and risks (RK-11). MOL Group prioritises the establishment and reinforcement of its business conducts and corporate ethics management system. The key principles of this system are laid in the **Code of Ethics and Business Conduct**:

Free and Fair Trade and Competition

MOL Group is dedicated to practicing fair market behaviour; its activities on the market must be conducted in accordance with the norms of fair competition and the spirit and letter of applicable competition law. Fully complying with competition law is not only a legal obligation but is related to attitudes and cultures that can positively impact a company's business. The aim of MOL Group´s Compliance plan is to raise awareness of our employees and to eliminate legal risks, thus supporting the effective implementation of business strategies in a legal way.

Group Compliance organization has a constantly adjusted scope to the changing regulatory and business environment (Group Compliance Plan), which focuses on those compliance risks that require engagement on corporate level, e.g. competition law, consumer protection, personal data protection rules and international trade restrictions and to prevent insider trading and anti-money laundering. These areas may bring high potential consequences (fines, reputational risks, behavioural remedies etc.). Group Compliance Plan is operated for minimizing compliance exposure by conducting investigations and performing trainings to increase awareness. Group Compliance has its dedicated experts. In-house investigations aiming at monitoring compliance with internal and external commitments are being performed.

Anti-Corruption and Anti-Fraud

MOL Group does not engage in and does not tolerate corruption in any form (including bribery, facilitation payment, kickback, extortion, misuse of authority for personal gain, undue benefits or gifts with the intent to influence), whether in the private or public sector on any scale. We maintain this view, even if our commitment to this policy places MOL Group in a non-competitive business position, or if speaking up against such activity results in MOL Group losing business. Throughout our entire value chain, within our social patronage, charity and sponsorship fields, we are committed to a zero-tolerance policy when it comes to corruption & bribery. Fraud, including the falsification of records of financial or non-financial information, money-laundering and insider dealing are prohibited.

Corporate Loyalty

Mol Group acknowledges its responsibility to protect shareholder investments and provide long-term returns that can compete with those of other leading companies in the industry. To ensure this, avoiding conflicts of interest, the protection of the company's interests, assets, business secrets, intellectual property, and ensuring data security are key priorities.

Trustful Business Relations and Responsible Stakeholder Relations

MOL Group is committed to extend the spirit and practice of responsible and sustainable business along the entire value chain and strive to have business relations based on trust and responsible communication with our external stakeholders.

For further details, please refer to the full text of MOL Group's Code of Ethics and Business Conduct, available online (in 13 languages) and accessible across the entire Group. In adherence to internal protocols, all of MOL Group must be acquainted with the Code and undergo annual compulsory trainings to ensure comprehension and compliance, with ethics integrated into the annual training curriculum also for the Board of Directors and the Supervisory Board. In 2024, 98% of MOL Group employees successfully completed their Annual Ethics training. Additionally, the Board of Directors and the Supervisory Board received their required training during meetings.

MOL Group also has stringent expectations for its partners, including suppliers, service station operators, joint ventures, and sponsors, urging them to align with the principlesin MOL Group's Business Partner Code of Ethics. This commitment to ethical business practices extends throughout the supply chain, with partners expected to propagate and enforce these standards among their own network of suppliers, subcontractors, and associates. All supplier and sponsorship contracts contain reference to the **Business Partner Code of Ethics** or other requirements on ethics values. If norms of the MOL Group Business Partner Code of Ethics are permanently and substantially breached, MOL Group will terminate its business cooperation with the business partner concerned.

The highest process-based policy establishing MOL Group's governance framework to identify, report, and investigate concerns about unlawful behaviour or violations of its **Code of Ethics and Business Conduct** is the **Security Area Book** (minimum disclosure requirements reported in section S1-B) in case of anti-fraud and internal investigation related issues**.** It defines fundamental rules and principles for anti-fraud and investigation services, ensuring consistency and control across the organization. MOL Group investigates business conduct incidents promptly, independently, and objectively, guided by a set of established principles

- **Clear Reporting Channels**: MOL Group provides accessible channels for employees to report concerns or violations, ensuring these mechanisms are widely communicated and understood across the organization. In order to ensure the lawful and ethical operation of MOL Group, the SpeakUp! whistleblower system has been established in 2006 to report violations of the Code, which are assessed by the Ethics Council. In case a report is identified to have relevance related to business misconducts, such as bribery or corruption, the case is forwarded to the Group Anti-Fraud & Investigation organizations to investigate. For further details, please refer to Section S1-3-C on Policies related to grievances and remediation.
- **Defined Responsibilities:** Group Anti-Fraud & Investigation organizations operate the system of internal investigations of MOL Group according to the annual fraud risk assessment plan acknowledged by senior management. Internal Investigation and Anti-fraud Teams conduct high priority, highly sensitive investigations as a group service to prevent and expose illegal criminal activities and protect the company from such. These establish, manage, supervise and operate MOL Group's Conflict of Interest investigation framework and directly control the investigation of local complex cases and risk assessments. Complex investigations can be started and closed only with the approval of the Group Security Director and tasks regarding the complex cases are delegated by him/her. Local (i.e. country or subsidiary level) Anti-Fraud & Investigation Teams run internal investigations and risk assessments to unfold abuses and offences on local level, and manage the process of complying with information request warrants arriving from law enforcement authorities in criminal proceedings and handles all contact with such authorities.
- **Unbiased and Independent Investigations**: Investigations must be conducted without bias. In cases of potential conflicts of interest, the Group Security Director and Country Security Manager are immediately informed. Investigators are required to maintain neutrality and professionalism throughout the process.
- **Proportionality and Due Diligence**: Investigation procedures are proportionate to the nature and scope of the suspected misconduct. Relevant evidence is collected systematically, ensuring both inculpatory and exculpatory information is documented in compliance with applicable legal and internal requirements.
- **Confidentiality & Data Protection**: All information related to reports and investigations is treated as confidential. The identity of whistleblowers and informants is safeguarded to the extent possible without compromising the integrity of the investigation. Investigation findings are shared only with individuals who have a legitimate need to know, in compliance with data protection laws. Personal data obtained during investigations is handled in compliance with the GDPR and other applicable regulations. Non-relevant information is promptly deleted, and all collected data is erased after the conclusion of the investigation.
- **Protection of Whistleblowers:** Employees who report concerns or refuse to participate in fraudulent or corrupt activities are protected from retaliation. MOL Group supports openness and guarantees that no adverse action, such as dismissal or disciplinary measures, will be taken against employees raising concerns in good faith, even if the concerns are ultimately unfounded.
- **Continuous Monitoring and Improvement:** Anti-Fraud & Investigation Teams regularly monitor, review investigation and anti-fraud procedures, ensuring those align with best practices and legal requirements.
- **Top-Level Commitment**: MOL Group's leadership actively supports the anti-fraud and investigation framework, fostering a culture of zero tolerance for misconduct and promoting ethical business practices. All country managing directors/chairmen – as part of their annual ethics related duties – have to report on the corruption-related risks of the given country they are working in and draw up relevant mitigation plans.

INCIDENTS OF CORRUPTION OR BRIBERY

/G1-4/

ESRS	Disclosure Requirement G1-4
GRI	GRI 3-3

	GRI 2-27 GRI 205-2 GRI 205-3

This section outlines MOL Group's actions to ensure fair business conduct practices, with a focus on anti-corruption and bribery, anti-competitive practices, and related events in 2024:

- 98% of MOL Group employees successfully completed the annual ethics training, which includes dedicated content on anti-corruption.
- MOL Group's Anti-Fraud Team issued quarterly Anti-Fraud newsletters, as a mass awareness tool which were distributed on company internal sites.
- No reported incidents of bribery, corruption, gifts, or hospitality were submitted through MOL Group's whistleblower reporting system, including INA Group.
- No employees were dismissed or disciplined for corruption-related offenses.
- No business partner contracts were terminated or not renewed due to corruption violations.
- No convictions were recorded for violations of anti-corruption or anti-bribery laws. In Germany, the Federal Antimonopoly Office initiated an ad-hoc sectoral assessment in which it requested information from MOL Germany regarding the wholesale petroleum trading market. As of the reporting date, no specific outcome has been reached. In Montenegro, the Agency for the Protection of Competition continued its investigation into an alleged violation of competition law (concerted practice) against INA – Crna Gora d.o.o.. MOL Group has challenged the agency's decision in court.
- No fine have been paid for violation of anti- bribery laws or anti-competitive business practices, nor did MOL Group incur any monetary losses as a result of legal proceedings associated with price fixing and/or price manipulation during 2024.

POLITICAL INFLUENCE AND LOBBYING ACTIVITIES

/G1-5/

ESRS	Disclosure Requirement G1-5
GRI	GRI 2-9-b GRI 415-1

Management oversight on political influence and lobbying activities

The framework for regulatory and public affairs activities is defined in the **Corporate Affairs Area Book**, with the Executive Vice President of Group Strategic Operations and Corporate Development serving as the process owner for implementation.

Standing reports are submitted to the management and supervisory bodies of MOL Group to ensure oversight of political influence and lobbying activities, including two reports per year to the Board of Directors on 'Political and Regulatory Environment Update and Outlook', one report per year to the Sustainable Development Committee of the Board on 'Future Outlook: Key Changes to External Regulatory Framework With Sustainable Development Focus and their Impact on MOL', and biennial reports to the Finance and Risk Management Committee of the Board as part of the Strategic Risk Review on 'Geopolitical And Regulatory Risks'.

Political contribution and lobbying activities

MOL Group aims to foster transparent relationships with governmental and EU officials, as well as external stakeholders, while ensuring compliance with all applicable local legislation and adherence to ethical standards. MOL Group's **Code of Ethics and Business Conduct** explicitly prohibits engagement in political activities or pursuing political agendas. It does not sponsor, donate, or support political programs, parties, or any organizations or events affiliated with them. Employees are free to participate in political activities in a personal capacity, provided these activities are not conducted in MOL Group's name or conflict with the company's interests.

These commitments are incorporated into internal policies as well. MOL Group's **Managing Corporate Giving Activities (Sponsorships, Donations, and Social Investments)** policy prohibits supporting political goals, parties, religious organizations, or any entities that violate human rights, public morals, or represent discriminatory opinions.

In alignment with these principles, MOL Group did not make any direct or in-kind political contributions in 2024.

Recognizing the risks and opportunities associated with regulatory and political changes, MOL Group actively monitors and analyses regulatory initiatives and political developments across its countries of operation. The company engages with EU institutions, national parliaments, governments, and municipalities to support compliance, mitigate risks, and capitalize on opportunities. Key topics MOL Group addressed through advocacy activities in 2024 (based on the EU Transparency Register) include:

- Banking and financial services
- Business and industry
- Climate action
- Competition
- Consumers
- Customs
- Economy, finance, and the euro
- Employment and social affairs
- Energy
- Environment
- International cooperation and development
- Research and innovation
- Single market
- Taxation
- Trade
- Trans-European Networks
- Transport

In terms of the main topics covered by advocacy, MOL Group actively supports EU and national regulations aimed at achieving climate-related targets, reducing CO2 emissions, and promoting renewable energy generation. We recognize the critical role of industrial transformation in meeting the EU's ambitious climate goals and are committed to contributing to this process. In addition, we emphasize the importance of accounting for regional specificities to ensure fair and effective implementation across the Central and Eastern European (CEE) region.

Regarding the EU Fit for 55 package, MOL Group fully supports its overarching climate objectives, including the EU Emissions Trading System, the Carbon Border Adjustment Mechanism, the Renewable Energy Directive, and the Energy Efficiency Directive. We believe achieving these goals requires massive investments in new technologies, supported by smart, technology-inclusive policies that create positive business cases for such investments. Our focus is on ensuring that national implementation of these directives reflects the unique circumstances and capabilities of the CEE region, enabling industry competitiveness while driving sustainability. Specifically, we advocate for the inclusion of all low-carbon technologies, greater flexibility, and a phased approach to compliance. Key areas of our efforts include creating regulatory conditions for hydrogen and biomethane adoption in transport and promoting energy savings through a broad range of technologies.

MOL Group also welcomes regulations that support carbon capture and storage (CCS) and carbon capture and utilisation (CCU), including initiatives under the Net-Zero Industry Act. We view CCS as a critical technology for achieving the EU's 2030 and 2050 emission reduction targets and support its inclusion among net-zero strategic projects. Our advocacy focuses on ensuring robust and nuanced regulations that address the complexities of the entire CCS value chain—from capture to transmission and storage. By promoting positive incentivizing measures, we aim to establish viable, sustainable business cases while considering the regional limitations of landlocked countries and their unique contributions to climate goals.

To optimise its advocacy capabilities, MOL Group actively participates in numerous trade, industry, and professional associations across the European Union. All participation is coordinated by the **Regulatory and Public Affairs department** and adheres to strict ethical standards. In 2024, MOL Group's total spending on membership fees for EU, international, and national associations amounted to USD 1 691 294, with the following breakdown:

1. **National Associations**: USD 626 669, covering topics such as employer rights, product categories (chemicals, fuels), transport, infrastructure, and energy efficiency.
2. **EU and International Associations**: USD 202 128, covering associations within the oil & gas and petrochemical industries, addressing topics such as decarbonization, low-carbon fuels, and chemical products.
3. **EU Policy Associations**: USD 862 497, covering memberships in organizations such as **FuelsEurope and Concawe**, **CEFIC**, and **IOGP**, addressing issues related to the European Green Deal, sustainable finance, renewable energy, emissions trading, and circular economy. MOL Group actively participates in shaping the agenda of these organisations, and has a high degree of consistency with their positions:
    1. **FuelsEurope**: Supports the European Green Deal, promoting climate neutrality, carbon pricing, and policies that create market demand for low-carbon liquid fuels.
    2. **IOGP**: Advocates for the Paris Agreement and European Green Deal, focusing on methane emissions reduction, platform electrification, renewable energy integration, and policies for carbon capture and storage (CCS) and blue hydrogen.
    3. **CEFIC**: Supports climate neutrality by 2050 and aims to enable a resource-efficient chemical sector. Key initiatives include bio-based and circular solutions, chemical recycling, and climate-neutral product markets.

MOL Group is also registered in the **EU Transparency Register** (REG number: 08569166274-90).

Board members holding position in public administration

In 2024, no new member of the Board of Directors or member of Supervisory Board has been appointed. Currently there is one member in the mentioned boards who is, or has in the last 2 years held position in public administration: Norbert Izer has been serving as a member of the Supervisory Board and the Audit Committee of MOL Group since July 15, 2022. Prior to this appointment, since May 2018, and during 2024, he has been leading the State Secretariat for Taxation within the Ministry of Finance.

Mandatory chamber memberships

In Hungary each economic operator is mandated to register at the chamber of commerce and industry. In line with that, MOL Plc. is registered at the Hungarian Chamber of Commerce and Industry, although as the term suggests, this must not be interpreted as a membership in its original sense.

MOL Plc. is a mandatory member of the Hungarian Chamber of Agriculture, Food Economics and Rural Development. Membership is mandated by the law due to catering services offered at service stations.

SUB-CHAPTER B: SUPPLY CHAIN MANAGEMENT

ESRS	Disclosure Requirement G1-2
GRI	GRI 204-1.1 GRI 3-3 GRI 308-1 GRI 414-1

IMPACTS ON SUPPLIERS

/G1. IRO-1/

Table IM-09: Key regional business partnerships

Severity	Significant, actual impact
Scope	Regional impact (primarily in Central-Eastern Europe)
Likelihood	Actual impact
Description	MOL Group is a major company in the CEE region, therefore a key buyer of products and services of regional companies. This, on one hand, provides secure income for many other companies. On the other hand, many companies (including SMEs) are reliant on the financial performance of MOL Group thus making them potentially exposed.
Actions	MOL Group's mitigation actions to reduce the risk of losing or negatively impacting business partners include conducting regular surveys with B2B customers to strengthen relationships and address any issues that may arise, and ensuring business continuity.
Time horizons	We consider the matter material on all time horizons.
Relevance in the value chain	The impact is relevant in all of MOL Group's value chains.

POLICIES RELATED TO RELATIONSHIPS WITH SUPPLIERS

/G1-2/

MOL Group Procurement is a functional organization that helps MOL Group to achieve its business objectives. It manages a comprehensive supplier base worldwide, including international and local suppliers based on the subject and scope of the procurement procedure. MOL Group contracts with local suppliers whenever it is beneficial, which can be a way of establishing a positive relationship with local communities (IM-09). Local suppliers are promoted since logistics related cost are always taken into consideration during the procurement process. In case of services related to MOL Group locations worldwide, the local presence of international supplies is also considered.

MOL Group Procurement aims to ensure transparency on Group level, treat suppliers equally and fairly, practice integrity and prevent conflicts of interest. Furthermore, the organization ensures that the non-HC purchased products and services are in compliance with relevant policies, laws and regulations and establish sustainable supply chain by integrating sustainability in its procurement processes.

MOL Group has set up the framework of Supplier Lifecycle Management, which consists of four pillars:

i) Supplier Qualification
ii) Supplier Evaluation & Selection
iii) Supplier Performance Evaluation
iv) Supplier Relationship Management

MOL Group has developed further cooperation with suppliers in order to facilitate MOL Group efforts related to sustainable development, including the preparation of a standard criteria system for activities with risk exposure. Sustainability strategies, targets and actions are being incorporated in the category management and supplier relationship management framework as laid out on **MOL Group's Code of Responsible Procurement**.

During 2024, the inbound supply chain CO2 assessment further improved, and supplier engagement program continued with hotspot suppliers. In order to accelerate Sustainable development and decarbonization in the supply chain, Group Procurement organized its Supplier Innovation Day in February 2024. Suppliers had the opportunity to get insight into MOL Group's strategy and challenges. Procurement organization also held its compulsory yearly Sustainability training where procurement professionals have been updated with new legislation and standards and new processes related to Sustainability. Furthermore, Procurement Excellence team organized its first ProcX Day where different sessions and workshops were organized to learn more about current processes and regulations related to sustainability, procurement and skill development.

MOL Group processes are compliant with ISO 50001:2018 requirements (energy management system), these are also applied when dealing with procurement of production materials/assets. Total cost of ownership (TCO, cost during the life-cycle) is part of the evaluation framework, where energy effective solutions are promoted. The origin of the given asset/material is also taken into account during the supplier selection procedure. MOL Group is only concluding contracts with suppliers that have been pre-screened from financial, legal and sustainability, and pre-qualified from HSE aspect. MOL Group is committed to be business partner of suppliers with ethical attitude, thus potential suppliers are also subject of ethical pre-screening (i.e. Illicit employment practices, money laundering activities, terrorist financing, bribery, corruption etc. are reasons for disqualification). Sourcing procedures are managed and controlled via a group-wide used system, which ensures transparency and fair competition of such supplier base. Official communication channels are always set up to enable traceability. Suppliers are also subject to regular post evaluation, and the results serve as a basis to the future cooperation between the parties. MOL Group has built up strong strategic relationships in defined procurement areas ensuring operational stability and long-term cooperation.

Business Partner Code of Ethics is a mandatory element of supplier contracts. Procurement organization also operates a blacklisting process that seeks to prevent MOL Group Companies from doing business with persons, businesses, organizations or entities who abuse the supply chain management system by committing a corrupt, fraudulent, unfair or irregular practice, or default on any contract wilfully or negligently, or the country/region where they operate became sanctioned. The blacklisting is based on the Performance Evaluation, and on continuous monitoring of watchlists, such as Sanctions lists, Political Exposure lists, Police Orders, Negative news. In 2024, Group Procurement updated its supply chain sustainability risk assessment process and identified high risk suppliers based on environmental and social issues. Suppliers' feedback are analysed centrally and corrective actions are defined in order to eliminate or mitigate environmental and social risk. In case of medium or high HSE risk, the supplier is subject to further examination or audit.

METRICS RELATED TO PAYMENT PRACTICES

/G1-6/

There is no unified standard payment target applicable for all MOL Group entities. However, the most commonly used standard payment term is 60 days – therefore we disclose the average time to pay an invoice from reception of invoice compared to this 60 days for all supplier categories. In 2024, 84% of invoices were paid within this timeframe. The average time to pay an invoice from its reception was 40 days. This figure was derived using a representative sampling methodology, covering entities accounting for approximately 70% of total consolidated net revenue. Payments were selected based on invoices where both the document date and payment date fell between January 1, 2024, and December 31, 2024. From this dataset, the days until payment metric was calculated and averaged, yielding the final result.

As of the reporting date, no legal proceedings related to late payments are outstanding. The company ensures that payments are made on or by the due date, aligning with contractual obligations and maintaining predictable cash flow management for suppliers.

SUB-CHAPTER C: DATA PROTECTION & CYBER SECURITY

IMPACTS AND RISKS RELATED TO DATA PROTECTION AND CYBER SECURITY ON SUPPLIERS

/entity-specific/

Cyber Security Risk is one of the 11 strategic risks identified by MOL Group. Annual risk review of the Enterprise Risk Management System (ERM) includes Cyber Security related risk assessment, with the involvement of MOL Group's Cyber Defence Centre.

Albeit not covered in the ESRS topic list during our 2024 Double Materiality Assessment, we have identified 1 impact and 1 risk related to Cyber security and Data Protection, as specified below:

IM-10: Risk of data exposure

Severity	Moderate, potential negative impact
Scope	Global
Likelihood	Low
Description	During its operations, MOL Group collects business and personal information related to employees, business partners, customers and other stakeholders for business purposes. MOL Group has strict procedures on data protection, handling and storing to ensure compliance with personal data regulations (e.g., GDPR) and prevent the abuse in relation to business sensitive information or trade secret regulations. However, the risk of a cyber-attack, IT security breaches, or misconduct by people accessing the data cannot be fully ruled out, which could lead to exposure of personal and or/business information.
Mitigation actions & remendability	Mitigation actions include implementing robust cyber security management practices and providing mandatory training for employees on proper data handling procedures. These actions are designed to protect sensitive information and ensure that staff are well-informed about best practices for data security. The remendability of the impact depends on the scale and nature of potential incidents – if data belongs to natural persons, it is considered an irremediable effect.
Time horizons	We consider potential impact material on all time horizons.
Relevance in the value chain	We consider potential impact material in relation to all of our value chains.

Table RK-11: Risk of information & cyber security incidents

Type	Operational
Likelihood	Low
Magnitude of financial effect	Medium
Description	Global trends are showing steadily growing frequency and intensity of Cyber-attacks / incidents. AI is a new global threat which is widely used by attackers as well as more specified Cyber Crime Groups targeting Industrial Control System's weaknesses, which may have increasing economic impact and relevance on MOL Group.
Related impact & dependencies	Since MOL Group handles the data on suppliers, consumers and other business partners, potential cyber attack against the company might affect those parties as well – see impact on Risk of data exposure (IM-10) for reference.
Mitigation actions	MOL Group has a well-developed cyber security system. To mitigate risks, the company is determined on the continuous improvement of cyber security capabilities, continuous supervision of cyber security risks, education of employees and partners, ensuring the protection of the confidentiality, integrity and availability of data. Cyber security is built into all of MOL Group products and services.
Financial effect & time horizons	Financial effect of the risk (including indirect effects) is difficult to be quantified, but the topic is considered material due to the severity of potential risks regardless of the likelihood, on all time horizons.

POLICIES ON DATA PROTECTION & CYBER SECURITY

/entitiy-specific/

GRI	GRI 418-1

Data Protection

As outlined in the Code of Ethics and Business Conduct, the protection of personal data is of paramount importance to MOL Group (IM-10). MOL Group is committed to conducting its business in full compliance with applicable data protection laws and regulations, particularly the General Data Protection Regulation (GDPR), while adhering to the highest standards of ethical conduct.

Through robust information technology solutions and regulatory frameworks, MOL Group ensures the confidentiality, integrity, and availability of electronically stored data throughout its lifecycle, encompassing storage, processing, and transfer. This commitment is underpinned by procedures and responsibilities described in the **Processing Personal Data at MOL Group** process description. These procedures are in accordance with Regulation (EU) 2016/679 of the European Parliament and of the Council of 27 April 2016 on the protection of natural persons with regard to the processing of personal data and on the free movement of such data, and repealing Directive 95/46/EC (General Data Protection Regulation, GDPR). This regulation lays down the rules on the processing of personal data and the related rights and obligations. All MOL Group-controlled entities operating within the matrix structure are responsible for ensuring compliance with applicable data protection requirements when processing personal data. The key elements of MOL Group's data protection framework include:

- **Information Security Training:** All personnel involved in the management, usage, or operation of MOL Group's IT infrastructure are required to regularly participate in information security awareness training.
- **Access Control:** Access to information infrastructure is granted exclusively to authenticated and authorized users based on the "need-to-know" principle.
- **Data Ownership:** Computer hardware, software, and all information stored on MOL Group's digital systems, including any MOL Group information on external or non-MOL Group systems, are considered company property.
- **Internet Usage Policy:** Limited non-work-related internet use is permitted, provided it does not compromise system or network security, performance, or stability, and does not interfere with professional responsibilities.
- **Data Monitoring:** To ensure security and compliance, MOL Group reserves the right to access and monitor devices and data stored therein, in accordance with privacy and data protection laws, for maintenance or to meet business or legal requirements.
- **Data Breach Management System:** The Archer system serves as MOL Group's platform for managing data breaches. Incidents are reported, investigated, and assessed in collaboration with relevant partner departments.
- **Incident Assessment:** Each data breach incident is evaluated by the Legal, Compliance, and Cybersecurity teams, with final approval provided by the Data Protection Officer.
- **Reporting of Data Breaches:** Suspected data breaches must be reported promptly through the *Data Breach Submission Form* or via email at databreach@mol.hu upon detection.

Cyber Security

MOL Group operates National Critical Infrastructure in Hungary, Slovakia, Croatia, Romania, Austria and Poland, therefore it is subject to regular mandatory external audits under local Cyber Security acts and NIS1 (NIS EU 2016/1148) and NIS2 (NIS2 EU 2022/2555) EU directives. To mitigate the risks associated with cyber crime and misconduct, MOL Group operates a well-established cyber security management framework (RK-11). The highest process-based policy establishing processes, basic rules and requirements related to Cyber Security in MOL Group is the **Cyber Security Area Book**. It includes main tasks and responsibilities of the Chief Information Security Officer and the Cyber Defence Centre. Key elements of the cyber security framework include:

- **Incident Management Policy and Procedure:** A comprehensive incident response process is in place, which includes continuous monitoring of security events, triaging alerts from various sources, and maintaining defined and documented use cases for incident management.
- **Awareness and Preparedness:** Regular exercises are conducted as part of the Cyber Security Awareness Programme and Cyber Security Strategy to address risks related to cyberattacks and improve organizational readiness.
- **Disaster Recovery Policy:** A robust disaster recovery policy and procedure ensure business continuity during disruptive events.
- **Operational Technology and Industrial Control Systems:** Specific initiatives address cyber security risks related to operational technology and industrial control systems.
- **Emergency Programme and Strategy:**
  A dedicated emergency programme and strategy provide preparedness and guidance for handling cyber security incidents.
- **Collaboration with Government Agencies:** Cyber security-related information is shared with relevant government agencies to strengthen collective defense efforts.
- **Threat Monitoring:** Cyber security threats are monitored on an ongoing basis to enable proactive risk identification and mitigation.
- **Internal Assessments and Audits:** Regular internal cyber security assessments, including Procurement Security Assurance and Design Security Assurance, are performed to enhance system resilience and mitigate potential vulnerabilities.

Expectations towards business partners

MOL Group is committed to fostering data protection and cyber security throughout its value chain. Therefore, all contracts with any type of contract contain reference to the **Business Partner Code of Ethics**, expecting alignment with the following principles:

- **Privacy**: Partners shall respect people's privacy and comply with personal data protection laws; only acquire and keep personal information that is necessary and provide adequate information to data owners in compliance with the law. MOL Group business partners shall adopt proper security measures to assure confidentiality, integrity and availability of information.
- **Information security**: Partners are expected to handle information related to other business partners as confidential, in accordance with the applicable confidentiality provisions. Business partners shall adopt proper security measures to assure confidentiality, integrity and availability of information. Business partners shall respect that valuable, confidential ideas, strategies and other types of business information created or developed at MOL Group represent company property, and in certain cases they are under the protection of intellectual property law.

ACTIONS RELATED TO DATA PROTECTION & CYBER SECURITY

/entitiy-specific/

In 2024 there was no major incident in MOL Group, due to continuous hardening activities that are extended into 2025.

In general, a major issue was the prevalence of AI assisted scams and attacks for MOL Group in 2024. It is a region-specific issue, since cyber-crime elements can leverage this new technology for attacking supply chains and the populace of Europe. In case of MOL Group the cyber criminals were using AI assisted phishing campaigns - however after the relevant email protection hardening efforts - these attacks were mitigated and could not reach most users; any other attempts were remediated.

AI as an emerging threat is present in scams - these appeared at the end of 2023 and continued to be an issue during the whole year on the mainstream social media platforms. Cyber criminals used available marketing materials and videos to fabricate a series of scams, which were targeted against the general populace. The scams were targeted using CTI platform and OSINT investigations, which resulted in swift "takedowns" of malicious content.

With the aim of enhancing employee awareness and knowledge about cybersecurity risks and best practices, MOL Group organized the Cyber Security Awareness Days on 19–20 November 2024. The event featured interactive sessions, expert talks, and practical guidance on protecting sensitive information and mitigating cyber threats, reinforcing MOL Group's commitment to maintaining a robust cybersecurity culture.

TARGETS AND METRICS RELATED TO CYBER SECURITY

/entitiy-specific/

MOL Group is committed to ensuring full compliance with all applicable data protection regulations when processing personal or sensitive information. The company's objective is to prevent any instances of data breaches or cybersecurity incidents. While MOL Group actively monitors and manages these risks, specific KPIs and time-bound targets in this area are currently not publicly disclosed.

Data protection

There was a total of 34 substantiated complaints received concerning breaches of customer privacy in 2024. The majority of the incidents were breach of confidentiality with 3 breaches of integrity. None of the incidents were reported to The National Authority for Data Protection and Freedom of Information (NAIH) in 2024.

Cyber Security

In 2024 there were no major incidents in MOL Group, due to continuous hardening activities and awareness campaigns that are extended into 2025.

EXCLUDED DISCLOSURES

Topic	Relevant IDs	Explanation
Animal welfare	G1-1_09	Animal welfare is not considered a material topic
Functions-at-risk of corruption and bribery	G1-1_11 G1-3_07	MOL Group's antifraud and anticorruption practices cover all functions without distinct areas. Therefore, functions-at-risk is not an applicable category.
Connection of investigation committee to administrative, management and supervisory bodies	G1-3_02 G1-3_03	Not specified in policies

Appendix I: Indicators under reasonable assurance

MOL Group has obtained external assurance on its sustainability report under limited assurance, and reasonable assurance on two selected indicators: CO2 emissions under the EU Emissions Trading System (EU ETS) and Total Recordable Injury Rate (TRIR) of MOL Group (excluding FGSZ Zrt., since the Midstream entity is unbundled from other MOL Group operations). In order to ensure continuity and comparability with MOL Group's sustainability reporting practices before the implementation of the requirements of the European Sustainability Reporting Standards (ESRS), the two metrics are also reported separately in this section. The below metrics were prepared in accordance with the revised Global Reporting Initiative (GRI) Standards.

CO2 Emissions under EU ETS

The CO2 emissions regulated under the EU ETS are critical for MOL Group as they directly impact the company's environmental footprint and compliance with climate regulations. Monitoring and managing these emissions help MOL Group contribute to global efforts in mitigating climate change and align with the ESRS E1-5 (paragraph 45 a.) disclosure requirements (equivalent to GRI 305-1), which aim to provide an understanding of the direct impacts of the undertaking on climate change.

	UNIT OF MEASURE	2024	2023	GRI
CO_2 emissions under EU ETS	mn tonnes CO_2-eq	5.66	5.81	305-1

Total Recordable Injury Rate (TRIR)

TRIR is a key indicator of workplace safety and reflects MOL Group's commitment to ensuring a safe working environment for its employees and contractors. This metric is essential for assessing the effectiveness of safety measures and fostering a culture of safety within the organization. The ESRS S1-14 (paragraph 88 c.) disclosure requirements emphasize the importance of reporting work-related accidents to provide transparency on workforce safety.

	UNIT OF MEASURE	2024	2023	GRI
Total Recordable Injury Rate (TRIR)	cases/mn working hr	1.04	1.31	403-9
o/w Own staff	cases/mn working hr	1.64	1.91	403-9
o/w Contractors	cases/mn working hr	0.54	0.81	403-9

The auditor's reasonable assurance opinion can be found at the end of this sustainability statement.

Appendix II: Management system & policies

Sustainability Report Appendix: Management system & policies

MOL Group consists of more than 200 companies, operating in more than 30 countries. To ensure achieving our long-term strategic goals while meeting the needs of stakeholders, our corporate governance is built on common, integrated operation to member companies to be part of MOL Group. Every company belonging to MOL Group Portfolio is assigned to relevant company group from governance point-of-view, based on:

- MOL Group ability to enforce its interests (ownership / management rights),
- MOL Group strategic objectives related to a given company,
- desired level of integration into MOL Group operation,
- activity characteristics, size, complexity and financial status.

Companies within MOL Group's portfolio are categorized in MOL Portfolio Database based on control rights, size, core business, type of operations (matrix, agile, entrepreneurial, non-matrix).

To ensure that all processes are harmonized at the MOL Group level, controls, processes and rules are described in regulations and implemented across the Group. All internal regulations are made available to all employees of MOL Group through the e-REG system.

MOL Group's corporate governance is built on the Main Governance documents:

- **Operational and Organisational Rules** serves as a basis for all other governance and operational rules. It defines the general Corporate Governance framework for the Group.
- **Descriptions of Tasks & Responsibilities** defines the setup of MOL Group organisations and the descriptions of its tasks and responsibilities.
- **Lists of Decision-making Authorities** defines who is responsible for internal decision-making to ensure transparent decision-making processes.
- **Area Books** are tools of Group level business or functional Process Owners to direct and control the operations of their respective areas at a high level. They are structured by business lines (Areas) rather than geographic scope. Area Books are the highest-level process-based regulations, focusing on end-to-end processes describing the operation model of their specific Area to be implemented across all MOL Group companies.
- **Process Descriptions** implement rules across organisational boundaries to ensure efficient processes and legal compliance. They regulate the processes listed in Area Books by defining processes which affect one or more Areas across multiple companies.
- **Methodology Instructions** help standardize operations by issuing a common methodology for performing specific tasks related to one or more Areas across multiple companies.

MOL Group is committed to implementing the best standards of corporate governance structures and practices geared towards shareholders' interests, while also considering the interests of a broader group of stakeholders. This approach is essential for enhancing the value generated for MOL Group's shareholders and people, as stated in the Operational and Organisational Rules. This policy aims to ensure that the interests of key stakeholders are considered when setting any policy integrated into MOL Group's governance system. However, detailed information on the assessment of stakeholders' interests and the considerations applied are not mandatory elements of the policy document and, therefore, cannot be disclosed for each individual policy referenced in the report (in reference to covering MDR-P_05).

Minimum disclosure requirements policies referenced in the Sustainability Report /MDR-P/:

Policy title	Key content /MDR-P_01/	Scope & exclusions /MDR-P_02/	Accountable for implementation /MDR-P_03/	Third-party standards or initiatives /MDR-P_04/	Availability /MDR-P_06/
Circular Economy Services Area Book	Defines the principles and requirements for the CES business segment. Main objectives: coordinate circular economy activities; waste management along the value chain; synergies with core businesses; implementing advanced waste management technologies to achieve strategic corporate targets in line with domestic and EU legislation.	MOL Plc. and controlled operative subsidiaries involved into matrix operation.	Head of Circular Economy Services (Process Owner)	-	Available internally to all employees via e-REG
MOL Group Code of Ethics and Business Conduct	Details MOL Group's commitment to ethical business conduct, including introduces the principles, behaviours and conduct that are necessary to create an ethical culture and operation in compliance with all laws and internal regulations.	All managers and employees of MOL Plc. and all business enterprises controlled directly or indirectly by MOL Plc.	Signed by top management, with main responsibility held by MOL Group Ethics Council	International Bill of Human Rights, European Convention on Human Rights, International Labour Organisation's Declaration on Fundamental Principles and Rights at Work, UN Guiding Principles on Business and Human Rights, OECD Guidelines for Multinational Enterprises, United Nations Global Compact, Modern Slavery Act 2015, UK Bribery Act 2010, U.S. Foreign Corrupt Practices Act, Partnering Against Corruption Initiative Global Principles for Countering Corruption, Act CLXV	Publicly available on MOL Group's website.

Policy title	Key content /MDR-P_01/	Scope & exclusions /MDR-P_02/	Accountable for implementation /MDR-P_03/	Third-party standards or initiatives /MDR-P_04/	Availability /MDR-P_06/
				of 2013 of Hungary on Complaints and Public Interest Disclosure	
Community Engagement Methodology	Guidance to site-level managers on how to plan and implement successful community engagement activities, the results of which should become integral parts of the general action planning process.	MOL Group - general	Vice President Corporate Communications and Marketing	AA1000SES:2015 Stakeholder Engagement Standard	Publicly available on MOL Group's website.
Corporate Affairs Area Book	Defines basic rules and requirements to establish the framework of MOL Group's activities with respect to regulatory and public affairs.	MOL Plc. and controlled operative subsidiaries involved into matrix operation	Group Strategic Operations and Corporate Development	-	Available internally to all employees via e-REG
Cyber Security Area Book	Defines the processes, basic rules and requirements established within MOL Group's Cyber Security.	MOL Group	Head of Information Security	-	Available internally to all employees via e-REG
Diversity & Inclusion Process Description	Ensuring that upholding Diversity & Inclusion standards is a common responsibility throughout MOL Group.	MOL Plc. and controlled, operative subsidiaries involved into matrix operation	Group HR Vice President	-	Available internally to all employees via e-REG
Downstream Development Area Book	Setting the direction for the Downstream business by developing business strategy and roadmap and description of how this is done through core processes.	MOL Plc. and controlled operative subsidiaries involved into matrix operation	Group Downstream Production and Development Senior Vice President	-	Available internally to all employees via e-REG
Downstream Production Area Book	The aim of this Area Book (hereinafter AB) is to define basic principles and processes about the operation of Downstream Production to show direction to the Production sites, cross functional units, and relevant stakeholders. The main objective of Downstream Production is to create value for our customers via converting raw materials to high quality products on safe, sustainable, reliable and efficient way.	MOL Plc. and controlled operative subsidiaries involved into matrix operation	Group Downstream Development Senior Vice President	-	Available internally to all employees via e-REG
Downstream Tactical Planning and Margin Management	Defining how to set short term targets for MOL Group's Downstream business segment.	MOL Plc. and controlled operative subsidiaries involved into matrix operation	Group Downstream Value chain management senior vice president	-	Available internally to all employees via e-REG
Energy Policy	MOL Plc.'s commitment to continuously improve the efficiency of our energy use, to increases competitiveness and helps to preserve the environment.	MOL Plc.	Signed by: CEO, Deputy CEO, Managing Director	Aligns with ISO 50001 (Energy Management Systems)	Publicly available on MOL Group's website and communicated internally through

Policy title	Key content /MDR-P_01/	Scope & exclusions /MDR-P_02/	Accountable for implementation /MDR-P_03/	Third-party standards or initiatives /MDR-P_04/	Availability /MDR-P_06/
					employee training, operational guidelines, and corporate initiatives.
Group HSE and Social Impact Policy	Declaring MOL Group's public commitment to acting responsibly regarding the health, safety, environmental and social impacts of our daily operations.	General, applicable to MOL Group and its contractors	Signed by Chairman & GCEO. All of our employees and contractors have a responsibility to maintain high HSE standards and management must take a leadership role in this. Accountability for implementing the policy lies primarily with the top management, local CEOs or Managing Directors, supported by the Group HSE Senior Vice President and local HSE Managers.	-	Publicly available on MOL Group website and communicated internally through employee training and operational management. Contractors and suppliers are informed via compliance requirements, ensuring broad awareness and implementation across the value chain.
Group level People Strategy	Sets the key principles related to Human Resource management within MOL Group.	MOL Group	Group HR Vice President	-	Presented to MOL Group top management and Supervisory Board whenever updated (latest update: June 2024)
Health Safety and Environment Area Book	Highest level process-based regulation in the field of HSE management, focusing on end-to-end processes describing the operation model	MOL Plc. and controlled operative subsidiaries involved into matrix operation	HSE Senior Vice President (Process Owner)	-	Available internally to all employees via e-REG.
Health Safety and Environment Management System	The main goal of this regulation is to define the Health, Safety and Environment requirements in MOL Group in order to support the execution of the business strategic objectives.	MOL Plc. and controlled operative	HSE Senior Vice President (Process Owner), and local	ISO 14001 for environmental management, OHSAS	Available internally to all employees via e-REG. Updates to

Policy title	Key content /MDR-P_01/	Scope & exclusions /MDR-P_02/	Accountable for implementation /MDR-P_03/	Third-party standards or initiatives /MDR-P_04/	Availability /MDR-P_06/
		subsidiaries involved into matrix operation	CEOs and local SD&HSE Managers.	18001 for occupational health and safety, AQUEDUCT Water Risk Atlas for the identification of water-risk areas, Management and Remediation of Sites in the Petroleum Industry (IPIECA), and Commission Decision 2000/532/EC regarding waste-handling.	KPIs and HSE indicators are communicated to relevant HSE contacts, ensuring stakeholders stay informed about performance metrics and continuous improvement initiatives.
HSE & Social Impact Policy	Lists MOL Group's commitments towards acting responsibly on the health, safety, environmental (HSE) and social impact of our activities as part of day-to-day business.	All employees and contractors have a responsibility to maintain high HSE standards and management must take a leadership role in this. We also aim to promote this policy in non-operated joint ventures.	Signed by top management.	-	Publicly available on MOL Group's website.
Human Resources Area Book	Defines and describes main HR processes, main rules and requirements and sets objective strategic goals, to ensure top quality HR services to the customers (employees and managers) across the MOL Group, compliant with local legal and market requirements.	MOL Plc. and controlled, operative subsidiaries involved into matrix operation.	HR Vice President	-	Available internally to all employees via e-REG
Integrated Management System of MOHU	States MOHU Plc.'s commitment to enhance waste management in Hungary, promoting a circular economy and sustainability, shifting	MOHU Plc.	CEO of MOHU Zrt.	ISO 9001 - Quality Management Systems; ISO 14001 -	Publicly available on MOHU's website (in Hungarian)

Policy title	Key content /MDR-P_01/	Scope & exclusions /MDR-P_02/	Accountable for implementation /MDR-P_03/	Third-party standards or initiatives /MDR-P_04/	Availability /MDR-P_06/
	societal views on waste, reducing pollution, and supporting carbon neutrality.			Environmental Management Systems; ISCC document on handling used cooking oil	
Manage Community Engagement and Grievances	Provides the principles and practices of community engagement and the process of identifying and involving stakeholders and the high-level process for handling incoming grievances from the public, communities and local authorities in order to achieve a Group-level integrated approach to community engagement and grievance management.	MOL Plc. and controlled, operative subsidiaries involved into matrix operation	Vice President Corporate Communications and Marketing	ISO 9001:2015, ISO 14001:2015, AA1000 Stakeholder Engagement Standard 2015, IPIECA: Community grievance mechanisms in the oil and gas industry	Available internally to all employees via e-REG
Managing Corporate Giving Activities Process Description	Defines Group level principles and processes related to sponsorship, donation and social investment activities in order to provide a comprehensive framework for the management of successful, efficient and transparent corporate giving activities within the company, highly supporting the achievement of MOL Group strategic objectives.	MOL Plc. and controlled, operative subsidiaries involved into matrix operation	Vice President Corporate Communications and Marketing	-	Available internally to all employees via e-REG
Mobility Area Book	Defines basic principles and requirements about the operation of Group Mobility for the related business units, subsidiaries and internal stakeholders. The main objective of the Group Mobility organization is to achieve its strategic target: to position MOL Group as an integrated, complex mobility service provider targeting customers both owning and not owning vehicles.	MOL Plc. and controlled, operative subsidiaries involved into matrix operation	Head of Group Mobility	-	Available internally to all employees via e-REG
MOL Group Operational and Organisational Rules	Defines general Operational & Organisational Rules to attain MOL Group strategic objectives and increase shareholder value.	MOL Plc. and those companies wherein on supreme body MOL Plc., directly or indirectly, bears more than 50 % of votes or where MOL Plc, directly or indirectly, exercises majority ownership or otherwise	Group Strategic Operations and Corporate Development Executive Vice President	-	Available internally to all employees via e-REG

Policy title	Key content /MDR-P_01/	Scope & exclusions /MDR-P_02/	Accountable for implementation /MDR-P_03/	Third-party standards or initiatives /MDR-P_04/	Availability /MDR-P_06/
		controlling rights based on a contract concluded with the other owner(s).			
Optimisation, Sales and New Businesses Area Book	Defines basic principles and requirements about the operation of Optimization, Sales, and New Businesses E2E Process that aims to connect Customers with Downstream capabilities to satisfy customer needs.	MOL Plc. and controlled operative subsidiaries involved into matrix operation	Group Downstream Executive Vice President	-	Available internally to all employees via e-REG
Process Safety Management Process Description	Defines the process safety management requirements in MOL Group in order to support the execution on of the business strategic objectives.	MOL Plc. and controlled, operative subsidiaries involved into matrix operation	Group HSE Vice President	-	Available internally to all employees via e-REG
Processing Personal Data at MOL Group process description	Ensures that the procedures of MOL Group companies are complying with the applicable laws regarding the protection of the personal data of the data subjects	MOL Plc. and controlled, operative subsidiaries involved into matrix operation.	Head of Group Legal & Compliance	Regulation (EU) 2016/679 of the European Parliament and of the Council of 27 April 2016; Directive 95/46/EC (General Data Protection Regulation, GDPR)	Available internally to all employees via e-REG
Renewables & Energy Efficiency Management Area Book	Defining basic rules and requirements to establish MOL Group's Renewables & Energy Efficiency Management Framework.	MOL Plc. and controlled European operative subsidiaries involved into matrix operation.	Head of Group Renewables	Energy Management System (ISO 50001)	Available internally to all employees via e-REG
Retail Area Book	Defines basic principles and requirements about the operation Group Retail in order to show direction to the business units and internal stakeholders. The main objective of the Group Retail organization is to maximize company value through understanding customer needs, increasing margin revenues, ensuring optimal store format portfolio and size and standardized high-quality delivery of customer experience	MOL Plc. and controlled, operative subsidiaries involved into matrix operation	Group Retail Senior Vice President	-	Available internally to all employees via e-REG
Security Area Book	Defines fundamental rules and basic requirements to establish, operate and continuously develop Security services at MOL Group. It contains a comprehensive set of principles for security governance,	MOL Plc. and controlled, operative	Group Security Director	SOLAC: Safety of Life At Sea Convention; ISPC: International	Available internally to all employees via e-REG

Policy title	Key content /MDR-P_01/	Scope & exclusions /MDR-P_02/	Accountable for implementation /MDR-P_03/	Third-party standards or initiatives /MDR-P_04/	Availability /MDR-P_06/
	security operations, technical security services, crisis & continuity management, travel security and anti-fraud & investigation related activities.	subsidiaries involved into matrix operation		Ship and Port facility Security	
Shape Tomorrow Strategy	Shape Tomorrow is MOL Group long-term integrated business and sustainability strategy.	MOL Group – in general	MOL Group's management as a whole	-	Publicly available on MOL Group's website.
Talent Management Process Description	Ensures harmonised and unified integrated Talent Management process across MOL Group, have unified Talent Management language, reach clarity over Talent roles, responsibilities and KPIs.	MOL Plc. and controlled, operative subsidiaries involved into matrix operation.	Group HR Vice President	-	Available internally to all employees via e-REG

ASSURANCE STATEMENT

The MOL Group sustainability report complies with the requirements of the European Sustainability Reporting Standards (ESRS) as adopted under the Corporate Sustainability Reporting Directive (CSRD).

MOL Group's sustainability auditor has provided:

- Limited assurance statement which covers the content of the sustainability statement,
- Reasonable assurance statement which covers two key indicators: CO_2 under ETS and TRIR for own workforce.

The assurance statements regarding the sustainability disclosures are provided as separate documents on MOL Group's website.